

ROBERT LAGA
Chairman

NICHOLAS FANNIN
Vice Chairman

RICHARD FRANZETTI, P.E.
Wetland Inspector

ROSE TROMBETTA
Secretary

TOWN OF CARMEL
ENVIRONMENTAL CONSERVATION BOARD



60 McAlpin Avenue
Mahopac, New York 10541
Tel. (845) 628-1500 - Ext. 190
www.ci.carmel.ny.us

BOARD MEMBERS

Edward Barnett
Anthony Federice
Emily Lavelle

ENVIRONMENTAL CONSERVATION BOARD AGENDA

APRIL 18, 2024 – 7:30 P.M.

EXTENSION OF WETLAND PERMIT

<u>APPLICANT</u>	<u>ADDRESS</u>	<u>TAX MAP #</u>	<u>COMMENTS</u>
1. NYCDEP West Branch Auxiliary Dam	34 Drewville Road	65.-1-5	Site Plan (Planning Board Referral)

SUBMISSION OF APPLICATION OR LETTER OF PERMISSION

2. Veolia (formerly Suez) Water Mahopac Wells	Behind 34 Coventry Circle	75.20-2-68	Upgrades to Existing Well Site
--	------------------------------	------------	--------------------------------



**Environmental
Protection**

Rohit T. Aggarwala
Commissioner

Ana Barrio
Deputy Commissioner
Bureau of Engineering
Design & Construction

Sean McAndrew, P.E.
Executive Director
Water System Capital
Program

16 Little Hollow Road
Grahamsville, NY 12740

Tel. (845) 334-7195
Fax (845) 985-2282
mcandrews@dep.nyc.gov

April 12, 2024

Town of Carmel
Environmental Conservation Board
60 McAlpin Avenue
Mahopac, NY 10541
Attn: Rose Trombetta

RE: New York City Department of Environmental Protection
Bureau of Engineering, Design and Construction
CRO-534: West Branch Reservoir Auxiliary Dam (Putnam County)
Slope Safety Improvements Project - Request to extend Wetland Permit

Dear Environmental Conservation Board Members,
The New York City Department of Environmental Protection (DEP) is requesting approval to extend the Wetland Permit for the referenced project at the West Branch Auxiliary Dam, Tax Map #65.-1-5, originally issued by the Environmental Conservation Board (ECB) on April 20, 2023.
The DEP is requesting to be added to the ECB's next available meeting agenda on April 18, 2024.

If you have any questions, please contact Linda Singh at 917-207-9477 or via e-mail at LindaSi@dep.nyc.gov.

Sincerely,

Arne Fareth, P.E.
Portfolio Manager

cc. L. Singh, DEP
I. Kennelty, DEP
S. Salzberg, DEP
E. LeClair, CDM Smith
M. Encinas, CDM Smith



ATZL, NASHER & ZIGLER P.C.

ENGINEERS - SURVEYORS - PLANNERS

Web: www.anzny.com

April 12, 2024

To: Mr. Robert Laga, Chairman
Town of Carmel Environmental Conservation Board (ECB)

Re: Site Plan update summary– Mahopac Wells 1, 2 & 3 (Behind 34 Coventry Circle,
Mahopac, NY 10541)

Cc: Ms. Rose Trombetta, Secretary

Dear Mr. Laga:

We wish to summarize the recent update to the Site Plan of the above referenced project which has been modified based on feedback received from your Board (ECB) during the March 21, 2024 meeting.


To eliminate any disturbance of the wetlands we have revised the Site Plan to incorporate a retaining wall on the west end of the proposed dry pond. The new design obviates the need to grade within or otherwise permanently disturb the wetlands. Therefore, wetland mitigation measures will no longer be necessary.

We respectfully request the ECB to kindly accept and subsequently approve the wetlands permit application for this project, conditioned on the following:

1. Veolia North America (“Veolia”) will submit a landscape maintenance bond to the Town Clerk after Planning Board approval has been obtained. In the interim timeframe, Veolia will communicate with various Town departments in order to clarify any questions they may have about the same.
2. Veolia will submit any new correspondences from the NYSDEC and/or ACOE when these are received. It is understood that if there are any changes to existing permits granted by these agencies, additional review by the ECB may be necessary.

Thank you for your cooperation in this matter.

Very Truly Yours,


Ryan A. Nasher, P.E.
Vice President

HUNTERS RUN HOMEOWNERS ASSOCIATION, INC.

March 20, 2024

Hon. Robert Laga, Chairman, and
Members of the Town of Carmel Environmental Conservation Board
60 McAlpin Avenue
Mahopac New York 10541

RE: *Submission by the Hunters Run Homeowners Association, Inc., in Support of
the Amended Application by Veolia Water New York Inc. (Veolia) (formerly
SUEZ Water New York, Inc.), for Approval of the PFAS Treatment Facility*


Dear Chairman Laga and Members of the Board,

I am president of the Hunters Run Homeowners Association, Inc. (the "HOA"), and am writing on behalf of the HOA in support of the above-referenced application. As you are aware, Veolia Water New York Inc. (formerly SUEZ Water New York, Inc.), has applied for site plan approval and a conditional use permit to authorize a PFAS water treatment facility within its easement that encumbers property owned by the HOA. The HOA has reviewed the set of plans currently before the Planning Board, titled "Mahopac Wells 1, 2 & 3", prepared by Atzl, Nasher & Zigler P.C., last revised February 12, 2024, which will also be subject to your review, and urges your Board to take positive action with respect to them.

The HOA recognizes that the proposed project will advance the important objective of meeting state-imposed requirements for water treatment, serving both the public at large and the HOA's members, while not generating any significant impacts.

Respectfully submitted,

Hunters Run Homeowners Association, Inc.

By: 
Kenneth Schweigler, President

cc: Rose Trombetta (via electronic mail)

Note: Only the wetland boundary within the project study area has been validated. If any work occurs outside of this project area, that portion of the wetland will need to be validated.

NYSDEC FRESHWATER WETLAND BOUNDARY VALIDATION

The freshwater wetland boundary as represented on these plans accurately depicts the limits of Freshwater Wetland CF-1 as delineated by Steve C. Smith on April 20, 21.

DEC Staff: Steve Fleming 6/24/21 Surveyor/Engineer

Date Valid: 6/24/21 Expiration Date: 6/24/26 SEAL 

Wetland boundary delineations as validated by the New York State Department of Environmental Conservation remain valid for five (5) years unless existing exempt activities, area hydrology, or land use practices change (e.g., agricultural to residential). After five (5) years the boundary must be revalidated by DEC staff. Revalidation may include a new delineation and survey of the wetland boundary.

Any proposed construction, grading, filling, excavating, clearing or other regulated activity in the freshwater wetland or within 100 feet of the wetland boundary as depicted on this plan requires a permit from the NYS Department of Environmental Conservation under Article 24 of the Environmental Conservation Law (Freshwater Wetlands Act) prior to commencement of work.



NYSDEC DELINEATED FRESHWATER WETLAND MAP

SUEZ Water New York, Inc.
PFAS Compliance Project H - Mahopac Well

Town of Carmel,
Putnam County, NY

- Legend**
- Action Area
 - Project Study Area
 - Test Pits
 - Flag Locations
 - Stream
 - Wetland Boundary
 - NYSDEC Freshwater Wetland Buffer
 - Delineated Freshwater Wetland
 - PFO



N



Gannett Fleming

SCALE: 1 in = 175 ft

0 87.5 175 350
|-----|-----|-----|-----|
Feet

Data Source: Aerial Imagery provided by ArcGIS web services. Streams and wetlands delineated by Gannett Fleming, Spring 2021.

This SWPPP was prepared in accordance with SPDES Permit No. GP-0-20-001 and must be kept on the job site and available for use of contractors and sub-contractors. Certifications by applicant/developer and by the contractors/subcontractors are included. A copy of the Notice of Intent (NOI), which must be filed at least 5 days prior to the commencement of any work along with the MS4 SWPPP acceptance form, is included herein. Notice of Termination (NOT) must be filed when all stormwater management facilities are in place and the site has been stabilized with specified vegetation. Sample inspection forms are included. Operation and maintenance plan is attached and included both temporary and permanent facilities maintenance. This SWPPP, together with all required plans, completed inspection forms and log of activities including any mitigation of items noted on inspection forms must be kept on the job site and available for inspection by all regulatory authorities.

FULL STORMWATER POLLUTION PREVENTION PLAN (SWPPP) REPORT

Prepared For:

**Mahopac Wells 1, 2, & 3
Town of Carmel, Putnam County, New York**

Prepared By:




ATZL, NASHER & ZIGLER
Engineers – Surveyors – Planners
232 North Main Street
New City, New York 10956
Tel. (845) 634-4694 • Fax (845) 634-5543

This plan has been prepared to comply with the provisions of the SPDES general permit no. GP-0-20-001, issued by the New York State Department of Environmental Conservation for storm water discharges from construction site activities.

I certify under penalty of law that this document and all attachments were prepared and revised under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment of knowing violations.

Revision 4: April 09, 2024
Revision 3: January 19, 2024
Revision 2: May 02, 2022
Revision 1: September 30, 2021
Date: August 27, 2021
Job No. 4870



Ryan A. Nasher, P.E. License No.: 89066
New York State Professional Engineer

Table of Contents



TABLE OF CONTENTS

**SECTION 1: Stormwater Pollution Prevention Plan Report Complying
GP 0-20-001**

1.0 INTRODUCTION

- 1.1 NOTICE OF INTENT
- 1.2 SWPPP GOALS AND OBJECTIVES

2.0 SITE DESCRIPTION

- 2.1 Project Name & Location:
- 2.2 Owner/Operator Name & Address:
- 2.3 General Contractor*:
- 2.4 Description:
- 2.5 Impervious Cover:
- 2.6 Site Area:
- 2.7 Location Map
- 2.8 Sequence of Major Activities:

3.0 CONTROLS

- 3.1 EROSION AND SEDIMENT CONTROLS STABILIZATION PRACTICES
 - 3.1.1 Temporary Stabilization:
 - 3.1.2 Permanent Stabilization:
- 3.2 STRUCTURAL PRACTICES
- 3.3 STORMWATER MANAGEMENT WATER QUALITY
 - 3.3.1 Name of Receiving Waters:
- 3.4 PEAK FLOW ATTENUATION
- 3.5 RUNOFF CONVEYANCE SYSTEMS
- 3.6 OTHER CONTROLS
 - 3.6.1 Waste Materials:
 - 3.6.2 Hazardous waste:
 - 3.6.3 Sanitary Waste:
 - 3.6.4 Offsite Vehicle Tracking:
- 3.7 TIMING OF CONTROL MEASURES
- 3.8 CERTIFICATION OF COMPLIANCE WITH FEDERAL, STATE AND LOCAL REGULATIONS

4.0 MAINTENANCE & INSPECTION PROCEDURES

- 4.1 SEDIMENT & EROSION CONTROL INSPECTION AND MAINTENANCE PRACTICES
- 4.2 SUMMARY OF SWPPP REQUIRED DOCUMENT FILINGS

5.0 NON-STORM WATER DISCHARGES

- 5.1 NON-STORMWATER DISCHARGES

MAHOPAC WELLS 1, 2, & 3
Full Stormwater Pollution Prevention Plan Report

6.0 INVENTORY FOR POLLUTION PREVENTION PLAN

6.1 MATERIAL SUBSTANCES

7.0 SPILL CONTROL & PREVENTION

7.1 MATERIAL MANAGEMENT PRACTICES

7.1.1 Good Housekeeping:

7.1.2 Hazardous Products:

7.2 PRODUCT SPECIFIC PRACTICES

7.2.1 Petroleum Products:

7.2.2 Fertilizers:

7.2.3 Paints:

7.2.4 Concrete Trucks:

7.3 SPILL CONTROL PRACTICES

8.0 SUPPORTING PLANS & REPORTS

9.0 POLLUTION PREVENTION PLAN CERTIFICATION

9.1 OWNER/OPERATOR CERTIFICATION

10.0 CERTIFICATION BY CONTRACTORS

10.1 PRIME CONTRACTOR CERTIFICATION

10.2 SUB-CONTRACTOR CERTIFICATION

Figures

Figure 1: Site Location Map (source: maps.google.com)

Appendices

Appendix A – SWPPP CONSTRUCTION SITE LOG BOOK

Appendix B – STORMWATER POND CONSTRUCTION INSPECTION CHECKLIST FORM

Appendix C – SPILL CONTROL & PREVENTION LOG

Appendix D – STORMWATER MANAGEMENT FACILITIES MAINTENANCE AGREEMENT

Appendix E – CONSTRUCTION PLAN DRAWINGS IN (11" X 17")

**SECTION 2: Stormwater System Design Report Complying NYS
Stormwater Management Design Manual, January 2015.**

Hydraulic & Hydrological Study:

• Revision Overview	2-1
• Introduction	2-1
• Site Location	2-2
• Hydrological Soil Group	2-2
• Existing Watershed	2-2
• Developed Watersheds	2-2
• Drainage Study	2-2
• Mitigation	2-2

Summary Table:

• Summary Flow Table at P.O.I.#1	2-4
--	-----

Location Maps:

• Street Map	2-5
• Soil Map	2-6

Drainage Calculation

• Existing Condition	2-7
• Developed Condition	2-7

Stormwater Management Practice Design Calculations

• Water Quantity Calculation	2-8
• Stormwater Sizing Calculation	2-9

HydroCAD Model for Existing and Proposed Conditions 1, 10, & 100 Year Storms

• Drainage Schematic	2-11
• 1-Year Storm Model	2-12
• 10-Year Storm Model	2-18
• 100-Year Storm Model	2-24

SECTION 3: SPDES General Permit Per GP 0-20-001

- 3.1 SPDES ACKNOWLEDGEMENT LETTER ISSUED BY NYSDEC
- 3.2 FILED OUT NOTICE OF INTENT (N.O.I.)
- 3.3 MS4 SWPPP ACCEPTANCE FORM

APPENDIX-F:

• Infiltration Test Certification	A-1
---	-----

MAPS:

• Drainage Map Existing Condition	E-1
• Drainage Map Proposed Condition	P-1

Section 1: O, I & M

MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

SECTION 1: OPERATION INSPECTION AND MAINTENANCE PLAN REPORT

BY

ATZL, NASHER & ZIGLER
ENGINEERS-SURVEYORS-PLANNERS
232 NORTH MAIN STREET
NEW CITY, NY 10956
TEL: (845) 634-4694
FAX: (845) 634-5543
E-MAIL: rnasher@anzny.com

1.0 INTRODUCTION

1.1 Notice of Intent:

Section 402 of the Clean Water Act requires permits for stormwater discharge from construction activities, which disturb one or more acres of land to obtain a permit. To implement this law, the New York State Department of Environmental Conservation (NYSDEC) issued the General Permit GP-0-20-001 for Stormwater Discharges from Construction Activities. The Notice of Intent (NOI) is the means to obtain coverage under this permit.

1.2 SWPPP Goals and Objective:

The goal of the Stormwater Pollution Prevention Plan (SWPPP) is to control runoff of pollutants from the project site during and after construction activities by complying with the NY State Pollutant Discharge Elimination System (SPDES) Stormwater Permit for construction activities and local rules and regulations. The SWPPP will implement the following practices:

- Reduction or elimination of erosion and sediment loading to waterbodies during construction;
- Control of the impact of stormwater runoff on the water quality of the receiving waters;
- Control of the increased volume and peak rate of runoff during and after construction; and
- Maintenance of stormwater controls during and after completion of construction.

The SWPPP will incorporate the proper selection, sizing and siting of the Stormwater Management Practices (SMPs) to protect water resources from stormwater impacts. The design of the proposed SMPs were determined using current engineering methodologies to provide appropriate sizing criteria to avoid overburdening stormwater conveyance structures. Erosion and Sediment Control (ESC), Water Quantity Control, and Water Quality Controls are inter-related components of the SWPPP.

The SWPPP is intended to be a "living" document. The document should be revised and updated by a qualified professional whenever site conditions dictate. Any proposed revisions shall undergo review by the owner or his designated representative prior to incorporation in the SWPPP and implementation at the site. Any proposed modifications shall be in accordance with the New York State Department of Environmental Conservation's technical standards.

2.0 SITE DESCRIPTION

2.1 Project Name & Location:

Mahopac Wells 1, 2, & 3
Town of Carmel
Putnam County, New York
Town of Ramapo Tax Map: Section 75.20, Block 2, Lot 68

2.2 Owner/Operator Name & Address:

Suez Water New York, Inc.
Attention: Steven Garabed
162 Old Mill Road
West Nyack, NY 10994
Email: steven.garabed@suez.com

2.3 General Contractor*:

(Company Name)

(Street Address)

(City, State, Zip Code)

(Phone Number)

*note – General Contractor shall be identified prior to commencement of work.

2.4 Description:

The project site is located east of Bucks Hollow Road, $\pm 890ft$ south of Astor Drive in the Town of Carmel, Putnam County, New York. The site has an area of about 53.382 acres. The existing site consists of a pond, woods, grass, an access gravel area road, and some impervious area. The developed site includes the construction of a building and an increase in the gravel coverage.

MAHOPAC WELLS 1, 2, & 3
Full Stormwater Pollution Prevention Plan (SWPPP) Report

Soil Name	Soil Map Symbol	Hydrological Soil Group
Charlton-Chatfield complex, 0 to 15 percent slopes, very rocky	CrC	B
Natchaug muck, 0 to 2 percent slopes	NcA	D
Sun loam	Sh	D

* Source: <https://websoilsurvey.sc.egov.usda.gov/App/WebSoilSurvey.aspx>

** HSG "B & D" were used in the drainage calculation.

Soil disturbing activities will include clearing and grubbing; installation of a stabilized construction entrance; grading (cuts & fills); excavation for the installation of drainage pipes, SMPs, sanitary sewer connections, water main connections, building foundations, stormwater management facilities and the preparation for final planting and seeding.

2.5 Impervious Cover:


Impervious cover within the planned disturbance will be increased from 0.126 acres in the existing condition to 0.242 acres in the proposed condition.

2.6 Site Area:

The site is approximately 53.382 acres and about 0.985 acres will be disturbed by the proposed construction activities.

MAHOPAC WELLS 1, 2, & 3
Full Stormwater Pollution Prevention Plan (SWPPP) Report

2.7 Location Map:



2.8 Sequence of Major Activities:

Phasing and schedule of construction is as follows (several phases will overlap):

Phase 1: Clearing and grubbing of designated areas

Phase 2: Land grading according to the approved site development plan

Phase 3: Building construction

Phase 4: Utilities construction

Phase 5: Final Grading, landscaping

The general order of activities will be as follows:

1. Schedule a pre-construction meeting.
2. Locate natural resources and the limit of disturbance per approved plans.
3. Install perimeter erosion and sediment control practices (silt fences).
4. Install construction entrances and temporary staging.
5. Limit grading for installation of E&SC practices.
6. Dispose clearing and grading materials as construction progresses.
7. Stockpile top soil and stabilize.
8. Perform rough grading/cut & fill and stabilize inactive areas.
9. Install utilities and drainage structures.
10. Construct foundation and building structure as per plan.
11. Apply soil restoration practices as described in the plan.
12. Perform final stabilization, i.e. top soil and landscaping.
13. Remove sediment accumulations and complete permanent post construction SMPs per the approved plan.
14. Remove E&SC practices and apply for a Notice of Termination (N.O.T.).

3.0 CONTROLS

3.1 Erosion and Sediment Controls Stabilization Practices:

3.1.1 Temporary Stabilization:

Topsoil, stockpiles, and soils that are exposed and left bare for a period of 14 days which are not being graded, not under active construction for 14 days or more, or not scheduled for permanent seeding within 14 days will be stabilized with temporary seed and mulch. All grass seed mixtures and application rates shall comply with Sediment and Erosion Control Plan.

Areas of the site, which are to be paved; will be temporarily stabilized by applying stone sub-base until bituminous pavement can be applied.

3.1.2 Permanent Stabilization:

Disturbed portions of the site where construction activities permanently cease shall be stabilized with permanent seed no later than 14 days after the last construction activity.

3.2 Structural Practices:

Proposed measures will include silt fences, construction fence, concrete washout, stockpile, and stabilized construction entrance.

3.3 Stormwater Management Water Quality:

Stormwater runoff generated by the rooftop will be directed towards the proposed dry pond system through a combination of downspouts and pipes.

The stormwater management system has been designed to comply with the most recent NYSDEC design manual requirements. The dry pond system is designed to treat the first flush water quality volume of required impervious area, according to NYSDEC redevelopment rules.

The property owner shall be responsible for the long-term operation, maintenance and inspection of the proposed stormwater management facilities and provide maintenance records to the Town of Carmel.

3.3.1 Name of Receiving Waters:

The site drains towards a NYSDEC wetland. The site is located in one of the watersheds identified in Appendix C of GP-0-20-001.

3.4 Peak Flow Attenuation:

In order to provide the zero net increase of peak runoff, a Dry Pond System has been proposed.

3.5 Runoff Conveyance Systems:

The stormwater pipes and the 12-inch riser with domed structure are design to convey the 10-year peak flow discharge.

3.6 Other Controls:

3.6.1 Waste Materials:

All waste materials will be collected and stored in securely lidded metal dumpsters rented from _____, a solid waste management company located in Putnam County (name of carting company to be identified 30 days prior to commencement of work). The dumpsters will meet Town of Carmel, Putnam County, and New York State solid waste management regulations. All trash and construction debris from the site will be deposited in the dumpsters. The dumpsters will be emptied as necessary, and the trash will be hauled off site to _____ (destination to be identified 30 days prior to commencement of work). No construction waste materials will be buried on site. All personnel will be instructed regarding the correct procedure for waste disposal. Notices stating these practices will be posted in the office trailer and _____, the Job Supervisor, individual who is responsible for managing the day to day site operations, will be responsible for seeing that these procedures are followed (Job Supervisor shall be identified 30 days prior to commencement of work).

3.6.2 Hazardous waste:

All hazardous waste materials will be disposed of in the manner specified by local or state regulation or by the manufacturer. Site personnel will be instructed in these practices and _____, Job Supervisor, individual who is responsible for managing the day to day site operations, will be responsible for seeing that these procedures are followed (Job Supervisor shall be identified 30 days prior to commencement of work).

3.6.3 Sanitary Waste:

A licensed sanitary waste management contractor (sanitary waste management contractor to be identified 30 days prior to commencement of work) will collect all sanitary waste from the portable units.

3.6.4 Offsite Vehicle Tracking:

A stabilized construction entrance and gravel pad will be provided to wash or spray-clean trucks over before leaving the site in order to prevent track-out of dirt, mud, debris and dust. In addition, trucks will be covered with a tarp and at least 6 inches of freeboard clearance will be maintained to keep excessive dust from escaping the truck during hauling operations.

3.7 Timing of Control Measures:

As indicated in the Sequence of Major Activities, the stabilized construction entrance and other sediment and erosion control activities will be constructed prior to earthwork activities on any part of the site. Any soil areas that are exposed and left bare for a period of 14 days which are not being graded, not under active construction for 14 days or more, or not scheduled for permanent seeding within 14 days will be treated with temporary seed and mulch. Once construction activity ceases permanently in an area, that area will be stabilized with permanent seed and mulch. After the entire site is stabilized, accumulated sediments will be removed from the sediment and erosion control structures and the controls will be removed.

3.8 Certification of Compliance With Federal, State And Local Regulations:

The stormwater pollution prevention plan reflects New York State Department of Environmental Conservation requirements for storm water management and erosion and sediment control, as established in Article 17, Titles 7, 8 and Article 70 of the Environmental Conservation Law. To ensure compliance, this plan was prepared in accordance with guidelines issued with the SPDES General Permit for Storm Water Discharges from Construction Activities that are Classified as "Associated with Construction Activity", published by the NYSDEC.

4.0 MAINTENANCE & INSPECTION PROCEDURES

4.1 Sediment & Erosion Control Inspection And Maintenance Practices:

The following are inspection and maintenance practices that will be used in coordination with the SWPPP Construction Log Book prepared for this project, the template which is included in Appendix A, to maintain sediment and erosion controls:

- The Operator shall have a qualified professional conduct an assessment of the site prior to the commencement of construction and certify in this inspection report that the appropriate erosion and sediment controls described in the SWPPP, as required by the SPDES General Permit for Stormwater Discharges, have been adequately installed or implemented to ensure overall preparedness of the site for commencement of construction. Qualified professional means a person knowledgeable in the principles and practice of erosion and sediment controls, such as a licensed professional engineer, Certified Professional in Erosion and Sediment Control (CPESC), soil scientist, or someone working under the direction and supervision of a licensed professional engineer, Certified Professional in Erosion and Sediment Control (CPESC), or soil scientist (person must have experience in the principles and practices of erosion and sediment control). The template for the initial inspection and assessment is included in Appendix A.
- All control measures will be inspected by a qualified professional at least once each week (7 days) and immediately following any storm event of 0.5 inches or greater.
- All measures will be maintained in good working order. If a repair is necessary, it will be initiated within 24 hours of discovery.
- Provide sprinkle water on the dirt road during hot summer or when appropriate to prevent particles to be air born.
- Built up sediment to be removed from the silt fence when it has reached 1/3 the height of the fence. Sediment traps will be cleaned when built up sediments reaches 25 percent of design capacity.
- Silt-fence will be inspected for depth of sediment, tears, to see if the fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground.
- Temporary and permanent seeding and planting will be inspected for bare spots, washouts, and healthy growth.
- A maintenance inspection report will be filled out after each inspection and will become part of the SWPPP.
- _____, Job Supervisor – Trained Individual per GP-0-20-001, will select individuals who will be responsible for coordinating efforts with the qualified professional for regular inspections, maintenance and repair activities, and filling out the inspection and maintenance report forms. Inspection reports will summarize:

MAHOPAC WELLS 1, 2, & 3
Full Stormwater Pollution Prevention Plan (SWPPP) Report

1. Name of Inspector
2. Qualifications of Inspector
3. Date of Inspection
4. Weather Conditions
5. Areas inspected, including measurements
6. Areas that have undergone temporary and permanent stabilization
7. Indicate all disturbed areas that have not undergone active site work during the previous 14-day period
8. Observed condition of all erosion and sediment control practices
9. Inspect all sediment control practices and record approximate degree of sediment accumulation as a percentage of the sediment storage volume
10. Actions Taken to Correct Problems
11. Incorporate changes necessary to the SWPPP

The template for regular inspections is included in Appendix A.

- Personnel selected for inspection and maintenance responsibilities will receive training from the Job Supervisor and/or the qualified professional. They will be trained in all the inspection and maintenance practices necessary for keeping the erosion and sediment controls used on site in good working order.
- The Operator shall ensure that a record of all inspection reports is maintained in the SWPPP Construction Log Book. The site logbook shall be maintained on site and be made available to the permitting authorities upon request. Prior to the commencement of construction, the Operator shall certify in the site log book that the SWPPP was prepared in accordance with the State's standards and meets all Federal, State and local erosion and sediment control requirements. The Operator shall retain copies of SWPPPs and any reports submitted in conjunction with this permit, and records of all data used to complete the NOI to be covered by this permit, for a period of at least three years from the date that the site is finally stabilized. The Operator shall post at the site, in a publicly accessible location, a summary of the site inspection activities on a monthly basis. The template for SWPPP Construction Log Book is included in Appendix A.
- Prior to filing of the Notice of Termination (NOT) or the end of permit term, the Operator shall have the qualified professional perform a final site inspection. The qualified professional shall certify that the site has undergone final stabilization using either vegetative or structural stabilization methods and that all temporary erosion and sediment controls (such as silt fencing) not needed for long-term erosion control have been removed. Final stabilization means that all soil-disturbing activities at the site have been completed and a uniform, perennial vegetative cover with a density of 80% has been established, or equivalent stabilization measures (such as the use of mulches or geotextiles) have been employed on all unpaved areas and areas not covered by permanent structure. The template for final inspections is included in Appendix A.

MAHOPAC WELLS 1, 2, & 3
Full Stormwater Pollution Prevention Plan (SWPPP) Report

- Clean out all **temporary** structures and pipes upon completion of the project.
- When the site has been finally stabilized, the operator must submit a Notice of Termination form to terminate coverage under the SPDES General Permit GP 0-20-001. The permittee must identify all of the permanent stormwater management structures that have been constructed. In addition, an manual describing the operation and maintenance practices that will be necessary for the structures to function as designed after the site is stabilized must be finalized and in-place. The permittee must also certify that the permanent structure have been constructed as described in the SWPPP.

The inspection procedures that will be used for the construction of the proposed Stormwater management facilities are included in the CONSTRUCTION INSPECTION CHECKLIST FORM prepared for this project, the template of which is included in Appendix B, to be used to ensure proper construction.

4.2 Summary of SWPPP Required Document Filings:

The following table provides a summary of the required forms and inspections that need to be completed as part of the SWPPP requirements and which checklist or report document forms need to be used for each:

<u>Name of Document</u>	<u>Form to be Used</u>	<u>When to complete</u>
Pre-Construction Meeting Documents Form	Appendix A – SWPPP Construction Site Log Book	Prior to beginning of construction
Owner/Operator Certification	Appendix A, SWPPP Report	Prior to beginning of construction
Prime Contractor Certification	SWPPP Report	Prior to beginning of construction
Sub-Contractor Certification	SWPPP Report	Prior to beginning of construction
Pre-Construction Site Assessment Form	Appendix A	Prior to beginning of construction
Construction Duration Inspection Forms	Appendix A	Every seven days
Three-Month Status Reports	Appendix A	Every three months
SMPs Construction Inspection Checklist Form	Appendix B	During the construction of the proposed stormwater facilities
Final Stabilization and Retention of Records	Appendix B	At completion of project
Spill Control & Prevention Log	Appendix C	Before and after completion of Project
Stormwater Facilities Maintenance Plan and Inspection Checklists	Appendix D	After completion of Project

5.0 NON-STORM WATER DISCHARGES

5.1 Non-Stormwater Discharges:

It is expected that the following non-storm water discharges will occur from the site during the construction period:

- Water from water line flushing.
- Pavement wash waters (where no spills or leaks of toxic or hazardous materials have occurred).
- Uncontaminated groundwater (from natural springs)

6.0 INVENTORY FOR POLLUTION PREVENTION PLAN

6.1 Material substances:

The materials or substances listed below are expected to be present on the site during construction:

- Concrete
- Detergents
- Paints (enamels and latex)
- Metal Studs
- Roofing Materials
- Tar and Paving Materials
- Fertilizers
- Petroleum Based Products
- Cleaning Solvents
- Wood
- Masonry Block

7.0 SPILL CONTROL & PREVENTION

7.1 Material Management Practices:

The following are the material management practices that will be used to reduce the risk of spills or other accidental exposure of materials and substances to storm water runoff:

MAHOPAC WELLS 1, 2, & 3
Full Stormwater Pollution Prevention Plan (SWPPP) Report

7.1.1 Good Housekeeping:

The following good housekeeping practices will be followed on site during the construction project:

- An effort will be made to store only enough products required to do the job.
- All materials stored on site will be stored in a neat, orderly manner in their appropriate containers and, if possible, under a roof or other enclosure.
- Product will be kept in their original containers with the original manufacturer's label.
- Substances will not be mixed with one another unless recommended by the manufacturer.
- Whenever possible, all of a product will be used up before disposing of the container.
- Manufacturer's recommendations for proper use and disposal will be followed.
- The Job Supervisor will inspect daily to ensure proper use and disposal of materials on site.

7.1.2 Hazardous Products:

The following practices will be used to reduce the risks associated with hazardous materials:

- Products will be kept in original containers unless they are not reseal able.
- Original labels and material safety data will be retained; they contain important product information.
- If surplus product must be disposed of, manufacturer's or local and State recommended methods for proper disposal will be followed.

7.2 Product Specific Practices:

The following product specific practices will be followed on site:

7.2.1 Petroleum Products:

All onsite vehicles will be monitored for leaks and receive regular preventative maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers, which are clearly labeled. Any asphalt substances used on site will be applied according to the manufacturer's recommendations.

7.2.2 Fertilizers:

Fertilizers will be applied only in the minimum amounts recommended by the manufacturer. Once applied, fertilizer will be worked into the soil to limit exposure to stormwater. Storage will be in a covered shed. The content of any partially used bags of fertilizer will be transferred to a sealable plastic bin to avoid spills.

7.2.3 Paints:

All containers will be tightly sealed and stored when not required for use. Excess paint will not be discharged to the storm drainage system, but will be properly disposed of according to manufacturer's instructions or State and local regulations.

7.2.4 Concrete Trucks:

Concrete trucks will not be allowed to wash out or discharge surplus concrete or drum wash water on the site.

7.3 Spill Control Practices:

In addition to the good housekeeping and material management practices discussed in the previous sections of this plan, the following practices will be followed for spill prevention and cleanups:

- Manufacturer's recommended methods for spill cleanup will be clearly posted and site personnel will be made aware of the procedures and the location of the information and cleanup supplies.
- Materials and equipment necessary for spill cleanup will be kept in the material storage areas on site. Equipment and materials will include, but not be limited to, brooms, dustpans, mops, rags, gloves, goggles, kitty litter, sand, sawdust, and plastic and metal trash containers specifically for this purpose.
- All spills will be cleaned up immediately after discovery.
- The spill area will be kept well ventilated, and personnel will wear appropriate protective clothing to prevent injury from contact with hazardous substances.
- Spills of toxic or hazardous material will be reported to the appropriate State or local government agency, regardless of the size of the spill. The Spill Control & Prevention Log form provided in Appendix C should be used for this purpose.
- The spill prevention plan will be adjusted to include measures to prevent a repetitive type of spill from re-occurring and how to clean up the spill if it does re-occur. A description of the spill, what caused it, and the cleanup measures will also be included.
- The Job Supervisor responsible for daily site operations, will be designated as the spill prevention and cleanup coordinator. He will designate at least

MAHOPAC WELLS 1, 2, & 3
Full Stormwater Pollution Prevention Plan (SWPPP) Report

three other site personnel who will receive spill prevention and cleanup training. These individuals will each become responsible for a particular phase of prevention and cleanup. The names of the responsible spill personnel will be posted in the material storage area and in the office trailer on site.

8.0 SUPPORTING PLANS & REPORTS

1. Site Plan Drawings prepared by Atzl, Nasher & Zigler
2. Soil & Erosion Control Plans prepared by Atzl, Nasher & Zigler
3. Stormwater Management Design Report by Atzl, Nasher & Zigler

9.0 POLLUTION PREVENTION PLAN CERTIFICATION

9.1 OWNER/OPERATOR CERTIFICATION

"I have read or been advised of the permit conditions and believe that I understand them. I also understand that, under the terms of the permit, there may be reporting requirements. I also certify under penalty of law that this document and all corresponding attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person(s) who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further understand that coverage under the general permit will be identified in the acknowledgement that I will receive as a result of submitting this NOI. I also understand that, by submitting this NOI, I am acknowledging that the SWPPP has been developed and will be implemented as the first element of construction and agree to comply with all the terms and conditions of the general permit for which this NOI is being submitted."

Signed: _____
(Owner/Operator)

Date: _____

(Printed Name & Title)

(Company Name, Address & Telephone Number)

10.0 CERTIFICATION BY CONTRACTORS

Made pursuant to the State Pollution Discharge Elimination System (SPDES) General Permit for Stormwater Discharges from Construction Activity (Permit No. GP 0-20-001) for:

Mahopac Wells 1, 2, & 3, Town of Carmel, Putnam County, New York

10.1 Prime Contractor Certification:

"I certify under penalty of law that I understand and agree to comply with the terms and conditions of the stormwater pollution prevention plan for the construction site identified in this plan as a condition of authorization to discharge stormwater. I also understand that the operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System (SPDES) General Permit for Stormwater Discharges from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards."

Prime Contractor:

(Signature)

(Company)

(Name)

(Street Address)

(Title)

(City, State, Zip Code)

(Date)

(Phone Number)

MAHOPAC WELLS 1, 2, & 3
Full Stormwater Pollution Prevention Plan (SWPPP) Report

10.2 Sub-Contractor Certification:

"I certify under penalty of law that I understand and agree to comply with the terms and conditions of the stormwater pollution prevention plan for the construction site identified in this plan as a condition of authorization to discharge stormwater. I also understand that the operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System (SPDES) General Permit for Stormwater Discharges from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards."

Sub-Contractor:

(Signature)

(Company)

(Name)

(Street Address)

(Title)

(City, State, Zip Code)

(Date)

(Phone Number)

**MAHOPAC WELLS 1, 2, & 3
Full Stormwater Pollution Prevention Plan (SWPPP) Report**

CONTRACTOR and SUBCONTRACTOR CERTIFICATION STATEMENT

for the New York State Department of Environmental Conservation (DEC) State Pollutant Discharge Elimination System Permit for Stormwater Discharges from Construction Activity (GP-0-20-001)

As per Part III.A.6 on page 13 of GP-0-20-001 (effective January 29, 2020):

'Prior to the commencement of construction activity, the owner or operator must identify the contractor(s) and subcontractor(s) that will be responsible for installing, constructing, repairing, replacing, inspecting and maintaining the erosion and sediment control practices included in the SWPPP; and the contractor(s) and subcontractor(s) that will be responsible for constructing the post-construction stormwater management practices included in the SWPPP. The owner or operator shall have each of the contractors and sub-contractors identify at least one person from their company that will be responsible for implementation of the SWPPP. This person shall be known as the *trained contractor*. The owner or operator shall ensure that at least one *trained contractor* is on site on a daily basis when soil disturbance activities are being performed.'

The owner or operator shall have each contractor and subcontractor involved in soil disturbance sign a copy of the following certification statement before they commence any construction activity:

_____	NYR _____	_____
<i>Name of Construction Site</i>	<i>DEC Permit ID</i>	<i>Municipality (MS4)</i>
<p><i>"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the qualified inspector during a site inspection. I also understand that the owner or operator must comply with the terms and conditions of the most current version of the New York State Pollutant Discharge Elimination System ("SPDES") general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.</i></p>		
_____	_____	
Responsible Corporate Officer/Partner Signature	Date	
_____	_____	
Name of above Signatory	Name of Company	
_____	_____	
Title of above Signatory	Mailing Address	
_____	_____	
Telephone of Company	City, State, and Zip	
Identify the specific elements of the SWPPP the contractor or subcontractor is responsible for:		
'TRAINED CONTRACTOR' FOR THE CERTIFIED CONTRACTOR OR SUBCONTRACTOR		
_____	_____	_____
<i>Name of Trained Employee</i>	<i>Title of Trained Employee</i>	<i>NYSDEC SWT #</i>

A copy of this signed contractor certification statement must be maintained at the SWPPP on site

Appendix - A

MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

APPENDIX-A

CONSTRUCTION SITE LOGBOOK

BY

ATZL, NASHER & ZIGLER
ENGINEERS-SURVEYORS-PLANNERS
232 NORTH MAIN STREET
NEW CITY, NY 10956
TEL: (845) 634-4694
FAX: (845) 634-5543
E-MAIL: rnasher@anzny.com

SWPPP CONSTRUCTION SITE LOG BOOK FOR MAHOPAC WELLS 1, 2, & 3

**NY STATE POLLUTANT DISCHARGE ELIMINATION SYSTEM
FOR CONSTRUCTION ACTIVITIES**

SWPPP CONSTRUCTION SITE LOG BOOK

For

**Mahopac Wells 1, 2, & 3
Town of Carmel
Putnam County, New York**

Table of Contents

- I. Pre-Construction Meeting Documents.
 - a. Preamble to Site Assessment and Inspections
 - b. Operator's Certification
 - c. Qualified Professional's Credentials & Certification
 - d. Pre-Construction Site Assessment Checklist
- II. Construction Duration Inspections
 - a. Directions
 - b. Modification to the SWPPP
- III. Monthly Summary Reports
- IV. Monitoring, Reporting, and Three-Month Status Reports
 - a. Operator's Compliance Response Format

Properly completing forms such as those contained in this document meet the inspection requirement of NYSDEC SPDES GP for Construction Activities. Completed forms shall be kept on site at all times and made available to authorities upon request.

SWPPP CONSTRUCTION SITE LOG BOOK FOR MAHOPAC WELLS 1, 2, & 3

I. PRE-CONSTRUCTION MEETING DOCUMENTS

Project Name MAHOPAC WELLS 1, 2, & 3
Permit No. _____ Date of Authorization _____
Name of Operator _____
Prime Contractor _____

a. Preamble to Site Assessment and Inspections -the following information to be read by all person's involved in the construction of stormwater related activities:

The Operator agrees to have a qualified professional¹ conduct an assessment of the site prior to the commencement of construction² and certify in this inspection report that the appropriate erosion and sediment controls described in the SWPPP have been adequately installed or implemented to ensure overall preparedness of the site for the commencement of construction.

Prior to the commencement of construction, the Operator shall certify in this site logbook that the SWPPP has been prepared in accordance with the State's standards and meets all Federal, State and local erosion and sediment control requirements.

When construction starts, site inspections shall be conducted by the qualified professional at least every 7 calendar days and within 24 hours of the end of a storm event of 0.5 inches or greater (Construction Duration Inspections). The Operator shall maintain a record of all inspection reports in this site log book. The site log book shall be maintained on site and be made available to the permitting authorities upon request. The Operator shall post at the site, in a publicly accessible location, a summary of the site inspection activities on a monthly basis (Monthly Summary Report).

The operator shall also prepare a written summary of compliance with this general permit at a minimum frequency of every three months (Operator's Compliance Response Form), while coverage exists. The summary should address the status of achieving each component of the SWPPP.

Prior to filing the Notice of Termination or the end of permit term, the Operator shall have a qualified professional perform a final site inspection. The qualified professional shall certify that the site has undergone final stabilization³ using either vegetative or structural stabilization methods and that all temporary erosion and sediment controls (such as silt fencing) not needed for long-term erosion control have been removed. In addition, the Operator must identify and certify that all permanent structures described in the SWPPP have been constructed and provide the owner(s) with an operation and maintenance plan that ensures the structure(s) continuously functions as designed.

1 "Qualified Professional means a person knowledgeable in the principles and practice of erosion and sediment controls, such as a Certified Professional in Erosion and Sediment Control (CPESC), soil scientist, licensed engineer or someone working under the direction and supervision of a licensed engineer (person must have experience in the principles and practices of erosion and sediment control).

2 "Commencement of construction" means the initial removal of vegetation and disturbance of soils associated with clearing, grading or excavating activities or other construction activities.

3 "Final stabilization" means that all soil-disturbing activities at the site have been completed and a uniform, perennial vegetative cover with a density of eighty (80) percent has been established or equivalent stabilization measures (such as the use of mulches or geotextiles) have been employed on all unpaved areas and areas not covered by permanent structures.

b. Operators Certification

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a class A misdemeanor pursuant to Section 210.45 of the Penal Law. "

Name (Please Print): _____

Title _____ Date: _____

Address: _____

Phone: _____ Email: _____

Signature: _____

c. Qualified Professional's Credentials & Certification

"I hereby certify that I meet the criteria set forth in the General Permit to conduct site inspections for this project and that the appropriate erosion and sediment controls described in the SWPPP and as described in the following Pre-construction Site Assessment Checklist have been adequately installed or implemented, ensuring the overall preparedness of this site for the commencement of construction."

Name (Please Print): _____

Title _____ Date: _____

Address: _____

Phone: _____ Email: _____

Signature: _____

d. Pre-construction Site Assessment Checklist (NOTE: Provide comments below as necessary)

I. Notice of Intent, SWPPP, and Contractors Certification:

Yes No NA

Has a Notice of Intent been filed with the NYS Department of Conservation?

Is the SWPPP on-site? Where? _____

Is the Plan current? What is the latest revision date? _____

Is a copy of the NOI (with brief description) onsite? Where? _____

Have all contractors involved with stormwater related activities signed a contractor's certification?

Pre-construction Site Assessment Checklist (continued)

SWPPP CONSTRUCTION SITE LOG BOOK FOR MAHOPAC WELLS 1, 2, & 3

2. Resource Protection

Yes No NA

- Are construction limits clearly flagged or fenced?
- Important trees and associated rooting zones, on-site septic system absorption fields, existing vegetated areas suitable for filter strips, especially in perimeter areas, have been flagged for protection.
- Creek crossings installed prior to land-disturbing activity, including clearing and blasting.

3. Surface Water Protection

Yes No NA

- Clean stormwater runoff has been diverted from areas to be disturbed.
- Bodies of water located either on site or in the vicinity of the site have been identified and protected.
- Appropriate practices to protect on-site or downstream surface water are installed.
- Are clearing and grading operations divided into areas <5 acres?

4. Stabilized Construction Entrance

Yes No NA

- A temporary construction entrance to capture mud and debris from construction vehicles before they enter the public highway has been installed.
- Other access areas (entrances, construction routes, equipment parking areas) are stabilized immediately as work takes place with gravel or other cover.
- Sediment tracked onto public streets is removed or cleaned on a regular basis.

5. Perimeter Sediment Controls

Yes No NA

- Silt fence material and installation comply with the standard drawing and specifications.
- Silt fences are installed at appropriate spacing intervals
- Sediment/detention basin was installed as first land disturbing activity.
- Sediment traps and barriers are installed.

6. Pollution Prevention for Waste and Hazardous Materials

Yes No NA

- The Operator or designated representative has been assigned to implement the spill prevention avoidance and response plan.
- The plan is contained in the SWPPP on page _____
- Appropriate materials to control spills are onsite. Where? _____

II. CONSTRUCTION DURATION INSPECTIONS

a. Directions:

Inspection Forms will be filled out during the entire construction phase of the project.

Required Elements:

(1) On a site map, indicate the extent of all disturbed site areas and drainage pathways. Indicate site areas that are expected to undergo initial disturbance or significant site work within the next 14-day period;

(2) Indicate on a site map all areas of the site that have undergone temporary or permanent stabilization;


(3) Indicate all disturbed site areas that have not undergone active site work during the previous 14-day period;

Inspect all sediment control practices and record the approximate degree of sediment accumulation as a percentage of sediment storage volume (for example, 10 percent, 20 percent, 50 percent);

(5) Inspect all erosion and sediment control practices and record all maintenance requirements such as verifying the integrity of barrier or diversion systems (earthen berms or silt fencing) and containment systems (sediment basins and sediment traps). Identify any evidence of rill or gully erosion occurring on slopes and any loss of stabilizing vegetation or seeding/mulching. Document any excessive deposition of sediment or ponding water along barrier or diversion systems. Record the depth of sediment within containment structures, any erosion near outlet and overflow structures, and verify the ability of rock filters around perforated riser pipes to pass water; and

(6) Immediately report to the Operator any deficiencies that are identified with the implementation of the SWPPP.

CONSTRUCTION DURATION INSPECTIONS



SITE PLAN/SKETCH

Inspector (Print Name)

Date of Inspection

Qualified Professional (Print Name)

Qualified Professional Signature

The above signed acknowledges that, to the best of his/her knowledge, all information provided on the forms is accurate and complete.

CONSTRUCTION DURATION INSPECTIONS

Maintaining Water Quality

Yes No NA

- Is there an increase in turbidity causing a substantial visible contrast to natural conditions?
- Is there residue from oil and floating substances, visible oil film, or globules or grease?
- All disturbance is within the limits of the approved plans.
- Have receiving lake/bay, stream, and/or wetland been impacted by silt from project?

Housekeeping

1. General Site Conditions

Yes No NA

- Is construction site litter and debris appropriately managed?
- Are facilities and equipment necessary for implementation of erosion and sediment control in working order and/or properly maintained?
- Is construction impacting the adjacent property?
- Is dust adequately controlled?

2. Temporary Stream Crossing

Yes No NA

- Maximum diameter pipes necessary to span creek without dredging are installed.
- Installed non-woven geotextile fabric beneath approaches.
- Is fill composed of aggregate (no earth or soil)?
- Rock on approaches is clean enough to remove mud from vehicles & prevent sediment from entering stream during high flow.

Runoff Control Practices

1. Excavation Dewatering

Yes No NA

- Upstream and downstream berms (sandbags, inflatable dams, etc.) are installed per plan.
- Clean water from upstream pool is being pumped to the downstream pool.
- Sediment laden water from work area is being discharged to a silt-trapping device.
- Constructed upstream berm with one-foot minimum freeboard.

2. Level Spreader

Yes No NA

- Installed per plan.
- Constructed on undisturbed soil, not on fill, receiving only clear, non-sediment laden flow.
- Flow sheets out of level spreader without erosion on downstream edge.

3. Interceptor Dikes and Swales

Yes No NA

- Installed per plan with minimum side slopes 2H:1V or flatter.
- Stabilized by geotextile fabric, seed, or mulch with no erosion occurring.
- Sediment-laden runoff directed to sediment trapping structure

4. Stone Check Dam

SWPPP CONSTRUCTION SITE LOG BOOK FOR MAHOPAC WELLS 1, 2, & 3

Yes No NA

- Is channel stable? (flow is not eroding soil underneath or around the structure).
- Check is in good condition (rocks in place and no permanent pools behind the structure).
- Has accumulated sediment been removed?.

5. Rock Outlet Protection

Yes No NA

- Installed per plan.
- Installed concurrently with pipe installation.

Soil Stabilization

1. Topsoil and Spoil Stockpiles

Yes No NA

- Stockpiles are stabilized with vegetation and/or mulch.
- Sediment control is installed at the toe of the slope.

2. Revegetation

Yes No NA

- Temporary seedings and mulch have been applied to idle areas.
- 4 inches minimum of topsoil has been applied under permanent seedings

Sediment Control

1. Stabilized Construction Entrance

Yes No NA

- Stone is clean enough to effectively remove mud from vehicles.
- Installed per standards and specifications?
- Does all traffic use the stabilized entrance to enter and leave site?
- Is adequate drainage provided to prevent ponding at entrance?

2. Silt Fence

Yes No NA

- Installed on Contour, 10 feet from toe of slope (not across conveyance channels).
- Joints constructed by wrapping the two ends together for continuous support.
- Fabric buried 6 inches minimum.
- Posts are stable, fabric is tight and without rips or frayed areas.
- Sediment accumulation is ___% of design capacity.

3. Storm Drain Inlet Protection (Use for Stone & Block; Filter Fabric; Curb; or, Excavated practices)

Yes No NA

- Installed concrete blocks lengthwise so open ends face outward, not upward.
- Placed wire screen between No. 3 crushed stone and concrete blocks.
- Drainage area is 1 acre or less.
- Excavated area is 900 cubic feet.
- Excavated side slopes should be 2:1.

SWPPP CONSTRUCTION SITE LOG BOOK FOR MAHOPAC WELLS 1, 2, & 3

- 2" x 4" frame is constructed and structurally sound.
- Posts 3-foot maximum spacing between posts.
- Fabric is embedded 1 to 1.5 feet below ground and secured to frame/posts with staples at max 8-inch spacing.
- Posts are stable, fabric is tight and without rips or frayed areas.
- Sediment accumulation ___% of design capacity.

4. Temporary Sediment Trap

Yes No NA

- Outlet structure is constructed per the approved plan or drawing.
- Geotextile fabric has been placed beneath rock fill.
- Sediment accumulation is ___% of design capacity.

5. Temporary Sediment Basin

Yes No NA

- Basin and outlet structure constructed per the approved plan.
- Basin side slopes are stabilized with seed/mulch.
- Drainage structure flushed and basin surface restored upon removal of sediment basin facility.
- Sediment accumulation is ___% of design capacity.

Note: Not all erosion and sediment control practices are included in this listing. Add additional pages to this list as required by site specific design.
Construction inspection checklists for post-development stormwater management practices can be found in Appendix F of the New York Stormwater Management Design Manual.

Appendix-B



MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

APPENDIX-B

CONSTRUCTION INSPECTION CHECKLISTS

BY

ATZL, NASHER & ZIGLER

ENGINEERS-SURVEYORS-PLANNERS

232 NORTH MAIN STREET

NEW CITY, NY 10956

TEL: (845) 634-4694

FAX: (845) 634-5543

E-MAIL: rnasher@anzny.com

MAHOPAC WELLS 1, 2, & 3
Stormwater System Design
Construction Inspection Checklist Form

STORMWATER MANAGEMENT
CONSTRUCTION INSPECTION CHECKLIST FORM

Project: **Mahopac Wells 1, 2, & 3**
 Location: **Town of Carmel, Putnam County, NY**

Site Status: _____
 Date of Inspection: _____
 Time of Inspection: _____
 Weather Conditions
 (including recent rainfall): _____
 Inspector's Name: _____

CONSTRUCTION SEQUENCE	SATISFACTORY/ UNSATISFACTORY	COMMENTS
1. Pre-Construction/Materials and Equipment		
Pre-construction meeting		
Pipe and appurtenances on-site prior to construction and dimensions checked		
1. Material (including protective coating, if specified)		
2. Diameter		
3. Dimensions of metal riser or pre-cast concrete outlet structure		
4. Required dimensions between water control structures (orifices, weirs, etc.) are in accordance with approved plans		
5. Barrel stub for prefabricated pipe structures at proper angle for design barrel slope		
6. Number and dimensions of prefabricated anti-seep collars		
7. Watertight connectors and gaskets		
8. Outlet drain valve		
Project benchmark near pond site		
Equipment for temporary de-watering		

MAHOPAC WELLS 1, 2, & 3
Stormwater System Design
Construction Inspection Checklist Form

2. Subgrade Preparation		
Area beneath embankment stripped of all Vegetation, topsoil, and organic matter		
3. Pipe Spillway Installation		
Method of installation detailed on plans		
A. Bed preparation		
Installation trench excavated with specified side slopes		
CONSTRUCTION SEQUENCE	SATISFACTORY/ UNSATISFACTORY	COMMENTS
Stable, uniform, dry subgrade of relatively impervious material (If subgrade is wet, contractor shall have defined steps before proceeding with installation)		
Invert at proper elevation and grade		
B. Pipe placement		
Metal / plastic pipe		
1. Watertight connectors and gaskets properly installed		
2. Anti-seep collars properly spaced and having watertight connections to pipe		
3. Backfill placed and tamped by hand under "haunches" of pipe		
4. Remaining backfill placed in max. 8 inch lifts using small power tamping equipment until 2 feet cover over pipe is reached		
3. Pipe Spillway Installation		
Concrete pipe		
1. Pipe set on blocks or concrete slab for pouring of low cradle		
2. Pipe installed with rubber gasket joints with no spalling in gasket interface area		
3. Excavation for lower half of anti-seep collar(s) with reinforcing steel set		

MAHOPAC WELLS 1, 2, & 3
Stormwater System Design
Construction Inspection Checklist Form

4. Entire area where anti-seep collar(s) will come in contact with pipe coated with mastic or other approved waterproof sealant		
5. Low cradle and bottom half of anti-seep collar installed as monolithic pour and of an approved mix		
6. Upper half of anti-seep collar(s) formed with reinforcing steel set		
7. Concrete for collar of an approved mix and vibrated into place (protected from freezing while curing, if necessary)		
8. Forms stripped and collar inspected for honeycomb prior to backfilling. Parge if necessary.		
C. Backfilling		
Fill placed in maximum 8 inch lifts		
Backfill taken minimum 2 feet above top of anti-seep collar elevation before traversing with heavy equipment		
4. Riser / Outlet Structure Installation		
Riser located within embankment		
A. Metal riser		
Riser base excavated or formed on stable subgrade to design dimensions		
CONSTRUCTION SEQUENCE	SATISFACTORY/ UNSATISFACTORY	COMMENTS
Set on blocks to design elevations and plumbed		
Reinforcing bars placed at right angles and projecting into sides of riser		
Concrete poured so as to fill inside of riser to invert of barrel		
B. Pre-cast concrete structure		

**MAHOPAC WELLS 1, 2, & 3
Stormwater System Design
Construction Inspection Checklist Form**

Dry and stable subgrade		
Riser base set to design elevation		
If more than one section, no spalling in gasket interface area; gasket or approved caulking material placed securely		
Watertight and structurally sound collar or Gasket joint where structure connects to pipe spillway		
C. Poured concrete structure		
Footing excavated or formed on stable Subgrade, to design dimensions with reinforcing steel set		
Structure formed to design dimensions, with reinforcing steel set as per plan		
Concrete of an approved mix and vibrated into place (protected from freezing while curing, if necessary)		
Forms stripped & inspected for "honeycomb" prior to backfilling; parge if necessary		
5. Embankment Construction		
Fill material		
Compaction		
Embankment		
1. Fill placed in specified lifts and compacted with appropriate equipment		
2. Constructed to design cross-section, side slopes and top width		
3. Constructed to design elevation plus allowance for settlement		
6. Impounded Area Construction		
Excavated / graded to design contours and side slopes		
Inlet pipes have adequate outfall protection		
Forebay(s)		

**MAHOPAC WELLS 1, 2, & 3
Stormwater System Design
Construction Inspection Checklist Form**

Pond benches		
7. Earth Emergency Spillway Construction		
Spillway located in cut or structurally stabilized with riprap, gabions, concrete, etc.		
Excavated to proper cross-section, side slopes and bottom width		
Entrance channel, crest, and exit channel Constructed to design grades and elevations		
CONSTRUCTION SEQUENCE	SATISFACTORY/ UNSATISFACTORY	COMMENTS
8. Outlet Protection		
A. End section		
Securely in place and properly backfilled		
B. Endwall		
Footing excavated or formed on stable Subgrade, to design dimensions and reinforcing steel set, if specified		
Endwall formed to design dimensions with Reinforcing steel set as per plan		
Concrete of an approved mix and vibrated into place (protected from freezing, if necessary)		
Forms stripped and structure inspected for "honeycomb" prior to backfilling; parge if necessary		
C. Riprap apron / channel		
Apron / channel excavated to design cross-Section with proper transition to existing ground		
Filter fabric in place		
Stone sized as per plan and uniformly place at the thickness specified		
9. Vegetative Stabilization		
Approved seed mixture or sod		
Proper surface preparation and required soil Amendments		

**MAHOPAC WELLS 1, 2, & 3
Stormwater System Design
Construction Inspection Checklist Form**

Excelsior mat or other stabilization, as per plan		
10. Miscellaneous		
Drain for ponds having a permanent pool		
Trash rack / anti-vortex device secured to outlet structure		
Trash protection for low flow pipes, orifices, etc.		
Fencing (when required)		
Access road		
Set aside for clean-out maintenance		
11. Stormwater Wetlands		
Adequate water balance		
Variety of depth zones present		
Approved pondscaping plan in place reinforcement budget for additional plantings		
Plants and materials ordered 6 months prior to construction		
Construction planned to allow for adequate planting and establishment of plant community (April-June planting window)		
Wetland buffer area preserved to maximum extent possible		

Comments:

Actions to be Taken:

Appendix - C

MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

APPENDIX-C

SPILL CONTROL AND PREVENTION LOG

BY

ATZL, NASHER & ZIGLER
ENGINEERS-SURVEYORS-PLANNERS
232 NORTH MAIN STREET
NEW CITY, NY 10956
TEL: (845) 634-4694
FAX: (845) 634-5543
E-MAIL: rnasher@anzny.com

Appendix - D



MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

APPENDIX-D MAINTENANCE AGREEMENT

BY

ATZL, NASHER & ZIGLER

ENGINEERS-SURVEYORS-PLANNERS

232 NORTH MAIN STREET

NEW CITY, NY 10956

TEL: (845) 634-4694

FAX: (845) 634-5543

E-MAIL: rnasher@anzny.com

Town of Carmel
Stormwater Facility Maintenance Agreement

Whereas, the Town of Carmel, County of Putnam, State of New York ("Municipality") and Suez Water New York, Inc ("facility owner") want to enter into an agreement to provide for the long term maintenance and continuation of stormwater control measures approved by the Municipality for the below named project, Mahopac Wells 1, 2, & 3.

Whereas, the Municipality and the facility owner desire that the stormwater control measures be built in accordance with the approved project plans and thereafter be maintained, cleaned, repaired, replaced and continued in perpetuity in order to ensure optimum performance of the components.

Therefore, the Municipality and the facility owner agree as follows:

1. This agreement inures to the benefit of the Municipality and binds the facility owner, its successors and assigns, to the maintenance provisions depicted in the approved project plans which are attached as Schedule A of this agreement.
2. The facility owner shall maintain, clean, repair, replace and continue the stormwater control measures depicted in Schedule A-1 and A-2 as necessary to ensure optimum performance of the measures to design specifications. The stormwater control measures shall include, but shall not be limited to, the following: pipes, and dry pond system.
3. The facility owner shall be responsible for all expenses related to the maintenance of the stormwater control measures and shall establish a means for the collection and distribution of expenses among parties for any commonly owned facilities.
4. The facility owner shall provide for the periodic inspection of the stormwater control measures, not less than once in every five-year period, to determine the condition and integrity of the measures. Such inspection shall be performed by a professional engineer licensed by the State of New York. The inspecting engineer shall prepare and submit to the Municipality, within 30 days of the inspection, a written report of the findings, including recommendations for those actions necessary for the continuation of the stormwater control measures.
5. The facility owner shall not authorize, undertake or permit alteration, abandonment, modification or discontinuation of the stormwater control measures except in accordance with written approval of the Municipality.

6. The facility owner shall undertake necessary repairs and replacement of the stormwater control measures at the direction of the Municipality or in accordance with the recommendations of the inspecting engineer.
7. The facility owner shall provide to the Municipality, within 30 days of the date of this agreement, a security for the maintenance and continuation of the stormwater control measures in the form of a bond, letter of credit or escrow account in the amount not to exceed \$2,500.00.
8. This agreement shall be recorded in the Office of the County Clerk, County of Putnam together with the deed for the subject premises.
9. In the event that the Municipality determines that the facility owner has failed to construct or maintain the stormwater control measures in accordance with the project plan or has failed to undertake corrective action specified by the Municipality or by the inspecting engineer, the Municipality is authorized to undertake such steps as reasonably necessary for the preservation, continuation or maintenance of the stormwater control measures and to affix the expenses thereof as a lien against the property.
10. Nothing within this agreement shall be construed to impose any affirmative obligation or covenant of performance on the Municipality.
11. This agreement is effective _____.

Facility Owner: Suez Water New York, INC

Owner's Representative: Steven Garabed, Manager of Engineering West Nyack Operations

Representative Signature: _____

ACKNOWLEDGEMENTS

State of New York)
) ss:
County of _____)

On the _____ day of _____ in the year _____ before me, the undersigned, personally appeared Christopher Graziano, personally known to me or proved to me on the basis of satisfactory evidence to be the individual(s) whose name(s) is (are) subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their capacity(ies), and that by his/her/their signature(s) on the instrument, the individual(s), or the person upon behalf of which the individual(s) acted, executed the instrument.

Signature and office of individual taking acknowledgment

Town of Carmel: _____

Representative Signature: Richard J. Franzetti, P.E, BCEE, Town Engineer

ACKNOWLEDGEMENTS


State of New York)
) ss:
County of _____)

On the _____ day of _____ in the year _____ before me, the undersigned, personally appeared Steven Garabed, personally known to me or proved to me on the basis of satisfactory evidence to be the individual(s) whose name(s) is (are) subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their capacity(ies), and that by his/her/their signature(s) on the instrument, the individual(s), or the person upon behalf of which the individual(s) acted, executed the instrument.

Signature and office of individual taking acknowledgment

SCHEDULE "A-1"

**STORMWATER MANAGEMENT FACILITIES
LAYOUT & LOCATION**



SCHEDULE "A-2"

STORMWATER MANAGEMENT SYSTEM INSPECTION AND MAINTENANCE SCHEDULE

Stormwater Management Structures:

- Stormwater Piping
- Dry Pond System

Inspections Schedule:

- Stormwater Pipes:
 - Monthly, and after major storms: Check for debris at inlets, outlets, and cleanouts.
- Dry Pond System
 - Monthly inspections during construction and on an annual basis thereafter.

Maintenance Schedule:

- Stormwater Piping: Must be cleaned as found necessary by inspection.
- Dry Pond System
 - Remove accumulated sediment and clean out and/or replace the filter gravel bed at the outfall pipe whenever accumulated sediment reaches a volume of 10% of the available basin capacity.
 - Restore any eroded embankments.
 - Remove accumulated debris within the basin and at outfall structures.

Stormwater Piping Inspection and Maintenance Checklist

Project: _____

Location: _____

Site _____

Status: _____

Date: _____

Time: _____

Inspector: _____

Inspection/Maintenance Items	Satisfactory or Unsatisfactory	Comments/Corrective Action
1. Inspection (Quarter-annually, After Major Storms)		
1. Accumulated sediment exceeds 10% of the diameter of the pipe.		
2. Vegetation the reduces free movement of water through pipes.		
3. Pipe damage: Any dent that increases flow area by more than 10% or puncture that impacts performance		
4. Trash accumulated to reduce free movement of water through pipes.		

Inspector shall use one sheet for each individual pipe run.

(Provide sketch to show location of unsatisfactory items)

ACTIONS TO BE TAKEN:

COMMENTS:

Dry Pond System Inspection and Maintenance Checklist

Project: _____
 Location: _____
 Site _____
 Status: _____
 Date: _____
 Time: _____
 Inspector: _____

Inspection/Maintenance Items	Satisfactory or Unsatisfactory	Comments/Corrective Action
1. Embankment and emergency spillway (Annual, After Major Storms)		
1. Vegetation and ground cover adequate		
2. Embankment erosion		
3. Animal burrows		
4. Unauthorized planting		
5. Cracking, bulging, or sliding of dam		
a) Upstream face		
b) Downstream face		
c) At or beyond toe		
• Downstream		
• Upstream		
d) Emergency spillway		
6. Pond, toe & chimney drains clear and functioning		
7. Seeps/leaks on downstream face		
8. Slope protection or riprap failure		
9. Vertical/horizontal alignment of top of dam "As-Built"		
10. Emergency spillway clear of obstructions and debris		
11. Other (specify)		

2. Riser and principal spillway		(Annual)
Type: Reinforced concrete		
- Corrugated pipe		
- Masonry		
1. Low flow orifice obstructed		
2. Low flow trash rack.		
a) Debris removal necessary		
b) Corrosion control		
3. Weir trash rack maintenance		
a) Debris removal necessary		
b) corrosion control		
4. Excessive sediment accumulation insider riser		
5. Concrete/masonry condition riser and barrels		
a) cracks or displacement		
b) Minor spalling (1")		
c) Major spalling (rebars exposed)		
d) Joint failures		
e) Water tightness		
6. Metal pipe condition		
7. Control valve		
a) Operational/exercised		
b) Chained and locked		
8. Pond drain valve		
a) Operational/exercised		
b) Chained and locked		
9. Outfall channels functioning		
10. Other (specify)		
3. Dry Pond Areas		
1. Vegetation adequate		
2. Undesirable vegetative growth		

3. Undesirable woody vegetation		
4. Low flow channels clear of obstructions		
5. Standing water or wet spots		
6. Sediment and / or trash accumulation		
7. Other (specify)		
4. Condition of Outfalls	(Annual, After Major Storms)	
1. Riprap failures		
2. Slope erosion		
3. Storm drain pipes		
4. Endwalls / Headwalls		
5. Other (specify)		
5. Other	(Annual)	
1. Encroachment on pond, wetland or easement area		
2. Complaints from residents		
3. Aesthetics		
a) Grass growing required		
b) Graffiti removal needed		
c) Other (specify)		
4. Conditions of maintenance access routes.		
5. Signs of hydrocarbon build-up		
6. Any public hazards (specify)		

ACTIONS TO BE TAKEN:

COMMENTS:

Appendix - E

MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

APPENDIX-E

CONSTRUCTION PLANS IN (11"X17") FORMAT

BY

ATZL, NASHER & ZIGLER

ENGINEERS-SURVEYORS-PLANNERS

232 NORTH MAIN STREET

NEW CITY, NY 10956



TEL: (845) 634-4694

FAX: (845) 634-5543

E-MAIL: rnasher@anzny.com

OWNERS WITHIN 500 FEET

7510-1-1	GENESE F & BRUCE E DEANGELO 163 BUCKS HOLLOW ROAD MAHOPAC, NY 10541	7510-1-11	TOWN OF CARMEL TAX MAP 131 DANIEL DRUMS TURNING MAHOPAC, NY 10541	7510-1-20	JAMES D & BRUCE A ZENKOWSKI 15 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-2	JOHN BARTON 157 BUCKS HOLLOW ROAD MAHOPAC, NY 10541	7510-1-12	MORRIS WOLF 3 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-21	YVONNE L & ANDREW C HONEY 17 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-3	JOHN NATIZIA 163 BUCKS HOLLOW ROAD MAHOPAC, NY 10541	7510-1-13	RONALD E & MARGARIT PARENTI 15 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-22	ANDREW & MARIA L CORNINE 16 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-4	VALERIO MESSIO LANGE TRUST 163 BUCKS HOLLOW ROAD MAHOPAC, NY 10541	7510-1-14	TOWN OF CARMEL 163 BUCKS HOLLOW ROAD MAHOPAC, NY 10541	7510-1-23	TRENDA & KRISTEN MOORE 14 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-5	DELA F & WALTER B WANGEL L D'AMICO/LLC 174 BUCKS HOLLOW ROAD MAHOPAC, NY 10541	7510-1-15	DAVID ROSS 22 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-24	ANDREW & CAROLAN LANDPARK 12 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-6	CHARLES MARIN INC 847 SOUTH LAKE ROAD MAHOPAC, NY 10541	7510-1-16	HARVEY JACOB LIE 23 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-25	JEANETTE L & ANDREW T OYER 14 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-7	SUTHER & BRUCE CARROLLS 163 BUCKS HOLLOW ROAD MAHOPAC, NY 10541	7510-1-17	FRANK JONES 70 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-26	EVY & APRIL J LAMIC 12 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-8	JAMES MCGARRE 100 BUCKS SALMON PLACE, NY 10541	7510-1-18	WYNN & NICHOL SPICER 38 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-27	SCOTT W OYER 40 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-9	BRUCE MCGARRE 100 BUCKS SALMON PLACE, NY 10541	7510-1-19	DONALD & LOUISE SACCHINELLO 40 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-28	JAMES QUARRY & NORMAN FRANZ 36 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-10	FULL STOP REALTY REALTY CORP. 100 BUCKS SALMON PLACE, NY 10541	7510-1-20	FRANK & LISA SIZALSKI 38 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-29	MATTHEW & KRISTEN REAPATED 36 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-11	WELTOP LANDS REALTY CORP. 100 BUCKS SALMON PLACE, NY 10541	7510-1-21	JOHN & LINDA WARRIS 38 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-30	DAVID & ANNE/ET AL 32 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-12	ANDREW DOWNS 441 HUNTER MAHOPAC, NY 10541	7510-1-22	LEONARD KOSKOWSKI & ORCA CORP 38 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-31	KEITH L & ANNET SCHWELBIL 38 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-13	FBI PROPERTIES, LLC 100 BUCKS SALMON PLACE, NY 10541	7510-1-23	JOHN & MELBA SIBING 38 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-32	JERRY & ANNETTA WOODS 38 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-14	TRENDA & KRISTEN MOORE 163 BUCKS HOLLOW ROAD MAHOPAC, NY 10541	7510-1-24	MARION FRONCH & BONNIE 38 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-33	MATTHEW & SARAH/ET AL CLARK 34 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-15	TRENDA & KRISTEN MOORE 163 BUCKS HOLLOW ROAD MAHOPAC, NY 10541	7510-1-25	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-34	DOUG MCGARRE 16 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-16	SCOTT FRONCH 427 BUCKS MAHOPAC, NY 10541	7510-1-26	ANDREW & LISA FRONCH 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-35	ANDREW & LISA FRONCH 74 ASTOR DRIVE MAHOPAC, NY 10541
7510-1-17	SCOTT FRONCH 427 BUCKS MAHOPAC, NY 10541	7510-1-27	JOHN & PHYLIS LAMPO 15 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-36	JOSEPH W & MARILYN L CHANDLER-WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-18	JACQUE REALTY CORP. 847 SOUTH LAKE ROAD MAHOPAC, NY 10541	7510-1-28	DAVID LAMBERT WIFE TRUST 15 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-37	PETER J & ROSALEA 12 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-19	MORIS REAL ESTATE LLC 100 BUCKS SALMON PLACE, NY 10541	7510-1-29	MORIS REAL ESTATE LLC 100 BUCKS SALMON PLACE, NY 10541	7510-1-38	JERRY A & MARLENE A FRONCH 38 ASTOR DRIVE MAHOPAC, NY 10541
7510-1-20	FRANK & MELBA SIBING 38 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-30	DAVID BRUCE WILK 100 BUCKS SALMON PLACE, NY 10541	7510-1-39	ANDREW & LISA FRONCH 74 ASTOR DRIVE MAHOPAC, NY 10541
7510-1-21	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-31	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-40	ALL BOWELL 12 NOTHMAN WAY MAHOPAC, NY 10541
7510-1-22	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-32	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-41	DELOTTED FAULTY TRUST 17 CONVENTY DR MAHOPAC, NY 10541
7510-1-23	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-33	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-42	MARILYN OYER 16 CONVENTY DR MAHOPAC, NY 10541
7510-1-24	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-34	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-43	DAVID & JENNY WILSON 12 CONVENTY DR MAHOPAC, NY 10541
7510-1-25	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-35	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-44	ALVIN ZENKOWSKI 17 CONVENTY DR MAHOPAC, NY 10541
7510-1-26	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-36	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-45	WYNN & NICHOL SPICER 38 ASTOR DRIVE MAHOPAC, NY 10541
7510-1-27	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-37	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-46	DAVID & JENNY WILSON 12 CONVENTY DR MAHOPAC, NY 10541
7510-1-28	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-38	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-47	ALVIN ZENKOWSKI 17 CONVENTY DR MAHOPAC, NY 10541
7510-1-29	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-39	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-48	WYNN & NICHOL SPICER 38 ASTOR DRIVE MAHOPAC, NY 10541
7510-1-30	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-40	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-49	DAVID & JENNY WILSON 12 CONVENTY DR MAHOPAC, NY 10541
7510-1-31	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-41	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-50	ALVIN ZENKOWSKI 17 CONVENTY DR MAHOPAC, NY 10541
7510-1-32	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-42	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-51	WYNN & NICHOL SPICER 38 ASTOR DRIVE MAHOPAC, NY 10541
7510-1-33	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-43	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-52	DAVID & JENNY WILSON 12 CONVENTY DR MAHOPAC, NY 10541
7510-1-34	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-44	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-53	ALVIN ZENKOWSKI 17 CONVENTY DR MAHOPAC, NY 10541
7510-1-35	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-45	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-54	WYNN & NICHOL SPICER 38 ASTOR DRIVE MAHOPAC, NY 10541
7510-1-36	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-46	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-55	DAVID & JENNY WILSON 12 CONVENTY DR MAHOPAC, NY 10541
7510-1-37	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-47	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-56	ALVIN ZENKOWSKI 17 CONVENTY DR MAHOPAC, NY 10541
7510-1-38	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-48	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-57	WYNN & NICHOL SPICER 38 ASTOR DRIVE MAHOPAC, NY 10541
7510-1-39	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-49	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-58	DAVID & JENNY WILSON 12 CONVENTY DR MAHOPAC, NY 10541
7510-1-40	DAVID & ROSALEA WOOD 14 NOTHMAN WAY MAHOPAC, NY 10541	7510-1-50	FRANKIE DENISE BERRY TRUST 74 ASTOR DRIVE MAHOPAC, NY 10541	7510-1-59	ALVIN ZENKOWSKI 17 CONVENTY DR MAHOPAC, NY 10541



TAX MAP REFERENCE:
TOWN OF CARMEL TAX MAP
163 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

DATE: 1998
REVISION: 1998
SCALE: 1" = 200'

PREPARED BY: ATZEL, NASHER & ZIGLER P.C.
200 North Main Street
New City, New York 10954
Tel: (914) 831-4894
Fax: (914) 834-1563
E-mail: info@atnz.com
Web: www.atnz.com

PROJECT: MAHOPAC WELLS 1, 2 & 3

TOWN OF CARMEL, NY

LOCATION MAP

DATE: 1998
REVISION: 1998
SCALE: 1" = 200'

PREPARED BY: ATZEL, NASHER & ZIGLER P.C.
200 North Main Street
New City, New York 10954
Tel: (914) 831-4894
Fax: (914) 834-1563
E-mail: info@atnz.com
Web: www.atnz.com

PROJECT: MAHOPAC WELLS 1, 2 & 3

TOWN OF CARMEL, NY


LOCATION MAP

DATE: 1998
REVISION: 1998
SCALE: 1" = 200'

PREPARED BY: ATZEL, NASHER & ZIGLER P.C.
200 North Main Street
New City, New York 10954
Tel: (914) 831-4894
Fax: (914) 834-1563
E-mail: info@atnz.com
Web: www.atnz.com


NO.	DATE	DESCRIPTION
1	04-08-24	DIVY PIONEER & LIMIT OF DISTURBANCE
2	02-12-24	LIMIT OF DISTURBANCE PER TOWN ENGINEER
3	01-19-24	CHANGE WELLS PER RECORD LAYOUT
4	02-02-22	DRAINAGE DESIGN PER POLLUTION TEST
5	02-03-22	PER PLANNING BOARD 3-10-22
6	02-07-22	PER 2-3-22 ECR JETTING
7	01-15-22	PER PG WELLS 1-13-22, PER CSR & PG REMEDIATION
8	11-13-21	PER PG WELLS 8-12-21

Drawn by: JG
Checked by: JG
Date: 08/11/2021
Project No: 4870
Sheet No: LM



CANTILEVER CONCRETE RETAINING WALL DETAIL
SCALE 1/4\"/>


- NOTES:**
1. ALL CONCRETE SHALL BE CAST IN PLACE AND CONSTRUCTION PROCEDURES SHALL BE IN ACCORDANCE WITH AC STANDARD SPEC.
 2. CONCRETE SHALL BE CAPABLE OF DEVELOPING A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI AT 28 DAYS.
 3. REINFORCING BARS SHALL BE STAINLESS STEEL TYPE 304. ALL REINFORCING BARS SHALL BE WELDED TOGETHER AT ALL INTERSECTIONS UNLESS OTHERWISE NOTED. ALL REINFORCING BARS SHALL BE ANCHORED WITH AC STANDARD SPEC.
 4. ALL REINFORCING BARS SHALL BE WELDED TOGETHER AT ALL INTERSECTIONS UNLESS OTHERWISE NOTED.
 5. FINISHES SHALL BE IN ACCORDANCE WITH AC STANDARD SPEC.
 6. ALL DIMENSIONS SHALL BE AS SHOWN UNLESS OTHERWISE NOTED.
 7. ALL DIMENSIONS SHALL BE AS SHOWN UNLESS OTHERWISE NOTED.




DRY POND FLOOR TILE GRAB DETAIL
SCALE 1/4\"/>




DRY POND PLAN VIEW
SCALE 1/4\"/>




SECTION A-A
SCALE 1/4\"/>



DYE RISER WITH DOME GRATE DETAIL
SCALE 1/4\"/>



STONE OUTLET DETAIL
SCALE 1/4\"/>



PROPOSED DRY POND PROFILE
SCALE 1/4\"/>



STATE OF NEW YORK
OFFICE OF THE ENGINEER
100 WEST STREET
ALBANY, NEW YORK 12242
TEL: (518) 487-2300
FAX: (518) 487-2301
WWW.STATE.NY.US/ENGINEER

1	04-09-21	REVISED
2	04-09-21	REVISED
3	04-09-21	REVISED
4	04-09-21	REVISED
5	04-09-21	REVISED
6	04-09-21	REVISED
7	04-09-21	REVISED
8	04-09-21	REVISED
9	04-09-21	REVISED
10	04-09-21	REVISED

ATEL, NASHER & BIGLER P.C.
ARCHITECTS-ENGINEERS-PLANNERS
222 South Main Street
New City, New York 10956
Tel: (914) 631-4000
Fax: (914) 631-4001
E-mail: aatel@atelny.com
Web: www.atepny.com

MAHOPAC WELLS 1, 2 & 3

TOWN OF CARMEL
PUTNAM COUNTY, NEW YORK

DETAILS

DATE: 04-09-21
DRAWN BY: [Name]
CHECKED BY: [Name]
SCALE: AS SHOWN

4870 5

Section 2: Drainage



MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

SECTION 2:

STORMWATER SYSTEM DESIGN REPORT COMPLYING WITH NYS STORMWATER MANAGEMENT DESIGN MANUAL JANUARY 2015

BY

ATZL, NASHER & ZIGLER
ENGINEERS-SURVEYORS-PLANNERS
232 NORTH MAIN STREET
NEW CITY, NY 10956
TEL: (845) 634-4694
FAX: (845) 634-5543
E-MAIL: rnasher@anzny.com



ATZL, NASHER & ZIGLER

ENGINEERS-SURVEYORS-PLANNERS

232 North Main Street, New City, NY 10956

Tel: (845) 634-4694

Fax: (845) 634-5543

Email: rnasher@anzny.com

Revision 4: April 9, 2024

Revision 3: January 19, 2024

Revision 2: May 02, 2022

Revision 1: September 30, 2021

August 27, 2021

Town of Carmel
60 McAlpin Avenue
Mahopac, NY 10541

Att.: Richard Franzetti, PE, LEED
Town Engineer

Ref.: Mahopac Wells 1, 2, & 3 (Job #4870)
Town of Carmel
Putnam County, New York

Sub: Hydraulic and Hydrological Study

1.0 REVISION OVERVIEW:

The previous SWPPP report dated January 19, 2024, proposed a dry pond system to achieve zero net increase of peak runoff. However, in order to minimize the limit of the disturbance a cantilever concrete wall has been proposed on the west side of the dry pond system. As a result, the volume provided by the dry pond has been revised accordingly. Regardless of the revision, the overall hydraulics of the SMP System remains the same.

1.1 INTRODUCTION:

The following hydraulic/hydrological study has been proposed for the above-mentioned project to provide zero net increase of peak runoff for the proposed project. The project disturbed area is 0.994 acres (43,300 sq.ft.), which is smaller than 1 acre. Therefore, a general construction permit is not required according to the NYSDEC 2015 version of the design manual. However, a zero-net increase of peak runoff is required per Town code.

1.2 SITE LOCATION:

The project is located at Bucks Hollow Road, ± 890 ft south of Astor Drive in the Town of Carmel, Putnam County, New York.

2.0 HYDROLOGICAL SOIL GROUP:

The soil onsite is the following, based on data from the Soil Survey of Putnam County, New York, dated October 1994.

Soil Name	Soil Map Symbol	Hydrological Soil Group
Charlton-Chatfield complex, 0 to 15 percent slopes, very rocky	CrC	B
Natchaug muck, 0 to 2 percent slopes	NcA	D
Sun loam	Sh	D

* Source: <https://websoilsurvey.sc.egov.usda.gov/App/WebSoilSurvey.aspx>

** HSG "B" was used in the drainage calculation.

3.1 EXISTING CONDITION:

The existing drainage area is 0.536 acres. The land cover of the drainage area consists of woods, gravel and grass area, plus some impervious area. The drainage area delineation is shown on the Existing Condition Drainage Map (E-1).

3.2 DEVELOPED CONDITION:

The proposed development includes the construction of a building and an increase in the gravel coverage. The peak runoff from the study area will be increased upon completion of the proposed development. The drainage area delineation is shown on the Developed Condition Drainage Map (D-1).

4.0 DRAINAGE STUDY:

Due to the proposed improvement the peak runoff of the designated drainage area will be increased. The hydrological software, HydroCAD has been used to calculate pre and post peak runoff rates for 1, 10, 100-year design storm events.


5.0 MITIGATION MEASURES:

To attenuate the post-developed peak flow to pre-developed peak flow, we are proposing a Dry Pond System. The Westchester Method was used to calculate the 10-year storm maximum storage.

The drainage study shows that the required 10-year storage for the site is 1,187.0 cu.ft. The Dry Pond System provides 1,213.0 cu.ft (@ELV= 582.50'), which is more than the required volume. The software HydroCAD was used to calculate peak flows for different storm events at the outlet "Point of Interest", for the Existing and Developed Condition. The summary table for the peak flow of different storm frequencies (1, 10, & 100-year storms) at the point of interest (P.O.I.), and water quantity design calculations are attached for your reference.

If you have further questions or concerns, feel free to contact me. Thank you.

Very Truly Yours,



Ryan A. Nasher, P.E.

P:\STORMWATER MANAGEMENT\4870\Current SWPPP Report\Section 2 - Drainage\4870 Drainage Report.docx

Summary Table

MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

SUMMARY TABLE

BY

ATZL, NASHER & ZIGLER
ENGINEERS-SURVEYORS-PLANNERS
232 NORTH MAIN STREET
NEW CITY, NY 10956
TEL: (845) 634-4694
FAX: (845) 634-5543
E-MAIL: rnasher@anzny.com

SUMMARY FLOW
EXISTING AND DEVELOPED CONDITIONS
1, 10, & 100 YEAR STORMS PEAK RUNOFF

STORM FREQUENCY (YEAR)	EXISTING CONDITION PEAK FLOW (CFS) (PER HYDROCAD)	DEVELOPED CONDITION PEAK FLOW, NO ROUTING (CFS) (PER HYDROCAD)	CHANGE IN FLOW, ΔQ (CFS)	REMARK
1	0.16	0.39	+0.23	*
10	0.95	1.37	+0.42	*
100	2.81	3.40	+0.59	*

* Note: Zero net increase of peak runoff will be achieved by the proposed Dry Pond System. The location of the system is shown on the site plan drawings.

Location Maps

MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

LOCATION MAPS

BY

ATZL, NASHER & ZIGLER
ENGINEERS-SURVEYORS-PLANNERS
232 NORTH MAIN STREET
NEW CITY, NY 10956
TEL: (845) 634-4694
FAX: (845) 634-5543
E-MAIL: rnasher@anzny.com



STREET MAP



NORTH



Source: <http://websoilsurvey.sc.egov.usda.gov/App/WebSoilSurvey.aspx>

SOIL MAP

Drainage Calculations



MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

DRAINAGE CALCULATION

BY

ATZL, NASHER & ZIGLER
ENGINEERS-SURVEYORS-PLANNERS
232 NORTH MAIN STREET
NEW CITY, NY 10956
TEL: (845) 634-4694
FAX: (845) 634-5543
E-MAIL: rnasher@anzny.com

EXISTING CONDITION:

The existing area of interest consists of one watershed (WS#1), with an area of about 0.536 acres. The site consists of woods/grass and gravel, plus some impervious areas. The drainage area is delineated on the Existing Condition Drainage Map (E-1).

WS#1E:

The soil within WS#1E belongs to Hydrological Soil Group "B".

Composition	HSG "B"
A_{Gravel}	0.116 acres
$A_{Impervious}$	0.01 acres
$A_{Wood/Grass}$	0.41 acres

A = 0.536 Acres

Due to the small size of the watershed, the time of concentration is considered the minimum of 0.1 hours.

WS#1E → P.O.I.#1

DEVELOPED CONDITION:

Upon development of the site, the total area of the developed watershed will remain the same as the existing watershed area (0.536 acres). The developed condition consists of the construction of a building and an increase in gravel coverage. The watershed area is delineated on the Developed Condition Drainage Map (D-1).

WS#1D:

The soil within WS#1D belongs to Hydrological Soil Group "B".

Composition	HSG "B"
A_{Gravel}	0.194 acres
$A_{Impervious}$	0.048 acres
$A_{Wood/Grass}$	0.294 acres

A = 0.536 Acres

Due to the small size of the watershed, the time of concentration is considered the minimum of 0.1 hours.

ROOFTOP → DRY POND SYSTEM → P.O.I.#1.

WS#1D → P.O.I.#1.

SMP Design



MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

STORMWATER MANAGEMENT PRACTICE DESIGN CALCULATIONS

BY

ATZL, NASHER & ZIGLER
ENGINEERS-SURVEYORS-PLANNERS
232 NORTH MAIN STREET
NEW CITY, NY 10956
TEL: (845) 634-4694
FAX: (845) 634-5543
E-MAIL: rnasher@anzny.com

WATER QUANTITY CALCULATION
WESTCHESTER METHOD

1. Select Design Storm

(Use 1-Year, 24-Hour Storm)

Total Rainfall = 4.90 inches

2. Calculate The Storage Volume (Vs):

10-Year, 24-Hour Rainfall = 4.90 inches

Soil: Hydrologic Soil Group (HSG) is "B", see attached Soil Survey Map.

Existing CN (WS#1E) = 65, $(Q_E)_{10} = 0.95$ cfs (Hydrocad, attached)

Runoff depth = 1.59 inches

Proposed CN (WS#1D) = 73, $(Q_D)_{10} = 1.37$ cfs (Hydrocad, attached)

Runoff depth = 2.20 inches

Drainage Area = 23,349 ft²

$$\Delta Vr = 2.20 \text{ in} - 1.59 \text{ in} = 0.61 \text{ in}$$

$$\Delta Vr = 0.61 \text{ in} * \frac{1 \text{ ft}}{12 \text{ in}}$$

$$\Delta Vr = 0.05 \text{ ft}$$

$$V_S = \Delta Vr * Area$$

$$V_S = 0.05 \text{ ft} * 23,349 \text{ ft}^2$$

$$V_S = 1,187.0 \text{ ft}^3$$

The 10-year storm storage volume is 1,187.0 ft³

SMP SIZING CALCULATION


In order to provide zero net increase of peak runoff a dry pond system has been proposed. The storage is calculated as 1,187.0 cu.ft. for the entire WS#1.

Calculate Provided Storage Volume:

The Dry Pond has the following characteristics:

- 31" deep
- 9" of ¾" gravel (porosity = 0.4) on bottom
- 4" of soil (porosity = 0.2) above the gravel
- 18" of freeboard between the top of the catch basin to the surface of the soil

A cross-sectional, not to scale sketch of the dry pond system is shown below:



DRY POND CROSS SECTION

N.T.S.

Void space in the dry pond cross-section:

$$= A1 \text{ (Void area above-ground)} + A2 \text{ (Void area in planting soil)} + A3 \text{ (Void area in gravel)}$$

$$= \left[(1.5') \left(\frac{1}{2} \right) (13.0' + 11.0') \right] + (0.2)(13.0')(0.33') + (0.4)(13.0')(0.83')$$

$$= 23.17 \text{ ft}^2$$

Required width of the dry pond: 24.0 ft

Required dry pond length (total):

$$= \frac{1,187.0 \text{ ft}^3}{24.0 \text{ ft}^2} = 49.5 \text{ ft}$$

Required length of the dry pond: 50.0 ft

Use one (1) dry pond. Required dimensions of the dry pond:

50.0 ft (Length) x 24.0 ft (Width)

Provided Storage:

$$= (50.0 \text{ ft})(24.0 \text{ ft}^2) \\ = 1,200.0 \text{ ft}^3$$

Note: HydroCAD was used to calculate the actual storage provided by the proposed system.

The proposed Dry Pond will provide 1,213.0 ft³ (@ ELV= 582.50') > 1,187.0 ft³

OK✓

(Please see HydroCAD for detailed calculations)

HydroCAD Model

MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

HYDROCAD MODEL FOR EXISTING AND PROPOSED CONDITIONS 1, 10, AND 100 YEAR STORMS

BY

ATZL, NASHER & ZIGLER
ENGINEERS-SURVEYORS-PLANNERS
232 NORTH MAIN STREET
NEW CITY, NY 10956
TEL: (845) 634-4694
FAX: (845) 634-5543
E-MAIL: rnasher@anzny.com

EXISTING
CONDITIONS

DEVELOPED
CONDITIONS



EXISTING



DEVELOPED



DRY DETENTION
BASIN



4870 Mahopac Wells 1, 2, & 3

Type III 24-hr 1-Year Rainfall=2.73"

Prepared by ATZL NASHER & ZIGLER

Printed 4/10/2024

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Page 2

Time span=0.00-30.00 hrs, dt=0.01 hrs, 3001 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment WS#1D: DEVELOPED

Runoff Area=0.536 ac 8.96% Impervious Runoff Depth=0.70"
Tc=6.0 min CN=73 Runoff=0.39 cfs 0.031 af

Subcatchment WS#1E: EXISTING

Runoff Area=0.536 ac 1.87% Impervious Runoff Depth=0.39"
Tc=6.0 min CN=65 Runoff=0.16 cfs 0.017 af

Pond SMP: DRY DETENTION BASIN

Peak Elev=0.00' Storage=0 cf

Total Runoff Area = 1.072 ac Runoff Volume = 0.048 af Average Runoff Depth = 0.54"
94.59% Pervious = 1.014 ac 5.41% Impervious = 0.058 ac

Summary for Subcatchment WS#1D: DEVELOPED


Runoff = 0.39 cfs @ 12.10 hrs, Volume= 0.031 af, Depth= 0.70"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.01 hrs
 Type III 24-hr 1-Year Rainfall=2.73"

Area (ac)	CN	Description
0.194	85	Gravel roads, HSG B
0.048	98	Paved parking, HSG B
0.294	61	>75% Grass cover, Good, HSG B
0.536	73	Weighted Average
0.488		91.04% Pervious Area
0.048		8.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment WS#1D: DEVELOPED



Summary for Subcatchment WS#1E: EXISTING

Runoff = 0.16 cfs @ 12.12 hrs, Volume= 0.017 af, Depth= 0.39"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.01 hrs
 Type III 24-hr 1-Year Rainfall=2.73"

Area (ac)	CN	Description
0.116	85	Gravel roads, HSG B
0.010	98	Paved parking, HSG B
0.410	58	Woods/grass comb., Good, HSG B
0.536	65	Weighted Average
0.526		98.13% Pervious Area
0.010		1.87% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment WS#1E: EXISTING

Hydrograph



Summary for Pond SMP: DRY DETENTION BASIN

Volume	Invert	Avail.Storage	Storage Description
#1	579.83'	1,562 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
579.83	717	0.0	0	0
580.67	717	40.0	241	241
581.00	565	20.0	42	283
581.01	565	100.0	6	289
582.00	638	100.0	595	884
583.00	717	100.0	678	1,562

4870 Mahopac Wells 1, 2, & 3

Type III 24-hr 1-Year Rainfall=2.73"

Prepared by ATZL NASHER & ZIGLER

Printed 4/10/2024

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Page 6

Stage-Discharge for Pond SMP: DRY DETENTION BASIN

Elevation (feet)	Discharge (cfs)	Elevation (feet)	Discharge (cfs)	Elevation (feet)	Discharge (cfs)
579.83	0.00	580.89	0.00	581.95	0.00
579.85	0.00	580.91	0.00	581.97	0.00
579.87	0.00	580.93	0.00	581.99	0.00
579.89	0.00	580.95	0.00	582.01	0.00
579.91	0.00	580.97	0.00	582.03	0.00
579.93	0.00	580.99	0.00	582.05	0.00
579.95	0.00	581.01	0.00	582.07	0.00
579.97	0.00	581.03	0.00	582.09	0.00
579.99	0.00	581.05	0.00	582.11	0.00
580.01	0.00	581.07	0.00	582.13	0.00
580.03	0.00	581.09	0.00	582.15	0.00
580.05	0.00	581.11	0.00	582.17	0.00
580.07	0.00	581.13	0.00	582.19	0.00
580.09	0.00	581.15	0.00	582.21	0.00
580.11	0.00	581.17	0.00	582.23	0.00
580.13	0.00	581.19	0.00	582.25	0.00
580.15	0.00	581.21	0.00	582.27	0.00
580.17	0.00	581.23	0.00	582.29	0.00
580.19	0.00	581.25	0.00	582.31	0.00
580.21	0.00	581.27	0.00	582.33	0.00
580.23	0.00	581.29	0.00	582.35	0.00
580.25	0.00	581.31	0.00	582.37	0.00
580.27	0.00	581.33	0.00	582.39	0.00
580.29	0.00	581.35	0.00	582.41	0.00
580.31	0.00	581.37	0.00	582.43	0.00
580.33	0.00	581.39	0.00	582.45	0.00
580.35	0.00	581.41	0.00	582.47	0.00
580.37	0.00	581.43	0.00	582.49	0.00
580.39	0.00	581.45	0.00	582.51	0.00
580.41	0.00	581.47	0.00	582.53	0.00
580.43	0.00	581.49	0.00	582.55	0.00
580.45	0.00	581.51	0.00	582.57	0.00
580.47	0.00	581.53	0.00	582.59	0.00
580.49	0.00	581.55	0.00	582.61	0.00
580.51	0.00	581.57	0.00	582.63	0.00
580.53	0.00	581.59	0.00	582.65	0.00
580.55	0.00	581.61	0.00	582.67	0.00
580.57	0.00	581.63	0.00	582.69	0.00
580.59	0.00	581.65	0.00	582.71	0.00
580.61	0.00	581.67	0.00	582.73	0.00
580.63	0.00	581.69	0.00	582.75	0.00
580.65	0.00	581.71	0.00	582.77	0.00
580.67	0.00	581.73	0.00	582.79	0.00
580.69	0.00	581.75	0.00	582.81	0.00
580.71	0.00	581.77	0.00	582.83	0.00
580.73	0.00	581.79	0.00	582.85	0.00
580.75	0.00	581.81	0.00	582.87	0.00
580.77	0.00	581.83	0.00	582.89	0.00
580.79	0.00	581.85	0.00	582.91	0.00
580.81	0.00	581.87	0.00	582.93	0.00
580.83	0.00	581.89	0.00	582.95	0.00
580.85	0.00	581.91	0.00	582.97	0.00
580.87	0.00	581.93	0.00	582.99	0.00

4870 Mahopac Wells 1, 2, & 3

Type III 24-hr 1-Year Rainfall=2.73"

Prepared by ATZL NASHER & ZIGLER

Printed 4/10/2024

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Page 7

Stage-Area-Storage for Pond SMP: DRY DETENTION BASIN

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
579.83	717	0	582.48	676	1,200
579.88	717	14	582.53	680	1,234
579.93	717	29	582.58	684	1,268
579.98	717	43	582.63	688	1,302
580.03	717	57	582.68	692	1,336
580.08	717	72	582.73	696	1,371
580.13	717	86	582.78	700	1,406
580.18	717	100	582.83	704	1,441
580.23	717	115	582.88	708	1,476
580.28	717	129	582.93	711	1,512
580.33	717	143	582.98	715	1,548
580.38	717	158			
580.43	717	172			
580.48	717	186			
580.53	717	201			
580.58	717	215			
580.63	717	229			
580.68	712	242			
580.73	689	249			
580.78	666	256			
580.83	643	263			
580.88	620	269			
580.93	597	275			
580.98	574	281			
581.03	566	300			
581.08	570	329			
581.13	574	357			
581.18	578	386			
581.23	581	415			
581.28	585	444			
581.33	589	473			
581.38	592	503			
581.43	596	533			
581.48	600	563			
581.53	603	593			
581.58	607	623			
581.63	611	653			
581.68	614	684			
581.73	618	715			
581.78	622	746			
581.83	625	777			
581.88	629	808			
581.93	633	840			
581.98	637	872			
582.03	640	904			
582.08	644	936			
582.13	648	968			
582.18	652	1,000			
582.23	656	1,033			
582.28	660	1,066			
582.33	664	1,099			
582.38	668	1,132			
582.43	672	1,166			

4870 Mahopac Wells 1, 2, & 3

Prepared by ATZL NASHER & ZIGLER

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.90"

Printed 4/10/2024

Page 8

Time span=0.00-30.00 hrs, dt=0.01 hrs, 3001 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment WS#1D: DEVELOPED

Runoff Area=0.536 ac 8.96% Impervious Runoff Depth=2.20"
Tc=6.0 min CN=73 Runoff=1.37 cfs 0.098 af

Subcatchment WS#1E: EXISTING

Runoff Area=0.536 ac 1.87% Impervious Runoff Depth=1.59"
Tc=6.0 min CN=65 Runoff=0.95 cfs 0.071 af

Pond SMP: DRY DETENTION BASIN

Peak Elev=0.00' Storage=0 cf

Total Runoff Area = 1.072 ac Runoff Volume = 0.169 af Average Runoff Depth = 1.89"
94.59% Pervious = 1.014 ac 5.41% Impervious = 0.058 ac

Summary for Subcatchment WS#1D: DEVELOPED


Runoff = 1.37 cfs @ 12.09 hrs, Volume= 0.098 af, Depth= 2.20"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=4.90"

Area (ac)	CN	Description
0.194	85	Gravel roads, HSG B
0.048	98	Paved parking, HSG B
0.294	61	>75% Grass cover, Good, HSG B
0.536	73	Weighted Average
0.488		91.04% Pervious Area
0.048		8.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment WS#1D: DEVELOPED



Summary for Subcatchment WS#1E: EXISTING


Runoff = 0.95 cfs @ 12.10 hrs, Volume= 0.071 af, Depth= 1.59"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.01 hrs
 Type III 24-hr 10-Year Rainfall=4.90"

Area (ac)	CN	Description
0.116	85	Gravel roads, HSG B
0.010	98	Paved parking, HSG B
0.410	58	Woods/grass comb., Good, HSG B
0.536	65	Weighted Average
0.526		98.13% Pervious Area
0.010		1.87% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment WS#1E: EXISTING



4870 Mahopac Wells 1, 2, & 3

Type III 24-hr 10-Year Rainfall=4.90"

Prepared by ATZL NASHER & ZIGLER

Printed 4/10/2024

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Page 11

Summary for Pond SMP: DRY DETENTION BASIN

Volume	Invert	Avail.Storage	Storage Description	
#1	579.83'	1,562 cf	Custom Stage Data (Prismatic) Listed below (Recalc)	
Elevation (feet)	Surf.Area (sq-ft)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
579.83	717	0.0	0	0
580.67	717	40.0	241	241
581.00	565	20.0	42	283
581.01	565	100.0	6	289
582.00	638	100.0	595	884
583.00	717	100.0	678	1,562

4870 Mahopac Wells 1, 2, & 3

Type III 24-hr 10-Year Rainfall=4.90"

Prepared by ATZL NASHER & ZIGLER

Printed 4/10/2024

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Page 12

Stage-Discharge for Pond SMP: DRY DETENTION BASIN

Elevation (feet)	Discharge (cfs)	Elevation (feet)	Discharge (cfs)	Elevation (feet)	Discharge (cfs)
579.83	0.00	580.89	0.00	581.95	0.00
579.85	0.00	580.91	0.00	581.97	0.00
579.87	0.00	580.93	0.00	581.99	0.00
579.89	0.00	580.95	0.00	582.01	0.00
579.91	0.00	580.97	0.00	582.03	0.00
579.93	0.00	580.99	0.00	582.05	0.00
579.95	0.00	581.01	0.00	582.07	0.00
579.97	0.00	581.03	0.00	582.09	0.00
579.99	0.00	581.05	0.00	582.11	0.00
580.01	0.00	581.07	0.00	582.13	0.00
580.03	0.00	581.09	0.00	582.15	0.00
580.05	0.00	581.11	0.00	582.17	0.00
580.07	0.00	581.13	0.00	582.19	0.00
580.09	0.00	581.15	0.00	582.21	0.00
580.11	0.00	581.17	0.00	582.23	0.00
580.13	0.00	581.19	0.00	582.25	0.00
580.15	0.00	581.21	0.00	582.27	0.00
580.17	0.00	581.23	0.00	582.29	0.00
580.19	0.00	581.25	0.00	582.31	0.00
580.21	0.00	581.27	0.00	582.33	0.00
580.23	0.00	581.29	0.00	582.35	0.00
580.25	0.00	581.31	0.00	582.37	0.00
580.27	0.00	581.33	0.00	582.39	0.00
580.29	0.00	581.35	0.00	582.41	0.00
580.31	0.00	581.37	0.00	582.43	0.00
580.33	0.00	581.39	0.00	582.45	0.00
580.35	0.00	581.41	0.00	582.47	0.00
580.37	0.00	581.43	0.00	582.49	0.00
580.39	0.00	581.45	0.00	582.51	0.00
580.41	0.00	581.47	0.00	582.53	0.00
580.43	0.00	581.49	0.00	582.55	0.00
580.45	0.00	581.51	0.00	582.57	0.00
580.47	0.00	581.53	0.00	582.59	0.00
580.49	0.00	581.55	0.00	582.61	0.00
580.51	0.00	581.57	0.00	582.63	0.00
580.53	0.00	581.59	0.00	582.65	0.00
580.55	0.00	581.61	0.00	582.67	0.00
580.57	0.00	581.63	0.00	582.69	0.00
580.59	0.00	581.65	0.00	582.71	0.00
580.61	0.00	581.67	0.00	582.73	0.00
580.63	0.00	581.69	0.00	582.75	0.00
580.65	0.00	581.71	0.00	582.77	0.00
580.67	0.00	581.73	0.00	582.79	0.00
580.69	0.00	581.75	0.00	582.81	0.00
580.71	0.00	581.77	0.00	582.83	0.00
580.73	0.00	581.79	0.00	582.85	0.00
580.75	0.00	581.81	0.00	582.87	0.00
580.77	0.00	581.83	0.00	582.89	0.00
580.79	0.00	581.85	0.00	582.91	0.00
580.81	0.00	581.87	0.00	582.93	0.00
580.83	0.00	581.89	0.00	582.95	0.00
580.85	0.00	581.91	0.00	582.97	0.00
580.87	0.00	581.93	0.00	582.99	0.00

4870 Mahopac Wells 1, 2, & 3

Prepared by ATZL NASHER & ZIGLER

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.90"

Printed 4/10/2024

Page 13

Stage-Area-Storage for Pond SMP: DRY DETENTION BASIN

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
579.83	717	0	582.48	676	1,200
579.88	717	14	582.53	680	1,234
579.93	717	29	582.58	684	1,268
579.98	717	43	582.63	688	1,302
580.03	717	57	582.68	692	1,336
580.08	717	72	582.73	696	1,371
580.13	717	86	582.78	700	1,406
580.18	717	100	582.83	704	1,441
580.23	717	115	582.88	708	1,476
580.28	717	129	582.93	711	1,512
580.33	717	143	582.98	715	1,548
580.38	717	158			
580.43	717	172			
580.48	717	186			
580.53	717	201			
580.58	717	215			
580.63	717	229			
580.68	712	242			
580.73	689	249			
580.78	666	256			
580.83	643	263			
580.88	620	269			
580.93	597	275			
580.98	574	281			
581.03	566	300			
581.08	570	329			
581.13	574	357			
581.18	578	386			
581.23	581	415			
581.28	585	444			
581.33	589	473			
581.38	592	503			
581.43	596	533			
581.48	600	563			
581.53	603	593			
581.58	607	623			
581.63	611	653			
581.68	614	684			
581.73	618	715			
581.78	622	746			
581.83	625	777			
581.88	629	808			
581.93	633	840			
581.98	637	872			
582.03	640	904			
582.08	644	936			
582.13	648	968			
582.18	652	1,000			
582.23	656	1,033			
582.28	660	1,066			
582.33	664	1,099			
582.38	668	1,132			
582.43	672	1,166			

4870 Mahopac Wells 1, 2, & 3

Type III 24-hr 100-Year Rainfall=8.70"

Prepared by ATZL NASHER & ZIGLER

Printed 4/10/2024

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Page 14

Time span=0.00-30.00 hrs, dt=0.01 hrs, 3001 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment WS#1D: DEVELOPED

Runoff Area=0.536 ac 8.96% Impervious Runoff Depth=5.43"
Tc=6.0 min CN=73 Runoff=3.40 cfs 0.243 af

Subcatchment WS#1E: EXISTING

Runoff Area=0.536 ac 1.87% Impervious Runoff Depth=4.47"
Tc=6.0 min CN=65 Runoff=2.81 cfs 0.200 af

Pond SMP: DRY DETENTION BASIN

Peak Elev=0.00' Storage=0 cf

Total Runoff Area = 1.072 ac Runoff Volume = 0.442 af Average Runoff Depth = 4.95"
94.59% Pervious = 1.014 ac 5.41% Impervious = 0.058 ac

4870 Mahopac Wells 1, 2, & 3

Prepared by ATZL NASHER & ZIGLER

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.70"

Printed 4/10/2024

Page 15

Summary for Subcatchment WS#1D: DEVELOPED


Runoff = 3.40 cfs @ 12.09 hrs, Volume= 0.243 af, Depth= 5.43"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=8.70"

Area (ac)	CN	Description
0.194	85	Gravel roads, HSG B
0.048	98	Paved parking, HSG B
0.294	61	>75% Grass cover, Good, HSG B
0.536	73	Weighted Average
0.488		91.04% Pervious Area
0.048		8.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment WS#1D: DEVELOPED



Summary for Subcatchment WS#1E: EXISTING


Runoff = 2.81 cfs @ 12.09 hrs, Volume= 0.200 af, Depth= 4.47"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-30.00 hrs, dt= 0.01 hrs
 Type III 24-hr 100-Year Rainfall=8.70"

Area (ac)	CN	Description
0.116	85	Gravel roads, HSG B
0.010	98	Paved parking, HSG B
0.410	58	Woods/grass comb., Good, HSG B
0.536	65	Weighted Average
0.526		98.13% Pervious Area
0.010		1.87% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment WS#1E: EXISTING



4870 Mahopac Wells 1, 2, & 3

Type III 24-hr 100-Year Rainfall=8.70"

Prepared by ATZL NASHER & ZIGLER

Printed 4/10/2024

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Page 17

Summary for Pond SMP: DRY DETENTION BASIN

Volume	Invert	Avail.Storage	Storage Description	
#1	579.83'	1,562 cf	Custom Stage Data (Prismatic) Listed below (Recalc)	
Elevation (feet)	Surf.Area (sq-ft)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
579.83	717	0.0	0	0
580.67	717	40.0	241	241
581.00	565	20.0	42	283
581.01	565	100.0	6	289
582.00	638	100.0	595	884
583.00	717	100.0	678	1,562

4870 Mahopac Wells 1, 2, & 3

Type III 24-hr 100-Year Rainfall=8.70"

Prepared by ATZL NASHER & ZIGLER

Printed 4/10/2024

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Page 18

Stage-Discharge for Pond SMP: DRY DETENTION BASIN

Elevation (feet)	Discharge (cfs)	Elevation (feet)	Discharge (cfs)	Elevation (feet)	Discharge (cfs)
579.83	0.00	580.89	0.00	581.95	0.00
579.85	0.00	580.91	0.00	581.97	0.00
579.87	0.00	580.93	0.00	581.99	0.00
579.89	0.00	580.95	0.00	582.01	0.00
579.91	0.00	580.97	0.00	582.03	0.00
579.93	0.00	580.99	0.00	582.05	0.00
579.95	0.00	581.01	0.00	582.07	0.00
579.97	0.00	581.03	0.00	582.09	0.00
579.99	0.00	581.05	0.00	582.11	0.00
580.01	0.00	581.07	0.00	582.13	0.00
580.03	0.00	581.09	0.00	582.15	0.00
580.05	0.00	581.11	0.00	582.17	0.00
580.07	0.00	581.13	0.00	582.19	0.00
580.09	0.00	581.15	0.00	582.21	0.00
580.11	0.00	581.17	0.00	582.23	0.00
580.13	0.00	581.19	0.00	582.25	0.00
580.15	0.00	581.21	0.00	582.27	0.00
580.17	0.00	581.23	0.00	582.29	0.00
580.19	0.00	581.25	0.00	582.31	0.00
580.21	0.00	581.27	0.00	582.33	0.00
580.23	0.00	581.29	0.00	582.35	0.00
580.25	0.00	581.31	0.00	582.37	0.00
580.27	0.00	581.33	0.00	582.39	0.00
580.29	0.00	581.35	0.00	582.41	0.00
580.31	0.00	581.37	0.00	582.43	0.00
580.33	0.00	581.39	0.00	582.45	0.00
580.35	0.00	581.41	0.00	582.47	0.00
580.37	0.00	581.43	0.00	582.49	0.00
580.39	0.00	581.45	0.00	582.51	0.00
580.41	0.00	581.47	0.00	582.53	0.00
580.43	0.00	581.49	0.00	582.55	0.00
580.45	0.00	581.51	0.00	582.57	0.00
580.47	0.00	581.53	0.00	582.59	0.00
580.49	0.00	581.55	0.00	582.61	0.00
580.51	0.00	581.57	0.00	582.63	0.00
580.53	0.00	581.59	0.00	582.65	0.00
580.55	0.00	581.61	0.00	582.67	0.00
580.57	0.00	581.63	0.00	582.69	0.00
580.59	0.00	581.65	0.00	582.71	0.00
580.61	0.00	581.67	0.00	582.73	0.00
580.63	0.00	581.69	0.00	582.75	0.00
580.65	0.00	581.71	0.00	582.77	0.00
580.67	0.00	581.73	0.00	582.79	0.00
580.69	0.00	581.75	0.00	582.81	0.00
580.71	0.00	581.77	0.00	582.83	0.00
580.73	0.00	581.79	0.00	582.85	0.00
580.75	0.00	581.81	0.00	582.87	0.00
580.77	0.00	581.83	0.00	582.89	0.00
580.79	0.00	581.85	0.00	582.91	0.00
580.81	0.00	581.87	0.00	582.93	0.00
580.83	0.00	581.89	0.00	582.95	0.00
580.85	0.00	581.91	0.00	582.97	0.00
580.87	0.00	581.93	0.00	582.99	0.00

4870 Mahopac Wells 1, 2, & 3

Type III 24-hr 100-Year Rainfall=8.70"

Prepared by ATZL NASHER & ZIGLER

Printed 4/10/2024

HydroCAD® 10.00-20 s/n 03403 © 2017 HydroCAD Software Solutions LLC

Page 19

Stage-Area-Storage for Pond SMP: DRY DETENTION BASIN

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
579.83	717	0	582.48	676	1,200
579.88	717	14	582.53	680	1,234
579.93	717	29	582.58	684	1,268
579.98	717	43	582.63	688	1,302
580.03	717	57	582.68	692	1,336
580.08	717	72	582.73	696	1,371
580.13	717	86	582.78	700	1,406
580.18	717	100	582.83	704	1,441
580.23	717	115	582.88	708	1,476
580.28	717	129	582.93	711	1,512
580.33	717	143	582.98	715	1,548
580.38	717	158			
580.43	717	172			
580.48	717	186			
580.53	717	201			
580.58	717	215			
580.63	717	229			
580.68	712	242			
580.73	689	249			
580.78	666	256			
580.83	643	263			
580.88	620	269			
580.93	597	275			
580.98	574	281			
581.03	566	300			
581.08	570	329			
581.13	574	357			
581.18	578	386			
581.23	581	415			
581.28	585	444			
581.33	589	473			
581.38	592	503			
581.43	596	533			
581.48	600	563			
581.53	603	593			
581.58	607	623			
581.63	611	653			
581.68	614	684			
581.73	618	715			
581.78	622	746			
581.83	625	777			
581.88	629	808			
581.93	633	840			
581.98	637	872			
582.03	640	904			
582.08	644	936			
582.13	648	968			
582.18	652	1,000			
582.23	656	1,033			
582.28	660	1,066			
582.33	664	1,099			
582.38	668	1,132			
582.43	672	1,166			

Section 3 : NOI & MS4

MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

SECTION 3:

**SPDES ACKNOWLEDGEMENT LETTER,
FILLED OUT NOTICE OF INTENT (N.O.I.),
AND
MS4 SWPPP ACCEPTANCE FORM**

BY

ATZL, NASHER & ZIGLER

ENGINEERS-SURVEYORS-PLANNERS

232 NORTH MAIN STREET

NEW CITY, NY 10956

TEL: (845) 634-4694

FAX: (845) 634-5543

E-MAIL: rnasher@anzny.com

NOTICE OF INTENT



New York State Department of Environmental Conservation

Division of Water

625 Broadway, 4th Floor

Albany, New York 12233-3505

NYR

--	--	--	--	--

(for DEC use only)

Stormwater Discharges Associated with Construction Activity Under State Pollutant Discharge Elimination System (SPDES) General Permit # GP-0-20-001
 All sections must be completed unless otherwise noted. Failure to complete all items may result in this form being returned to you, thereby delaying your coverage under this General Permit. Applicants must read and understand the conditions of the permit and prepare a Stormwater Pollution Prevention Plan prior to submitting this NOI. Applicants are responsible for identifying and obtaining other DEC permits that may be required.

- IMPORTANT -

RETURN THIS FORM TO THE ADDRESS ABOVE

OWNER/OPERATOR MUST SIGN FORM

Owner/Operator Information

Owner/Operator (Company Name/Private Owner Name/Municipality Name)

S U E Z W A T E R N E W Y O R K , I N C

Owner/Operator Contact Person Last Name (NOT CONSULTANT)

G A R A B E D

Owner/Operator Contact Person First Name

S T E V E N

Owner/Operator Mailing Address

1 6 3 O L D M I L L R O A D

City

W E S T N Y A C K

State

N Y

Zip

1 0 9 9 4 -

Phone (Owner/Operator)

8 4 5 - 6 2 0 - 3 3 1 9

Fax (Owner/Operator)

- - - - -

Email (Owner/Operator)

S T E V E N . G A R A B E D @ S U E Z . C O M

FED TAX ID

- (not required for individuals)

Project Site Information

Project/Site Name

MAHOPAC WELLS 1, 2, & 3

Street Address (NOT P.O. BOX)

BUCKS HOLLOW ROAD

Side of Street

 North South East West

City/Town/Village (THAT ISSUES BUILDING PERMIT)

TOWN OF CARMEL

State Zip

NY

10541 -

County

PUTNAM

DEC Region

3

Name of Nearest Cross Street

ASTOR DRIVE

Distance to Nearest Cross Street (Feet)

890

Project In Relation to Cross Street

 North South East WestTax Map Numbers
Section-Block-Parcel

75.20 - 2 - 68

Tax Map Numbers

1. Provide the Geographic Coordinates for the project site. To do this, go to the NYSDEC Stormwater Interactive Map on the DEC website at:

<https://gisservices.dec.ny.gov/gis/stormwater/>

Zoom into your Project Location such that you can accurately click on the centroid of your site. Once you have located the centroid of your project site, go to the bottom right hand corner of the map for the X, Y coordinates. Enter the coordinates into the boxes below. For problems with the interactive map use the help function.

X Coordinates (Easting)

-7 3 7 4 0

Ex. -73.749

Y Coordinates (Northing)

4 1 3 6 0

Ex. 42.652

2. What is the nature of this construction project?

- New Construction
- Redevelopment with increase in impervious area
- Redevelopment with no increase in impervious area

3. Select the predominant land use for both pre and post development conditions.

SELECT ONLY ONE CHOICE FOR EACH

- Pre-Development Existing Land Use**
- FOREST
 - PASTURE/OPEN LAND
 - CULTIVATED LAND
 - SINGLE FAMILY HOME
 - SINGLE FAMILY SUBDIVISION
 - TOWN HOME RESIDENTIAL
 - MULTIFAMILY RESIDENTIAL
 - INSTITUTIONAL/SCHOOL
 - INDUSTRIAL
 - COMMERCIAL
 - ROAD/HIGHWAY
 - RECREATIONAL/SPORTS FIELD
 - BIKE PATH/TRAIL
 - LINEAR UTILITY
 - PARKING LOT
 - OTHER

W A T E R F A C I L I T Y

- Post-Development Future Land Use**
- SINGLE FAMILY HOME
 - SINGLE FAMILY SUBDIVISION Number of Lots
 - TOWN HOME RESIDENTIAL
 - MULTIFAMILY RESIDENTIAL
 - INSTITUTIONAL/SCHOOL
 - INDUSTRIAL
 - COMMERCIAL
 - MUNICIPAL
 - ROAD/HIGHWAY
 - RECREATIONAL/SPORTS FIELD
 - BIKE PATH/TRAIL
 - LINEAR UTILITY (water, sewer, gas, etc.)
 - PARKING LOT
 - CLEARING/GRADING ONLY
 - DEMOLITION, NO REDEVELOPMENT
 - WELL DRILLING ACTIVITY *(Oil, Gas, etc.)
 - OTHER

W A T E R F A C I L I T Y

*Note: for gas well drilling, non-high volume hydraulic fractured wells only

4. In accordance with the larger common plan of development or sale, enter the total project site area; the total area to be disturbed; existing impervious area to be disturbed (for redevelopment activities); and the future impervious area constructed within the disturbed area. (Round to the nearest tenth of an acre.)

Total Site Area	Total Area To Be Disturbed	Existing Impervious Area To Be Disturbed	Future Impervious Area Within Disturbed Area																								
<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;">5</td><td style="width: 20px; height: 20px;">3</td><td style="width: 20px; height: 20px;">.</td><td style="width: 20px; height: 20px;">4</td></tr> </table>			5	3	.	4	<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;">0</td><td style="width: 20px; height: 20px;">.</td><td style="width: 20px; height: 20px;">9</td></tr> </table>				0	.	9	<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;">0</td><td style="width: 20px; height: 20px;">.</td><td style="width: 20px; height: 20px;">1</td></tr> </table>				0	.	1	<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;">0</td><td style="width: 20px; height: 20px;">.</td><td style="width: 20px; height: 20px;">2</td></tr> </table>				0	.	2
		5	3	.	4																						
			0	.	9																						
			0	.	1																						
			0	.	2																						

5. Do you plan to disturb more than 5 acres of soil at any one time? Yes No

6. Indicate the percentage of each Hydrologic Soil Group (HSG) at the site.

<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td></tr> </table> A %				<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr><td style="width: 20px; height: 20px;">1</td><td style="width: 20px; height: 20px;">0</td><td style="width: 20px; height: 20px;">0</td></tr> </table> B %	1	0	0	<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td></tr> </table> C %				<table border="1" style="display: inline-table; border-collapse: collapse;"> <tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td></tr> </table> D %			
1	0	0													

7. Is this a phased project? Yes No

8. Enter the planned start and end dates of the disturbance activities.

Start Date <table border="1" style="display: inline-table; border-collapse: collapse;"> <tr><td style="width: 20px; height: 20px;">0</td><td style="width: 20px; height: 20px;">5</td><td style="width: 20px; height: 20px;">/</td><td style="width: 20px; height: 20px;">0</td><td style="width: 20px; height: 20px;">6</td><td style="width: 20px; height: 20px;">/</td><td style="width: 20px; height: 20px;">2</td><td style="width: 20px; height: 20px;">0</td><td style="width: 20px; height: 20px;">2</td><td style="width: 20px; height: 20px;">4</td></tr> </table>	0	5	/	0	6	/	2	0	2	4	-	End Date <table border="1" style="display: inline-table; border-collapse: collapse;"> <tr><td style="width: 20px; height: 20px;">0</td><td style="width: 20px; height: 20px;">5</td><td style="width: 20px; height: 20px;">/</td><td style="width: 20px; height: 20px;">0</td><td style="width: 20px; height: 20px;">9</td><td style="width: 20px; height: 20px;">/</td><td style="width: 20px; height: 20px;">2</td><td style="width: 20px; height: 20px;">0</td><td style="width: 20px; height: 20px;">2</td><td style="width: 20px; height: 20px;">5</td></tr> </table>	0	5	/	0	9	/	2	0	2	5
0	5	/	0	6	/	2	0	2	4													
0	5	/	0	9	/	2	0	2	5													

9. Identify the nearest surface waterbody(ies) to which construction site runoff will discharge.

Name

P L U M B R O O K

Grid for additional name information

9a. Type of waterbody identified in Question 9?

- Wetland / State Jurisdiction On Site (Answer 9b)
- Wetland / State Jurisdiction Off Site
- Wetland / Federal Jurisdiction On Site (Answer 9b)
- Wetland / Federal Jurisdiction Off Site
- Stream / Creek On Site
- Stream / Creek Off Site
- River On Site
- River Off Site
- Lake On Site
- Lake Off Site
- Other Type On Site
- Other Type Off Site

Grid for 'Other Type Off Site' answer

9b. How was the wetland identified?

- Regulatory Map
- Delineated by Consultant
- Delineated by Army Corps of Engineers
- Other (identify)

Grid for 'Other (identify)' answer

10. Has the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001? Yes No

11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? Yes No

12. Is the project located in one of the watershed areas associated with AA and AA-S classified waters? Yes No
If no, skip question 13.

13. Does this construction activity disturb land with no existing impervious cover and where the Soil Slope Phase is identified as an E or F on the USDA Soil Survey? Yes No
If Yes, what is the acreage to be disturbed?

Grid for acreage to be disturbed

14. Will the project disturb soils within a State regulated wetland or the protected 100 foot adjacent area? Yes No

Post-construction Stormwater Management Practice (SMP) Requirements

Important: Completion of Questions 27-39 is not required if response to Question 22 is No.

27. Identify all site planning practices that were used to prepare the final site plan/layout for the project.

- Preservation of Undisturbed Areas
- Preservation of Buffers
- Reduction of Clearing and Grading
- Locating Development in Less Sensitive Areas
- Roadway Reduction
- Sidewalk Reduction
- Driveway Reduction
- Cul-de-sac Reduction
- Building Footprint Reduction
- Parking Reduction

27a. Indicate which of the following soil restoration criteria was used to address the requirements in Section 5.1.6("Soil Restoration") of the Design Manual (2010 version).

- All disturbed areas will be restored in accordance with the Soil Restoration requirements in Table 5.3 of the Design Manual (see page 5-22).
- Compacted areas were considered as impervious cover when calculating the **WQv Required**, and the compacted areas were assigned a post-construction Hydrologic Soil Group (HSG) designation that is one level less permeable than existing conditions for the hydrology analysis.

28. Provide the total Water Quality Volume (WQv) required for this project (based on final site plan/layout).

Total WQv Required

. acre-feet

29. Identify the RR techniques (Area Reduction), RR techniques (Volume Reduction) and Standard SMPs with RRv Capacity in Table 1 (See Page 9) that were used to reduce the Total WQv Required(#28).

Also, provide in Table 1 the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

Note: Redevelopment projects shall use Tables 1 and 2 to identify the SMPs used to treat and/or reduce the WQv required. If runoff reduction techniques will not be used to reduce the required WQv, skip to question 33a after identifying the SMPs.

Table 1 - Runoff Reduction (RR) Techniques and Standard Stormwater Management Practices (SMPs)

<u>RR Techniques (Area Reduction)</u>	<u>Total Contributing Area (acres)</u>		<u>Total Contributing Impervious Area (acres)</u>	
<input type="checkbox"/> Conservation of Natural Areas (RR-1) ...	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
<input type="checkbox"/> Sheetflow to Riparian Buffers/Filters Strips (RR-2)	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
<input type="checkbox"/> Tree Planting/Tree Pit (RR-3)	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
<input type="checkbox"/> Disconnection of Rooftop Runoff (RR-4) ..	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
<u>RR Techniques (Volume Reduction)</u>				
<input type="checkbox"/> Vegetated Swale (RR-5)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Rain Garden (RR-6)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Stormwater Planter (RR-7)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Rain Barrel/Cistern (RR-8)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Porous Pavement (RR-9)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Green Roof (RR-10)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<u>Standard SMPs with RRv Capacity</u>				
<input type="checkbox"/> Infiltration Trench (I-1)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Infiltration Basin (I-2)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Dry Well (I-3)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Underground Infiltration System (I-4)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Bioretention (F-5)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Dry Swale (O-1)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<u>Standard SMPs</u>				
<input type="checkbox"/> Micropool Extended Detention (P-1)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Wet Pond (P-2)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Wet Extended Detention (P-3)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Multiple Pond System (P-4)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Pocket Pond (P-5)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Surface Sand Filter (F-1)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Underground Sand Filter (F-2)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Perimeter Sand Filter (F-3)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Organic Filter (F-4)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Shallow Wetland (W-1)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Extended Detention Wetland (W-2)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Pond/Wetland System (W-3)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Pocket Wetland (W-4)	<input type="text"/>	<input type="text"/>		<input type="text"/>
<input type="checkbox"/> Wet Swale (O-2)	<input type="text"/>	<input type="text"/>		<input type="text"/>

33. Identify the Standard SMPs in Table 1 and, if applicable, the Alternative SMPs in Table 2 that were used to treat the remaining total WQv(=Total WQv Required in 28 - Total RRv Provided in 30).

Also, provide in Table 1 and 2 the total impervious area that contributes runoff to each practice selected.

Note: Use Tables 1 and 2 to identify the SMPs used on Redevelopment projects.

- 33a. Indicate the Total WQv provided (i.e. WQv treated) by the SMPs identified in question #33 and Standard SMPs with RRv Capacity identified in question 29.

WQv Provided

. acre-feet

Note: For the standard SMPs with RRv capacity, the WQv provided by each practice = the WQv calculated using the contributing drainage area to the practice - RRv provided by the practice. (See Table 3.5 in Design Manual)

34. Provide the sum of the Total RRv provided (#30) and the WQv provided (#33a).

.

35. Is the sum of the RRv provided (#30) and the WQv provided (#33a) greater than or equal to the total WQv required (#28)? Yes No

If Yes, go to question 36.

If No, sizing criteria has not been met, so NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.

36. Provide the total Channel Protection Storage Volume (CPv) required and provided or select waiver (36a), if applicable.

CPv Required

. acre-feet

CPv Provided

. acre-feet

- 36a. The need to provide channel protection has been waived because:

- Site discharges directly to tidal waters or a fifth order or larger stream.
- Reduction of the total CPv is achieved on site through runoff reduction techniques or infiltration systems.

37. Provide the Overbank Flood (Qp) and Extreme Flood (Qf) control criteria or select waiver (37a), if applicable.

Total Overbank Flood Control Criteria (Qp)

Pre-Development

. CFS

Post-development

. CFS

Total Extreme Flood Control Criteria (Qf)

Pre-Development

. CFS

Post-development

. CFS



Department of
Environmental
Conservation

NYS Department of Environmental Conservation
Division of Water
625 Broadway, 4th Floor
Albany, New York 12233-3505

MS4 Stormwater Pollution Prevention Plan (SWPPP) Acceptance Form

for

Construction Activities Seeking Authorization Under SPDES General Permit
*(NOTE: Attach Completed Form to Notice Of Intent and Submit to Address Above)

I. Project Owner/Operator Information

1. Owner/Operator Name: SUEZ WATER NEW YORK, INC

2. Contact Person: STEVEN GARABED

3. Street Address: 163 OLD MILL ROAD

4. City/State/Zip: WEST NYACK / NY / 10994

II. Project Site Information

5. Project/Site Name: MAHOPAC WELLS 1, 2, & 3

6. Street Address: BUCKS HOLLOW ROAD

7. City/State/Zip: CARMEL / NY / 10541

III. Stormwater Pollution Prevention Plan (SWPPP) Review and Acceptance Information

8. SWPPP Reviewed by: RICHARD FRANZETTI, PE, LEED

9. Title/Position: TOWN ENGINEER

10. Date Final SWPPP Reviewed and Accepted:

IV. Regulated MS4 Information

11. Name of MS4: TOWN OF CARMEL

12. MS4 SPDES Permit Identification Number: NYR20A 294

13. Contact Person: RICHARD FRANZETTI, PE, LEED

14. Street Address: 60 MCALPIN AVENUE

15. City/State/Zip: MAHOPAC, NY 10541

16. Telephone Number: 845-628-1500

MS4 SWPPP Acceptance Form - continued

V. Certification Statement - MS4 Official (principal executive officer or ranking elected official) or Duly Authorized Representative

I hereby certify that the final Stormwater Pollution Prevention Plan (SWPPP) for the construction project identified in question 5 has been reviewed and meets the substantive requirements in the SPDES General Permit For Stormwater Discharges from Municipal Separate Storm Sewer Systems (MS4s).

Note: The MS4, through the acceptance of the SWPPP, assumes no responsibility for the accuracy and adequacy of the design included in the SWPPP. In addition, review and acceptance of the SWPPP by the MS4 does not relieve the owner/operator or their SWPPP preparer of responsibility or liability for errors or omissions in the plan.

Printed Name: RICHARD FRANZETTI, PE, LEED

Title/Position: TOWN ENGINEER

Signature:

Date:

VI. Additional Information

Appendix - F



MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

APPENDIX-F INFILTRATION TEST CERTIFICATION

BY

ATZL, NASHER & ZIGLER
ENGINEERS-SURVEYORS-PLANNERS
232 NORTH MAIN STREET
NEW CITY, NY 10956
TEL: (845) 634-4694
FAX: (845) 634-5543
E-MAIL: rnasher@anzny.com



ATZL, NASHER & ZIGLER P.C.

ENGINEERS-SURVEYORS-PLANNERS

232 North Main Street, New City, NY 10956

Tel: (845) 634-4694

Fax: (845) 634-5543

Email: rnasher@anzny.com

April 15, 2022

Town of Carmel
60 McAlpin Avenue
Mahopac, NY 10541

Attn: Richard Franzetti, PE, LEED
Town Engineer

Re: Infiltration Test Certification
Mahopac Wells 1, 2, & 3 (Job #4870)
Town of Carmel
Putnam County, New York

Dear Mr. Franzetti,

A soil infiltration test was performed on April 11, 2022. The infiltration test location map is attached to this report for your reference (Page F-5). The infiltration test failed due to the presence of groundwater.

The results are as follows.

Test Hole #1

Infiltration test was proposed at a depth of 72-inches (6-feet):

<u>Soil Log</u>	<u>Soil Type</u>
0" to 12"	Topsoil
12" to 96"	Silt & Sand

Groundwater was found at 72-inches (6-feet) deep, El.: 577.0.

Note: An infiltration practice is not acceptable on the site per the infiltration test.

If you have further questions or concerns, feel free to contact our office. Thank you.

Very Truly Yours,




Ryan A. Nasher, P.E.




Figure 1: View of deep test hole (Test Hole#1) at 72-inches deep and the 30-inch pvc pipe used to determine the infiltration rate.



Figure 2: View of the soil profile (Test Hole#1).



- NOTES**
1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A SAFE AND PROPER EXCAVATION OPERATION IN A MANNER SO THAT THE WORKERS, PUBLIC AND AUTHORITIES MAY BE PROTECTED FROM UNREASONABLE HAZARD.
 2. SLOPE SIDES OF EXCAVATIONS TO COMPLY WITH LOCAL CODES AND ORDINANCES REGARDING EROSION, SHIELD AND BRACE WHERE EROSION IS NOT POSSIBLE BECAUSE OF SPACE RESTRICTIONS OR STABILITY OF MATERIAL EXCAVATED. COMPLY WITH OSHA REQUIREMENTS.
 3. FOR THE SAFETY OF PERSONNEL, SHEETING SHALL BE USED AS REQUIRED IN ANY TRENCH OR EXCAVATION MORE THAN FIVE (5) FEET ABOVE THE PERSONNEL'S FOOTING.




TYPICAL INFILTRATION TEST CROSS SECTION

INFILTRATION AND DEEP TEST FOR STORMWATER MITIGATION PRACTICE

TEST HOLE DEPTH	EXISTING GRAVE EL.	INFILTRATION TEST DEPTH	DEEP TEST DEPTH
10'-0"	EL.=58.0	EL.=57.0	EL.=55.0 (2'-0")

LEGEND

---	EXISTING 1" CONDUIT
---	EXISTING 1/2" CONDUIT
---	EXISTING 3/4" CONDUIT
---	EXISTING 1" DUCT
---	EXISTING 1 1/2" DUCT
---	EXISTING 2" DUCT
---	EXISTING 3" DUCT
---	EXISTING 4" DUCT
---	EXISTING 6" DUCT
---	EXISTING 8" DUCT
---	EXISTING 10" DUCT
---	EXISTING 12" DUCT
---	EXISTING 15" DUCT
---	EXISTING 18" DUCT
---	EXISTING 24" DUCT
---	EXISTING 30" DUCT
---	EXISTING 36" DUCT
---	EXISTING 42" DUCT
---	EXISTING 48" DUCT
---	EXISTING 54" DUCT
---	EXISTING 60" DUCT
---	EXISTING 66" DUCT
---	EXISTING 72" DUCT
---	EXISTING 78" DUCT
---	EXISTING 84" DUCT
---	EXISTING 90" DUCT
---	EXISTING 96" DUCT
---	EXISTING 102" DUCT
---	EXISTING 108" DUCT
---	EXISTING 114" DUCT
---	EXISTING 120" DUCT
---	EXISTING 126" DUCT
---	EXISTING 132" DUCT
---	EXISTING 138" DUCT
---	EXISTING 144" DUCT
---	EXISTING 150" DUCT
---	EXISTING 156" DUCT
---	EXISTING 162" DUCT
---	EXISTING 168" DUCT
---	EXISTING 174" DUCT
---	EXISTING 180" DUCT
---	EXISTING 186" DUCT
---	EXISTING 192" DUCT
---	EXISTING 198" DUCT
---	EXISTING 204" DUCT
---	EXISTING 210" DUCT
---	EXISTING 216" DUCT
---	EXISTING 222" DUCT
---	EXISTING 228" DUCT
---	EXISTING 234" DUCT
---	EXISTING 240" DUCT
---	EXISTING 246" DUCT
---	EXISTING 252" DUCT
---	EXISTING 258" DUCT
---	EXISTING 264" DUCT
---	EXISTING 270" DUCT
---	EXISTING 276" DUCT
---	EXISTING 282" DUCT
---	EXISTING 288" DUCT
---	EXISTING 294" DUCT
---	EXISTING 300" DUCT
---	EXISTING 306" DUCT
---	EXISTING 312" DUCT
---	EXISTING 318" DUCT
---	EXISTING 324" DUCT
---	EXISTING 330" DUCT
---	EXISTING 336" DUCT
---	EXISTING 342" DUCT
---	EXISTING 348" DUCT
---	EXISTING 354" DUCT
---	EXISTING 360" DUCT
---	EXISTING 366" DUCT
---	EXISTING 372" DUCT
---	EXISTING 378" DUCT
---	EXISTING 384" DUCT
---	EXISTING 390" DUCT
---	EXISTING 396" DUCT
---	EXISTING 402" DUCT
---	EXISTING 408" DUCT
---	EXISTING 414" DUCT
---	EXISTING 420" DUCT
---	EXISTING 426" DUCT
---	EXISTING 432" DUCT
---	EXISTING 438" DUCT
---	EXISTING 444" DUCT
---	EXISTING 450" DUCT
---	EXISTING 456" DUCT
---	EXISTING 462" DUCT
---	EXISTING 468" DUCT
---	EXISTING 474" DUCT
---	EXISTING 480" DUCT
---	EXISTING 486" DUCT
---	EXISTING 492" DUCT
---	EXISTING 498" DUCT
---	EXISTING 504" DUCT
---	EXISTING 510" DUCT
---	EXISTING 516" DUCT
---	EXISTING 522" DUCT
---	EXISTING 528" DUCT
---	EXISTING 534" DUCT
---	EXISTING 540" DUCT
---	EXISTING 546" DUCT
---	EXISTING 552" DUCT
---	EXISTING 558" DUCT
---	EXISTING 564" DUCT
---	EXISTING 570" DUCT
---	EXISTING 576" DUCT
---	EXISTING 582" DUCT
---	EXISTING 588" DUCT
---	EXISTING 594" DUCT
---	EXISTING 600" DUCT
---	EXISTING 606" DUCT
---	EXISTING 612" DUCT
---	EXISTING 618" DUCT
---	EXISTING 624" DUCT
---	EXISTING 630" DUCT
---	EXISTING 636" DUCT
---	EXISTING 642" DUCT
---	EXISTING 648" DUCT
---	EXISTING 654" DUCT
---	EXISTING 660" DUCT
---	EXISTING 666" DUCT
---	EXISTING 672" DUCT
---	EXISTING 678" DUCT
---	EXISTING 684" DUCT
---	EXISTING 690" DUCT
---	EXISTING 696" DUCT
---	EXISTING 702" DUCT
---	EXISTING 708" DUCT
---	EXISTING 714" DUCT
---	EXISTING 720" DUCT
---	EXISTING 726" DUCT
---	EXISTING 732" DUCT
---	EXISTING 738" DUCT
---	EXISTING 744" DUCT
---	EXISTING 750" DUCT
---	EXISTING 756" DUCT
---	EXISTING 762" DUCT
---	EXISTING 768" DUCT
---	EXISTING 774" DUCT
---	EXISTING 780" DUCT
---	EXISTING 786" DUCT
---	EXISTING 792" DUCT
---	EXISTING 798" DUCT
---	EXISTING 804" DUCT
---	EXISTING 810" DUCT
---	EXISTING 816" DUCT
---	EXISTING 822" DUCT
---	EXISTING 828" DUCT
---	EXISTING 834" DUCT
---	EXISTING 840" DUCT
---	EXISTING 846" DUCT
---	EXISTING 852" DUCT
---	EXISTING 858" DUCT
---	EXISTING 864" DUCT
---	EXISTING 870" DUCT
---	EXISTING 876" DUCT
---	EXISTING 882" DUCT
---	EXISTING 888" DUCT
---	EXISTING 894" DUCT
---	EXISTING 900" DUCT
---	EXISTING 906" DUCT
---	EXISTING 912" DUCT
---	EXISTING 918" DUCT
---	EXISTING 924" DUCT
---	EXISTING 930" DUCT
---	EXISTING 936" DUCT
---	EXISTING 942" DUCT
---	EXISTING 948" DUCT
---	EXISTING 954" DUCT
---	EXISTING 960" DUCT
---	EXISTING 966" DUCT
---	EXISTING 972" DUCT
---	EXISTING 978" DUCT
---	EXISTING 984" DUCT
---	EXISTING 990" DUCT
---	EXISTING 996" DUCT
---	EXISTING 1002" DUCT
---	EXISTING 1008" DUCT
---	EXISTING 1014" DUCT
---	EXISTING 1020" DUCT
---	EXISTING 1026" DUCT
---	EXISTING 1032" DUCT
---	EXISTING 1038" DUCT
---	EXISTING 1044" DUCT
---	EXISTING 1050" DUCT
---	EXISTING 1056" DUCT
---	EXISTING 1062" DUCT
---	EXISTING 1068" DUCT
---	EXISTING 1074" DUCT
---	EXISTING 1080" DUCT
---	EXISTING 1086" DUCT
---	EXISTING 1092" DUCT
---	EXISTING 1098" DUCT
---	EXISTING 1104" DUCT
---	EXISTING 1110" DUCT
---	EXISTING 1116" DUCT
---	EXISTING 1122" DUCT
---	EXISTING 1128" DUCT
---	EXISTING 1134" DUCT
---	EXISTING 1140" DUCT
---	EXISTING 1146" DUCT
---	EXISTING 1152" DUCT
---	EXISTING 1158" DUCT
---	EXISTING 1164" DUCT
---	EXISTING 1170" DUCT
---	EXISTING 1176" DUCT
---	EXISTING 1182" DUCT
---	EXISTING 1188" DUCT
---	EXISTING 1194" DUCT
---	EXISTING 1200" DUCT
---	EXISTING 1206" DUCT
---	EXISTING 1212" DUCT
---	EXISTING 1218" DUCT
---	EXISTING 1224" DUCT
---	EXISTING 1230" DUCT
---	EXISTING 1236" DUCT
---	EXISTING 1242" DUCT
---	EXISTING 1248" DUCT
---	EXISTING 1254" DUCT
---	EXISTING 1260" DUCT
---	EXISTING 1266" DUCT
---	EXISTING 1272" DUCT
---	EXISTING 1278" DUCT
---	EXISTING 1284" DUCT
---	EXISTING 1290" DUCT
---	EXISTING 1296" DUCT
---	EXISTING 1302" DUCT
---	EXISTING 1308" DUCT
---	EXISTING 1314" DUCT
---	EXISTING 1320" DUCT
---	EXISTING 1326" DUCT
---	EXISTING 1332" DUCT
---	EXISTING 1338" DUCT
---	EXISTING 1344" DUCT
---	EXISTING 1350" DUCT
---	EXISTING 1356" DUCT
---	EXISTING 1362" DUCT
---	EXISTING 1368" DUCT
---	EXISTING 1374" DUCT
---	EXISTING 1380" DUCT
---	EXISTING 1386" DUCT
---	EXISTING 1392" DUCT
---	EXISTING 1398" DUCT
---	EXISTING 1404" DUCT
---	EXISTING 1410" DUCT
---	EXISTING 1416" DUCT
---	EXISTING 1422" DUCT
---	EXISTING 1428" DUCT
---	EXISTING 1434" DUCT
---	EXISTING 1440" DUCT
---	EXISTING 1446" DUCT
---	EXISTING 1452" DUCT
---	EXISTING 1458" DUCT
---	EXISTING 1464" DUCT
---	EXISTING 1470" DUCT
---	EXISTING 1476" DUCT
---	EXISTING 1482" DUCT
---	EXISTING 1488" DUCT
---	EXISTING 1494" DUCT
---	EXISTING 1500" DUCT



ATZEL, NASHER & ZIGLER, P.C.
 ENGINEERS - SURVEYORS - PLANNERS

332 North Main Street
 New City, New York 10956
 Tel: (845) 834-6694
 Fax: (845) 834-5843
 E-mail: info@atzy.com
 Web: www.atzy.com

ATZEL, NASHER & ZIGLER, P.C.
 N.Y.S. P.E. LIC. NO. 29098

ATZEL, NASHER & ZIGLER, P.C.
 N.Y.S. P.E. LIC. NO. 80228

REVISION	DATE	DESCRIPTION

ATZEL, NASHER & ZIGLER, P.C.
 ENGINEERS - SURVEYORS - PLANNERS

332 North Main Street
 New City, New York 10956
 Tel: (845) 834-6694
 Fax: (845) 834-5843
 E-mail: info@atzy.com
 Web: www.atzy.com

PROJECT: **MAHOPAC WELLS 1, 2 & 3**

TOWN OF CARMEL
 PUTNAM COUNTY, NEW YORK

FILE: **TEST HOLE LOCATION PLAN**

DESIGN BY: GS	CHECKED BY: BN
DATE: MARCH 21, 2023	SCALE: 1" = 30'
PROJECT NO: 4870	DRAWING NO: 1

Drainage Maps

MAHOPAC WELLS 1, 2, & 3

**TOWN OF CARMEL
PUTNAM COUNTY
NEW YORK**

DRAINAGE MAPS

BY

ATZL, NASHER & ZIGLER

ENGINEERS-SURVEYORS-PLANNERS

232 NORTH MAIN STREET

NEW CITY, NY 10956

TEL: (845) 634-4694

FAX: (845) 634-5543

E-MAIL: rnasher@anzny.com

OWNERS WITHIN 500 FEET:

TOWN OF CARMEL TAX MAP

75.16-1-1 GEORGE P. & TRACEY E. SALIANO
140 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-1-2 JOHN BATTISTA
157 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-1-3 JOHN BATTISTA
165 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

5.16-1-4 KAUNER BREVOUX LIVING TRUST
163 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-1-6 ZOLA V. MATAJO & MANUEL L. CHILLOGALLI
173 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-1-8 CHARLES MARINA INC
807 SOUTH LAKE ROAD
MAHOPAC, NY 10541

75.16-1-9 SOTEROS & RENE KAMOUSLIS
153 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-1-10 JAMES MCCABE
PO BOX 472
BALDWIN PLACE, NY 10555

75.16-1-15 BRUCE BRADSHAW
465 ROUTE 6
MAHOPAC, NY 10541

75.16-1-16 HELTOP MANOR REALTY CORP.
466 ROUTE 6
MAHOPAC, NY 10541

75.16-1-17 HELTOP MANOR REALTY CORP.
466 ROUTE 6
MAHOPAC, NY 10541

75.16-1-18 ACHELES DAVIES
441 ROUTE 6
MAHOPAC, NY 10541

75.16-1-19 FIVE PROPERTIES, LLC
44 BLOOMER ROAD
MAHOPAC, NY 10541

75.16-1-20 THOMAS & GENE SIMONE
150 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-1-21 THOMAS & GENE SIMONE
150 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-1-22 SCOTT NYGARD
427 ROUTE 6
MAHOPAC, NY 10541

75.16-1-23 SCOTT NYGARD
423 ROUTE 6
MAHOPAC, NY 10541

75.16-1-24 JACREY REALTY CORP.
421 ROUTE 6
MAHOPAC, NY 10541

75.16-1-27 NEIRA REAL ESTATE LLC
10 SOUTH WESSON LANE
MAHOPAC, NY 10541

75.16-1-28 BOUAMAL & ROZALIE FLIP
5 BATTISTA DRIVE
MAHOPAC, NY 10541

75.16-1-29 SANTA & ROBERT PORTINO
7 BATTISTA DRIVE
MAHOPAC, NY 10541

75.16-1-30 THOMAS SIMONE
150 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-1-41 ANTHONY & ROSE FABIANO
154 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-1-601 JOHN PARK
7 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-602 JORGE & RUFFINA TEJADA
190 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-1-59 PAUL & KELLY HARRIS
15 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-58 ERNESTO & GLOMERAN LOPEZ
21 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-57 AYANA MISHALES & ORAN NESEMET AYUSO
27 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-56 MARK & LUBANG WHITERS
31 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-55 JOSHUA & SAMANTHA MOSER
37 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-54 JAMES & PATRICIA MOONBAIN
41 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-50 LAWRENCE & KATHLEEN KEANE
51 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-49 CAROLEA PROSSA
55 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-48 TIMOTHY OREN & KELLY HORAN
51 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-47 LOUIS & LINDA DAUDIO
65 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-46 JOSEPH & ROSEANN BRUSSO
69 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-45 MICHAEL & MARIANNE VICALE
73 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-44 VINCENT & ANNAME VAGGIO
81 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-1-43 JAMES & CAROLINE COOKE
140 DANILA DRIVE
MAHOPAC, NY 10541

75.16-1-42 JACOB & TRACY POSNAK
137 DANILA DRIVE
MAHOPAC, NY 10541

75.16-1-41 MATTHEW & CAROLYN TURRONE
133 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-30 NORBERT VOGL
6 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-31 DONALD K. & MEGAN M. HARTNETT
12 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-32 TOWN OF CARMEL
60 MCALPIN AVENUE
MAHOPAC, NY 10541

75.16-2-33 DIANE ISSAH
22 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-34 HUNTER JAYON LLC
22 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-35 FRANK GIUNTI
30 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-36 WAYNE & SUSAN SPEAR
36 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-37 DOMENICK & LOUISE SACCHITELLO
44 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-38 FRANK & LISA DIAZDINO
45 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-39 JOHN & LINDA NAINNA
50 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-40 LINDA RODRIGUEZ & ERICA ACHELES DAVIES
58 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-41 KEVIN & MELBA DANRO
62 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-42 VALDOR KUNCA & BOHMIKA KUNCOVA
63 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-43 PAKOITA GEORGE BREVY TRUST
74 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-44 HERBERT F. JR. & JANE M. HILLERY
75 ASTOR DRIVE
MAHOPAC, NY 10541

75.16-2-45 JOHN & PHILLIP DIAPOLI
84 SOUTH WESSON LANE
MAHOPAC, NY 10541

75.16-2-46 BINNS FAMILY BREVY TRUST #1
5 SOUTH WESSON LANE
MAHOPAC, NY 10541

75.16-2-47 NICOLE STEIN & MICHAEL & BEALE
888 ROUTE 6
MAHOPAC, NY 10541

75.16-2-48 DAQ ROUTE SIX, LLC
PO BOX 838
MAHOPAC, NY 10541

75.16-2-49 ITALIAN AMERICAN CLUB INC
PO BOX 831
MAHOPAC, NY 10541

75.16-2-50 ADRIANA CERQUERIA
PO BOX 780
CRISTON FALLS, NY 10019

75.16-2-51 TINA MARE RAPISARDA
85 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-52 JAMES & ROBERTA PAGANO
89 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-53 MICHAEL HART & DIANA SMOTHER
93 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-54 ROBERT & LIANA GERTZER
97 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-55 EUGENIA GARCA
PO BOX 797
MAHOPAC, NY 10541

75.16-2-56 JOHN & DONNA BENVIN
102 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-57 RICHARD WELZ
117 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-58 KENNETH & ROSEMARY WALDRON
123 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-59 HIGH WEN & MELBA M. BERNAN
125 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-59 FARMER TRUST CRECITO
129 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-60 DEBOTHAL AYLA & DEBOTHAL WANDANA
11 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-61 RICHARD & DEBRA RUSSO
127 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-62 RON & DARLENE LOVE GAFNI
17 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-63 KEVIN & CATHLEEN BROWNE
21 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-64 MICHAEL & MARIONNE BRONINE
21 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-66 HYMAN REICHBACH REVOC TRUST
27 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-65 MARK & PATRIC LEFF
29 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-66 PATRICK M. & ALTHEA M. DALEY
31 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-29 JACK D. & ROBIN M. ZENCHOK
33 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-30 DOUGLAS J. & MAGALU C. HONEY
37 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-31 ARTHUR & MARIA L. CERBONE
39 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-32 TERENCE & KRISTEN WOCKE
41 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-33 JOSEPH & CAROLANN LACAPARRA
43 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-34 JENNIFER A. & ANDREW T. DWYER
44 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-35 ELVIS & APRIL J. LUMIC
42 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-36 SCOTT M. ORONN
40 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-37 JAMES CLIBERTI & VERONICA FANELLA
38 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-38 ANTHONY & ANGILO DEMATTEO
36 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-39 DAN & MARINA CHALENSKY
32 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-40 KENNETH L. & JANET SCHWIGLER
28 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-41 JEFFREY & ANTONIETTA WEDER
26 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-42 MATTHEW & SAMANTHA A. CLARK
24 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-43 DONNA ROSSOMANDO
18 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-44 ADAM & LAN PHAM
16 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-45 JOSEPH M. & MARLENE S. CAMARCO-VOGL
14 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-46 PETER J. & TERESA M. GORBULO
12 NOTTINGHAM WAY
MAHOPAC, NY 10541

75.16-2-47 JEFFREY A. & KATHLEEN A. TUTTLE
8 COVENTRY CIR
MAHOPAC, NY 10541

75.16-2-48 KEVIN & HIL & FAROORAH
13 COVENTRY CIR
MAHOPAC, NY 10541

75.16-2-49 BILL BENEILLO
15 COVENTRY CIR
MAHOPAC, NY 10541

75.16-2-50 DIABATISTA FAMILY TRUST
17 COVENTRY CIR
MAHOPAC, NY 10541

75.16-2-51 BARBARA O'BRIEN
19 COVENTRY CIR
MAHOPAC, NY 10541

75.16-2-52 CHARLES M. & PAMELA E. BLOEKER
21 COVENTRY CIR
MAHOPAC, NY 10541

75.16-2-53 DANIEL & JEAN MARIE SHERIDAN
23 COVENTRY CIR
MAHOPAC, NY 10541

75.16-2-54 KATHY SONENBERG
27 COVENTRY CIR
MAHOPAC, NY 10541

75.16-2-55 RY CONF-LINC CT
WEST BREST
ATIN AP CASTANO
2 SONDORV AVE
WHITE PLAINS, NY 10606

75.16-2-56 MARREE BUFTONE
34 COVENTRY CIR
MAHOPAC, NY 10541

75.16-2-57 JAMES & SANDRA MARINELLI
32 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-70 HUGH WEN & MELBA M. BERNAN
125 DANILA DRIVE
MAHOPAC, NY 10541

75.16-2-71 FARMER TRUST CRECITO
PO BOX 2749
ADDITION, NY 12501

75.16-2-72 VERNON NEW YORK INC
PO BOX 2749
ADDITION, NY 12501

75.16-2-73 KATHLEEN BARRETT
28 COVENTRY CIR
MAHOPAC, NY 10541

75.16-2-73 BUCKHOLLOW LLC 122
4 BAURELLEN COURT
MAHOPAC, NY 10541

75.16-2-74 WILLIAM & LOUISE DE GASPERI
112 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-2-75 JOHN LEMENS REVOCABLE TRUST
100 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-2-76 JOHN LEMENS REVOCABLE TRUST
30 OREST ROAD
MAHOPAC, NY 10541

75.16-2-77 JOHN LEMENS REVOCABLE TRUST
100 BUCKS HOLLOW ROAD
MAHOPAC, NY 10541

75.16-2-85 MICHAEL J. & EILEEN O'BRIEN
16 COVENTRY CIR
MAHOPAC, NY 10541

75.16-2-86 JOSEPH & EBORAH KRINOC
68 DANILA DRIVE
MAHOPAC, NY 10541

75.20-1-13 LINDA M. WRODE
44 BLOOMER ROAD
MAHOPAC, NY 10541

75.20-1-12 STEPHEN A. & MARY BETH WRABEL
50 BLOOMER ROAD
MAHOPAC, NY 10541

75.20-1-11 MAREE A. REZZO
54 BLOOMER ROAD
MAHOPAC, NY 10541

75.20-1-10 GILBERT & LUCAS BAKERSWILL
86 BLOOMER ROAD
MAHOPAC, NY 10541

75.20-1-9 JOSEPH C. & JOHN G. MAGNITTA
60 BLOOMER ROAD
MAHOPAC, NY 10541

75.20-1-8 GILBERT & LUCAS BAKERSWILL
86 BLOOMER ROAD
MAHOPAC, NY 10541

75.20-1-7 RICHARD & KATHLEEN DIRUSSO
71 DANILA DRIVE
MAHOPAC, NY 10541

75.20-1-6 MICHAEL & CATHERINE SCARABBA
2 CRECITO COURT
MAHOPAC, NY 10541

75.20-1-5 PAMEL & MAROLINA ZABA
6 CRECITO COURT
MAHOPAC, NY 10541

75.20-1-4 ZENOVEN PRNAS
PO BOX 312
BALDWIN PLACE, NY 10505

75.20-1-3 JESS V. DARA BERKOWITZ
10 CRECITO COURT
MAHOPAC, NY 10541

75.20-1-22 MILJANO LONGO
11 CRECITO COURT
MAHOPAC, NY 10541

75.20-1-21 GLEAD HILL CORP.
220 GLENBORO AVENUE
YONKERS, NY 10725

75.20-1-16 SUEZ WATER NEW YORK
PO BOX 7870
PHOENIX, AZ 85050

75.20-1-25 CRAIG H. & JENNIFER M. HETTINGER
112 DANILA DRIVE
MAHOPAC, NY 10541

75.20-1-24 JORGE & BERNARDO
116 DANILA DRIVE
MAHOPAC, NY 10541

75.20-1-23 DONALD & SALLY WESS
122 DANILA DRIVE
MAHOPAC, NY 10541

75.20-1-22 DEAN & MARTIN COYNE
126 DANILA DRIVE
MAHOPAC, NY 10541

75.20-1-21 PETER & VIBORE FELDOUN
150 DANILA DRIVE
MAHOPAC, NY 10541

75.20-1-20 MICHAEL & EUNICE LAMELLE
134 DANILA DRIVE
MAHOPAC, NY 10541


75.20-1-19 ALEJANDRO MERLINO
90 BLOOMER ROAD
MAHOPAC, NY 10541

75.20-1-18 STEPHEN MILLER
90 DANILA DRIVE
MAHOPAC, NY 10541

75.20-1-17 ANTHONY CHIACHI & ERN COYEN
PARENT ESTATE
PO BOX 398
MAHOPAC, NY 10541

75.20-1-16 MARETA T. & LEE M. DOBENS
109 DANILA DRIVE
MAHOPAC, NY 10541

LOCATION MAP
SCALE: 1"=500'



VICINITY MAP
SCALE: 1"=500'

TAX MAP REFERENCE:
TOWN OF CARMEL TAX MAP
SECTION 75.20, BLOCK 2, LOT 68
ADDRESS:
BUCKS HOLLOW ROAD
MAHOPAC, NY 10541
AREA:
53.362 ACRES
DATUM:
VERTICAL:
HORIZONTAL: NAD 1983, NEW YORK STATE
PLANE COORDINATE SYSTEM
EAST ZONE

SUBDIVISION REFERENCES:
"MAP OF HUNTERS' ROOF" FILED IN THE
PUTNAM COUNTY CLERK'S OFFICE ON
MARCH 28, 1988, AS MAP NO. 2298.

REVISION	DATE	DESCRIPTION
8	04-09-24	DRY POND & LIMIT OF DISTURBANCE
7	02-12-24	LIMIT OF DISTURBANCE PER TOWN ENGINEER
6	01-19-24	DRAINAGE REVISION PER BILLING LAYOUT
5	05-02-22	DRAINAGE REVISION PER INFILTRATION TEST
4	02-25-22	PER PLANNING BOARD 2-10-22
3	02-07-22	PER 2-3-22 EOB MEETING
2	01-25-22	PER PW MFG. 1-15-22, PER EOB & PW SUBMISSION
1	11-15-21	PER PW MFG. 9-22-21

ATZL, NASHER & ZIGLER P.C.
ENGINEERS-SURVEYORS-PLANNERS
232 North Main Street
New City, New York 10956
Tel: (845) 634-4544
Fax: (845) 834-5543
E-mail: info@amny.com
Web: www.ANZYG.com

PROJECT:
MAHOPAC WELLS 1, 2 & 3


TOWN OF CARMEL,
PUTNAM COUNTY, NEW YORK

TITLE:
LOCATION MAP

DRAWN BY: IS
DATE: AUGUST 27, 2021
PROJECT NO:
4870

CHECKED BY: JRA
SCALE: AS SHOWN
DRAWING NO:
LM






PLAN NOTES:

OWNER/APPLICANT: VEOLIA (FORMERLY SUEZ) WATER NEW YORK
 162 OLD MILL ROAD
 WEST HAVEN, NY 10994

- BOUNDARY AND SITE INFORMATION TAKEN FROM A SURVEY PREPARED BY ATZL, NASHER AND ZIGLER, P.C.
- THE SUBJECT PROPERTY IS NOT LOCATED WITHIN A 100 YEAR FLOOD ZONE AS SHOWN ON FLOOD INSURANCE RATE MAP NUMBER 3607900226 DATED 3/4/2013.
- TOPOGRAPHY ELEVATIONS SHOWN ARE GENERALLY IN ACCORDANCE WITH NAD 1983 AND NAVD 1988 DATUM.

SITE ADDRESS: BUCKS HOLLOW ROAD
 MAHOPAC, NY 10541

- EXISTING USE: COMMERCIAL WATER SUPPLY
- ALL UTILITIES ARE ABOVE GRADE.
- PROPOSED LANDSCAPING IS TO CONFORM TO §142 OF TOWN CODE.
- WETLANDS AS FLAGGED BY STEVE SMITH AND CLAYTON FREY ON APRIL 22, 2021.
- THE WHITE TRAILER (THE "TREATMENT TRAILER") WILL BE REMOVED WITHIN 20 DAYS AFTER CONSTRUCTION OF THE GAC TREATMENT BUILDING IS COMPLETE.
- IN ITS ATTEMPTS TO MEET NEW YORK STATE DEPARTMENT OF HEALTH REGULATIONS MORE QUICKLY, VEOLIA ORDERED THE BUILDING IN THE GREEN COLOR PREVIOUSLY FOUND PROVISIONALLY ACCEPTABLE TO (BUT NOT FINALLY APPROVED BY) THE PLANNING BOARD. THE HIGH PRESTERS THE COLOR FAIRVIEW TAUPE (BENJAMIN MOORE, HC-85). IF THIS COLOR IS ACCEPTABLE TO AND APPROVED BY THE PLANNING BOARD, VEOLIA WILL PAINT THE GAC TREATMENT BUILDING AND EXISTING PUMP HOUSE FAIRVIEW TAUPE (BENJAMIN MOORE, HC-85) WITHIN THREE MONTHS OF THE FINAL LANDSCAPING INSTALLATION.



DISTRICT REGULATIONS:

ZONE "C"	DISTRICT "C1"	REQUIRED	EXISTING	PROPOSED
MINIMUM LOT AREA		120,000 SQ. FT.	172,135 SQ. FT.	172,135 SQ. FT.
MINIMUM LOT WIDTH		200 FT.	570A FT.	570A FT.
MINIMUM STREET FRONTAGE (ON TOWN ROAD)		100 FT.	580B FT.	580B FT.
MINIMUM STREET FRONTAGE (ON OUL-DE-SAC)		50 FT.	N/A	N/A
MINIMUM FRONT YARD		40 FT.	1380A FT.	1484A FT.
MINIMUM SIDE YARD		25 FT.	95 FT.	192 FT.
MINIMUM TOTAL SIDE YARD		50 FT.	787 FT.	782 FT.
MINIMUM REAR YARD		40 FT.	308 FT.	289 FT.
MAXIMUM BUILDING HEIGHT		12 FT.	35 FT.	23 FT.
MAXIMUM LOT COVERAGE		0.15	0.0002	0.0000
MINIMUM LANDSCAPE BUFFER		10 FT.	0 FT.	0 FT.

NET LOT AREA CALCULATION:
 GROSS LOT AREA = 2,325,300 SQ. FT.
 LESS AREA OF WETLANDS = 1,933,185 SQ. FT.
 NET LOT AREA = 392,115 SQ. FT.

NET LOT AREA CALCULATION:
 GROSS LOT AREA = 2,325,300 SQ. FT.
 LESS AREA OF WETLANDS = 1,933,185 SQ. FT.
 NET LOT AREA = 392,115 SQ. FT.

NET LOT AREA CALCULATION:
 GROSS LOT AREA = 2,325,300 SQ. FT.
 LESS AREA OF WETLANDS = 1,933,185 SQ. FT.
 NET LOT AREA = 392,115 SQ. FT.

FLOOD HAZARD:
 THE SURVEYED LOT IS SITUATED IN "AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN" AS DESIGNATED BY FEMA, PER FIRM MAP NO. 3607900226, WITH AN EFFECTIVE DATE OF MARCH 4, 2013.

NOTE:
 UTILITY LOCATIONS ARE BASED ON ABOVE-GROUND OBSERVATIONS & UTILITY MARKOUTS AT TIME OF FIELD SURVEY. THE TYPE AND LOCATION OF UTILITIES ARE NOT GUARANTEED TO BE ACCURATE OR ALL-INCLUSIVE.

SUBDIVISION REFERENCES:
 "MAP OF HUNTERS' RUN" FILED IN THE PUTNAM COUNTY CLERK'S OFFICE ON MARCH 25, 1988, AS MAP NO. 2296.

LEGEND

- EXISTING 2' CONTOUR
- EXISTING 5' CONTOUR
- EXISTING NATURAL
- EXISTING FINE INWANT
- EXISTING GAS LINE
- EXISTING CATCH BASIN
- EXISTING STORM DRAIN LINE
- EXISTING SEWER MANHOLE
- EXISTING SEWER LINE
- EXISTING SPOT ELEVATION
- EXISTING STORMWALL
- EXISTING CHAIN LINK FENCE
- EXISTING TELECOMMUNICATION LINE
- EXISTING ELECTRIC LINE
- EXISTING WETLAND BUFFER
- EXISTING WETLANDS
- EXISTING SOIL
- EXISTING LIGHT POLE
- EXISTING UTILITY POLE
- EXISTING WATER VALVE
- EXISTING GAS VALVE
- PROPOSED DATE
- PROPOSED WATER SERVICE
- PROPOSED UNDERGROUND ELECTRIC
- PROPOSED ROOF DRAIN
- PROPOSED STORM DRAIN
- PROPOSED SLT FENCE
- PROPOSED CONSTRUCTION FENCE
- PROPOSED KYLE GARDEN PROSECTOR
- PROPOSED KYLE GARDEN PROSECTOR
- TEST HOLE LOCATION

TAX MAP REFERENCE:
 TOWN OF CARMEL, TAX MAP SECTION 75.20, BLOCK 2, LOT 68

ADDRESS:
 BUCKS HOLLOW ROAD
 MAHOPAC, NY 10541

AREAS:
 53,382 ACRES

DATUM:
 VERTICAL: NAVD 1988
 HORIZONTAL: NAD 1983, NEW YORK STATE PLANE COORDINATE SYSTEM, EAST ZONE

WETLANDS (PFO)

THE EDUCATION LAW OF THE STATE OF NEW YORK PROVIDES THAT NO PERSON SHALL BE FINED OR PROSECUTED FOR VIOLATING ANY PROVISION OF THIS EDUCATION LAW UNLESS HE OR SHE HAS BEEN ADVISED BY A SIGNIFICANT OFFICIAL OF THE STATE DEPARTMENT OF EDUCATION OF THE NATURE AND CONSEQUENCES OF SUCH VIOLATION. WHERE SUCH ALTERNATIVE REMEDY IS AVAILABLE, THE STATE DEPARTMENT OF EDUCATION SHALL NOT PROSECUTE OR FINES ANY INDIVIDUAL, CORPORATION OR ENTITY FOR VIOLATING ANY PROVISION OF THIS EDUCATION LAW SECTION 7009(2)

DRAWING LIST:

No.	TITLE	ORIGIN DATE	REVISION
1	SITE PLAN	AUGUST 27, 2021	APRIL 09, 2024
2	OWNER LIST	AUGUST 27, 2021	APRIL 09, 2024
3	EXISTING CONDITION	AUGUST 27, 2021	APRIL 09, 2024
4	DRAINAGE PLAN	AUGUST 27, 2021	APRIL 09, 2024
5	DETAILS	AUGUST 27, 2021	APRIL 09, 2024
6	EROSION & SEDIMENT CONTROL PLAN	AUGUST 27, 2021	APRIL 09, 2024
7	TREE & LANDSCAPE PLAN	AUGUST 27, 2021	APRIL 09, 2024
8	LIGHTING PLAN	AUGUST 27, 2021	APRIL 09, 2024
9	TURNING RADIUS MANEUVERABILITY PLAN	NOVEMBER 15, 2021	APRIL 09, 2024

8	04-09-24	DRY POND & LIMIT OF DISTURBANCE
7	02-10-24	LIMIT OF DISTURBANCE PER TOWN ENGINEER
6	01-19-24	DRAINAGE REVISION PER BUILDING LAYOUT
5	06-02-22	DRAINAGE REVISION PER INFILTRATION TEST
4	02-25-22	PER PLANNING BOARD 2-15-22
3	02-07-22	PER 2-3-22 ECB MEETING
2	01-25-22	PER PW MTS. 1-13-22, PER ECB & PW SUBMISSION
1	11-15-21	PER PW MTS. 9-22-21

ATZL, NASHER & ZIGLER P.C.
 ENGINEERS-SEVERE/PLANNERS
 232 North Main Street
 New City, New York 10966
 Tel: (845) 634-4694
 Fax: (845) 634-5543
 E-mail: info@anzny.com
 Web: www.anzny.com


PROJECT:
 MAHOPAC WELLS 1, 2 & 3

**TOWN OF CARMEL
 PUTNAM COUNTY, NEW YORK**

OVERALL SITE PLAN

TITLE:
 OVERALL SITE PLAN


DRAWN BY: JSI **CHECKED BY:** JJA
DATE: AUGUST 27, 2021 **SCALE:** 1" = 100' FT.
PROJECT NO.: 4870 **DRAWING NO.:** 1



LEGEND

- EXISTING 1" CONTOUR
- EXISTING 2" CONTOUR
- EXISTING WATERLINE
- EXISTING FIRE HYDRANT
- EXISTING GAS LINE
- EXISTING CATCH BASIN
- EXISTING STORM DRAIN LINE
- EXISTING SEWER MANHOLE
- EXISTING SEWER LINE
- EXISTING SPOT ELEVATION
- EXISTING STORMWALL
- EXISTING CHAIN LINK FENCE
- EXISTING OVERHEAD WIRES
- EXISTING TELECOMMUNICATION LINE
- EXISTING ELECTRIC LINE
- EXISTING SIGN
- EXISTING LIGHT POLE
- EXISTING UTILITY POLE
- EXISTING WATER VALVE
- EXISTING GAS VALVE
- HYBRID WETLAND BUFFER
- EXISTING ELECTRIC LINE

WETLANDS (PFO)



EXISTING CONDITION DETAIL
SCALE: 1" = 50'

8	04-09-24	DRY POND & LIMIT OF DISTURBANCE
7	02-12-24	LIMIT OF DISTURBANCE PER TOWN ENGINEER
6	01-19-24	DRAINAGE REVISION PER BUILDING LAYOUT
5	06-02-22	DRAINAGE REVISION PER INFILTRATION TEST
4	02-25-22	PER PLANNING BOARD 2-15-22
3	02-07-22	PER 2-3-22 ECB MEETING
2	01-25-22	PER PW MTS. 1-13-22, PER ECB & PW SUBMISSION
1	11-15-21	PER PW MTS. 9-22-21
REVISION	DATE	DESCRIPTION

ATZEL, NASHER & ZIGLER P.C.
ENGINEERS-SEWER/DRY-PLANNERS
232 North Main Street
New City, New York 10966
Tel: (845) 634-4694
Fax: (845) 634-5543
E-mail: info@anzny.com
Web: www.anzny.com


PROJECT: **MAHOPAC WELLS 1, 2 & 3**

TOWN OF CARMEL
PUTNAM COUNTY, NEW YORK

TITLE: **EXISTING CONDITION**

DRAWN BY: IS	CHECKED BY: JRA
DATE: AUGUST 27, 2021	SCALE: 1" = 100 FT.
PROJECT NO: 4870	DRAWING NO: 3


UNAUTHORIZED ALTERATIONS OR ADDITIONS TO A SEWER LINE BEARING A LICENSED LAND SURVEYOR'S SEAL OR THE SIGNATURE OF THE SURVEYOR VIOLATE SECTION 20-B OF THE EDUCATION LAW OF THE STATE OF NEW YORK. ANY PERSON WHO VIOLATES THIS SECTION SHALL BE CONSIDERED TO BE IN VIOLATION OF SECTION 20-B OF THE EDUCATION LAW OF THE STATE OF NEW YORK. THE SURVEYOR HAS REVIEWED THE DRAWING OF THIS PROJECT AND HAS FOUND IT TO BE IN ACCORDANCE WITH THE EDUCATION LAW OF THE STATE OF NEW YORK. THE SURVEYOR HAS REVIEWED THE DRAWING OF THIS PROJECT AND HAS FOUND IT TO BE IN ACCORDANCE WITH THE EDUCATION LAW OF THE STATE OF NEW YORK. THE SURVEYOR HAS REVIEWED THE DRAWING OF THIS PROJECT AND HAS FOUND IT TO BE IN ACCORDANCE WITH THE EDUCATION LAW OF THE STATE OF NEW YORK.




CANTILEVER CONCRETE RETAINING WALL DETAIL
SCALE: 1"=1'-0"

CONCRETE


1. ALL CONCRETE WORK (BOTH MATERIALS AND CONSTRUCTION PROCEDURES) SHALL BE IN ACCORDANCE WITH ACI STANDARD 318.
2. CONCRETE SHALL BE CAPABLE OF DEVELOPING A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI AT 28 DAYS.
3. REINFORCING BARS SHALL BE DEFORMED BILLET STEEL BARS IN ACCORDANCE WITH ASTM A615, GRADE 60. ALL DETAILING OF REINFORCING SHALL BE IN ACCORDANCE WITH ACI STANDARD 315.
4. CALCIUM CHLORIDE OR SOLUTIONS CONTAINING CHLORIDE WILL NOT BE PERMITTED AS ADMIXTURES IN ANY CONCRETE.
5. CONCRETE PROTECTION FOR REINFORCING STEEL SHALL BE AS FOLLOWS: SLABS: 3/4" BEAMS & COLUMNS (EDGEWAYS): 1.5" INSIDE FACE OF WALLS: 1" CONCRETE POURED ON GROUND: 3" EXTERIOR FACE OF WALLS (AGAINST EARTH) 2".




P-DRY POND FLOOR TILE DRAIN DETAIL
N.T.S.




DRY POND PLAN VIEW
SCALE: 1"=20"



SECTION A-A
SCALE: 1"=5"




TYP. RISER WITH DOMED GRATE DETAIL
N.T.S.



STONE OUTLET DETAIL
N.T.S.

OUTLET ID.	DIAM.	DEPTH	A	B	C	D	H
#	6"	6"	3"	3"	3"	3"	12"
#	4"	4"	3"	3"	3"	3"	12"



PROPOSED DRY POND PROFILE
SCALE: 1"=5"

UNAUTHORIZED ALTERATIONS OR ADDITIONS TO A SHEET ARE BEING A VIOLATION OF THE PROFESSIONAL SEAL & REGULATION OF THE STATE ENGINEERS PLANNERS

THE EDUCATION LAW OF THE STATE OF NEW YORK PROHIBITS ANY PERSON ATTEMPTING ANYTHING ON THESE DRAWINGS AND/OR THE ACCOMPANYING SPECIFICATIONS UNLESS IT IS UNDER THE SUPERVISION OF A LICENSED PROFESSIONAL ENGINEER OR ARCHITECT. WHERE SUCH ALTERATIONS ARE MADE, THE PROFESSIONAL ENGINEER OR ARCHITECT, DATE OF SIGNATURE THEREON SHALL BE DEEMED TO BE ALTERING THE FULL LETTER OF THE ALTERATION ON THE DRAWING AND/OR IN THE SPECIFICATIONS OVER EDUCATION LAW SECTION 7209(2)




REVISION	DATE	DESCRIPTION
8	04-09-24	DRY POND & LIMIT OF DISTURBANCE
7	02-12-24	LIMIT OF DISTURBANCE PER TOWN ENGINEER
6	01-19-24	DRAINAGE REVISION PER BUILDING LAYOUT
5	06-02-22	DRAINAGE REVISION PER INFILTRATION TEST
4	02-25-22	PIER PLANNING BOARD 2-10-22
3	02-07-22	PER 2-3-22 ECB MEETING
2	01-25-22	PER PW MTS. 1-13-22, PER ECB & PW SUBMISSION
1	11-15-21	PER PW MTS. 9-22-21

ATZL, NASHER & ZIGLER P.C.
ENGINEERS-SEEVERSON-PLANNERS
232 North Main Street
New City, New York 10966
Tel: (845) 634-4694
Fax: (845) 634-4543
E-mail: info@anzny.com
Web: www.ANZNY.com

PROJECT: **MAHOPAC WELLS 1, 2 & 3**
TOWN OF CARMEL
PUTNAM COUNTY, NEW YORK

TITLE: **DETAILS**
DRAWN BY: IS
CHECKED BY: JSA
DATE: AUGUST 27, 2021
SCALE: AS SHOWN
PROJECT NO: 4870
DRAWING NO: 5




LEGEND

- EXISTING 2' CONTOUR
- EXISTING 10' CONTOUR
- EXISTING WATERLINE
- EXISTING FIRE HYDRANT
- EXISTING GAS LINE
- EXISTING CATCH BASIN
- EXISTING STORM DRAIN LINE
- EXISTING SEWER MANHOLE
- EXISTING SEWER LINE
- EXISTING SPOT ELEVATION
- EXISTING STONEWALL
- EXISTING SHAW LOW FENCE
- EXISTING OVERHEAD WIRE
- EXISTING TELECOMMUNICATION LINE
- EXISTING ELECTRIC LINE
- HYBRID WELAND BUFFER
- EXISTING WELANDS
- EXISTING SIGN
- EXISTING LIGHT POLE
- EXISTING UTILITY POLE
- EXISTING WATER VALVE
- EXISTING GAS VALVE
- PROPOSED GAS VALVE
- PROPOSED WATER SERVICE
- PROPOSED UNDERGROUND ELECTRIC
- PROPOSED CONTOURS
- PROPOSED ROOF DRAIN
- PROPOSED STORM DRAIN
- PROPOSED SILT FENCE
- PROPOSED CONSTRUCTION FENCE
- PROPOSED RAIN GARDEN PROTECTION
- PROPOSED LIMIT OF DISTURBANCE
- TEST HOLE LOCATION

SPILL CONTROL AND FUELING PLAN NOTES:

- FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION, FUELING AND CLEANUPS:
- FUELING SHALL BE PERFORMED OUTSIDE OF THE BUFFER AREA.
 - MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES.
 - MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREAS ON SITE. EQUIPMENT AND MATERIALS WILL INCLUDE, BUT NOT BE LIMITED TO, BROOMS, DUSTPANS, ROPS, RAGS, GLOVES, COOGLERS, MITY LITTER, SAND, SAWDUST, AND PLASTIC AND METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE.
 - ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY.
 - THE SPILL AREA WILL BE KEPT WELL VENTILATED, AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH HAZARDOUS SUBSTANCES.
 - SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF THE SIZE OF THE SPILL. THE SPILL CONTROL & PREVENTION LOG FORM PROVIDED IN APPENDIX C SHOULD BE USED FOR THIS PURPOSE.
 - THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT A RECURRING TYPE OF SPILL FROM REOCCURRING AND HOW TO CLEAN UP THE SPILL IF IT DOES REOCCUR. A DESCRIPTION OF THE SPILL MUST CAUSE TO AND THE CLEANUP MEASURES WILL ALSO BE INCLUDED.
 - THE JOB SUPERVISOR RESPONSIBLE FOR DAILY SITE OPERATIONS WILL BE DESIGNATED AS THE SPILL PREVENTION AND CLEANUP COORDINATOR. HE WILL DESIGNATE AT LEAST THREE OTHER SITE PERSONNEL WHO WILL RECEIVE SPILL PREVENTION AND CLEANUP TRAINING. THESE INDIVIDUALS WILL EACH BECOME RESPONSIBLE FOR A PARTICULAR PHASE OF PREVENTION AND CLEANUP. THE NAMES OF THE RESPONSIBLE SPILL PERSONNEL WILL BE POSTED IN THE MATERIAL STORAGE AREA AND IN THE OFFICE TRAILER ON SITE.



TEMPORARY WETLAND MITIGATION NOTE:


- SINCE WETLAND AREAS ARE TEMPORARILY DISTURBED, STOCKPILE WETLAND TOPSOIL AND REPLACE TO THE ORIGINAL GRADE AFTER GRADING IS COMPLETED. APPLY ERLENK-100 (OR SIMILAR) AT A RATE OF 8 POUNDS/1000SQ. APPLY CLEAN STRAW AS A MULCH AT THE RATE OF 3T/ACRE AND WITHOUT BLENDING. NO SOIL AMENDMENTS SHOULD BE USED ON WETLAND AREAS. COMPLETION OF THIS APPROACH WILL ACCOMPLISH 1:1 RESTORATION OF TEMPORARY WETLAND DISTURBANCE.

EROSION & SEDIMENT CONTROL PLAN NOTES:


- TOWN OF CARMEL WETLAND INSPECTOR WILL BE NOTIFIED FOR INSPECTION OF SILT FENCE FIRE AND POST CONSTRUCTION.
- ANY FILL REQUIRED WILL BE CERTIFIED PER HYSDIC REGULATIONS.
- NO FUELING, CONSTRUCTION OR STAGING OF CONSTRUCTION EQUIPMENT WILL OCCUR ON WETLANDS.

CONSTRUCTION NOTES FOR PRE FABRICATED SILT FENCE


- WHEN TWO SECTIONS OF FLEXER CLOTH (AQUO DASH) OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FUSED.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL DROPPED WHEN TRUCKS DEVELOP IN THE SILT FENCE.




CONSTRUCTION ENTRANCE DETAIL #1
N.T.S.
TO BE PLACED ALONG LIMIT OF DISTURBANCE
72" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.
34" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.




CONCRETE WASHOUT DETAIL #3
N.T.S.




EQUIPMENT STORAGE DETAIL
N.T.S.



CONCRETE WASHOUT DETAIL #3
N.T.S.




EQUIPMENT STORAGE DETAIL
N.T.S.



CONSTRUCTION NOTES FOR PRE FABRICATED SILT FENCE

- WHEN TWO SECTIONS OF FLEXER CLOTH (AQUO DASH) OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FUSED.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL DROPPED WHEN TRUCKS DEVELOP IN THE SILT FENCE.



CONSTRUCTION ENTRANCE DETAIL #1
N.T.S.
TO BE PLACED ALONG LIMIT OF DISTURBANCE
72" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.
34" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.

CONSTRUCTION NOTES FOR PRE FABRICATED SILT FENCE

- WHEN TWO SECTIONS OF FLEXER CLOTH (AQUO DASH) OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FUSED.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL DROPPED WHEN TRUCKS DEVELOP IN THE SILT FENCE.



CONSTRUCTION ENTRANCE DETAIL #1
N.T.S.
TO BE PLACED ALONG LIMIT OF DISTURBANCE
72" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.
34" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.

CONSTRUCTION NOTES FOR PRE FABRICATED SILT FENCE

- WHEN TWO SECTIONS OF FLEXER CLOTH (AQUO DASH) OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FUSED.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL DROPPED WHEN TRUCKS DEVELOP IN THE SILT FENCE.



CONSTRUCTION ENTRANCE DETAIL #1
N.T.S.
TO BE PLACED ALONG LIMIT OF DISTURBANCE
72" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.
34" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.

CONSTRUCTION NOTES FOR PRE FABRICATED SILT FENCE


- WHEN TWO SECTIONS OF FLEXER CLOTH (AQUO DASH) OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FUSED.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL DROPPED WHEN TRUCKS DEVELOP IN THE SILT FENCE.



CONSTRUCTION ENTRANCE DETAIL #1
N.T.S.
TO BE PLACED ALONG LIMIT OF DISTURBANCE
72" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.
34" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.

CONSTRUCTION NOTES FOR PRE FABRICATED SILT FENCE

- WHEN TWO SECTIONS OF FLEXER CLOTH (AQUO DASH) OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FUSED.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL DROPPED WHEN TRUCKS DEVELOP IN THE SILT FENCE.



CONSTRUCTION ENTRANCE DETAIL #1
N.T.S.
TO BE PLACED ALONG LIMIT OF DISTURBANCE
72" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.
34" MIN. FENCE POSTS, SPACING 10' MAX. C. TO C.

NO.	DATE	DESCRIPTION
8	04-09-24	DRY POND & LIMIT OF DISTURBANCE
7	02-12-24	LIMIT OF DISTURBANCE PER TOWN ENGINEER
6	01-19-24	DRAINAGE REVISION PER BUILDING LAYOUT
5	06-02-22	DRAINAGE REVISION PER INFILTRATION TEST
4	02-25-22	PER PLANNING BOARD 2-15-22
3	02-07-22	PER 2-3-22 EOB MEETING
2	01-25-22	PER PW MTS. 1-13-22, PER EOB & PW SUBMISSION
1	11-15-21	PER PW MTS. 9-22-21

ATZL, NASHER & ZIGLER P.C.
ENGINEERS-SEVERSIANS-PLANNERS
232 North Main Street
New City, New York 10966
Tel: (845) 634-4694
Fax: (845) 634-5563
E-mail: info@atzy.com
Web: www.ANZNY.com


MAHOPAC WELLS 1, 2 & 3

TOWN OF CARMEL
PUTNAM COUNTY, NEW YORK

EROSION & SEDIMENT CONTROL PLAN

DRAWN BY: IS	CHECKED BY: JKA
DATE: AUGUST 27, 2021	SCALE: 1" = 30' FT.
PROJECT NO: 4870	DRAWING NO: 6





PLANTING SPECIFICATIONS:
 GENERAL: ALL PLANTS, TREES, AND SHRUBS SHALL MEET THE SPECIFICATIONS FOR "PLANT MATERIAL" AS PER THE AMERICAN STANDARDS FOR NURSERY STOCK. THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO INSPECT ALL PLANTS PRIOR TO SHIPPING AND INSTALLATION. THERE ARE TO BE NO SUBSTITUTIONS OF THE PLANTS WITHOUT THE CONSENT OF THE LANDSCAPE ARCHITECT.
 PLANTING: ALL PLANTS SHALL BE PLANTED IN PITS TWO TIMES THE DIAMETER OF THE ROOT BALL OR CONTAINER. PLANT HEIGHT SHOULD BE PLACED AT OR SLIGHTLY ABOVE PREVIOUS GRADE. PULL BACK BURLAP FROM TOP OF BALL AND CUT WIRE ON TREE BACK. ENSURE THAT THE BURLAP IS NOT EXPOSED ABOVE GRADE BECAUSE OF WATER LOSS. STAKING AND GUYING SHALL BE USED ONLY WHEN NECESSARY. WHEN THE METHOD IS USED, CARE SHOULD BE TAKEN TO PROTECT THE TREE BARK AND WIRES SHOULD BE REMOVED AS SOON AS POSSIBLE.
 MULCHING: ALL PLANTING BEDS (EXCEPT GROUNDCOVER) SHALL BE MULCHED WITH THREE INCHES OF SHREDED BARK TO CONSERVE WATER AND KEEP ROOTS COVERED DURING INITIAL GROWTH STAGE. DO NOT PLACE MULCH HEAVILY AROUND CROWN OF PLANTS.
 WATER CARE: ALL TREES AND SHRUBS SHALL BE SPRAYED WITH AN ANTI-DESICCANT THE FIRST NOVEMBER AFTER PLANTING.
 WATERING: ALL PLANTS SHALL BE WATERED BY THE CONTRACTOR DURING THE INITIAL GROWTH STAGE. TREES SHALL BE HEAVILY WATERED SEVERAL TIMES DURING THE FIRST MONTH AFTER PLANTING AND THEN REGULARLY FOR THE NEXT TWO SUMMERS.
 PLANT GUARANTEE: CONTRACTOR SHALL GUARANTEE ALL NEWLY INSTALLED PLANTS FORTWO-YEAR PROVIDED THAT THEY ARE GIVEN PROPER WATERING/CARE AND CONTRACTOR IS NOTIFIED OF UNHEALTHY STRESSED PLANTS IMMEDIATELY. THE TWO YEAR GUARANTEE WILL START AT THE TIME OF THE ISSUANCE OF THE CERTIFICATE OF OCCUPANCY.


NOTE:
 VEOLIA WATER OF NEW YORK INC. ITS SUCCESSORS OR ASSIGNS WILL MAINTAIN THE PROPOSED LANDSCAPING AND TREES SHOWN ON SHEET 7 OF THE CURRENT SITE PLAN TITLED "TREE & LANDSCAPE PLAN" (TREE & LANDSCAPE PLAN) AND BEAR ALL EXPENSES IN CONNECTION THEREWITH.
 ANY TREE INSTALLED THAT DOES NOT SURVIVE OR IS IN AN UNHEALTHY CONDITION AT ANY TIME DURING THE FIRST TWO (2) YEARS FOLLOWING ITS PLANTING, SHALL BE REPLACED BY VEOLIA, ITS SUCCESSORS OR ASSIGNS, AT NO COST TO THE TOWN OF CARMEL.

TREE LEGEND



TREE LIST

NO.	SIZE	DESCRIPTION	COMMENTS	NO.	SIZE	DESCRIPTION	COMMENTS
41	9"	BIRCH	GOOD	2001	8"	MAPLE	GOOD
42	10"	POPLAR	GOOD	2002	14"	MAPLE	GOOD
54	12"	ASH	GOOD	2003	8"	BIRCH	GOOD
50	8"	QUAO BIRCH	GOOD	2004	10"	MAPLE	GOOD
56	8"	BIRCH	GOOD	2006	12"	TRIPLE BIRCH	GOOD
57	8"	TWIN BIRCH	GOOD	2006	8"	MAPLE	GOOD
58	11"	BIRCH	GOOD	2007	10"	MAPLE	GOOD
60	8"	BIRCH	GOOD	2008	8"	TWIN MAPLE	GOOD
60	7"	TWIN BIRCH	GOOD	2009	10"	MAPLE	GOOD
61	12"	ASH	GOOD	2010	10"	MAPLE	GOOD
62	8"	MAPLE	GOOD	2011	13"	TWIN MAPLE	POOR
63	8"	ELM	GOOD	2012	10"	ASH	GOOD
64	20"	OW	GOOD	2013	13"	TWIN MAPLE	GOOD
65	8"	BIRCH	GOOD	2014	10"	MAPLE	GOOD
66	8"	BIRCH	GOOD	2015	10"	MAPLE	GOOD
67	10"	ASH	GOOD	2016	10"	MAPLE	GOOD
68	10"	OW	GOOD	2017	14"	MAPLE	GOOD
69	10"	BIRCH	GOOD	2018	10"	TWIN MAPLE	GOOD
70	20"	BIRCH	GOOD	2019	8"	MAPLE	GOOD
71	10"	BIRCH	GOOD	2020	10"	TWIN MAPLE	GOOD
72	12"	BIRCH	GOOD	2021	13"	FENIA MAPLE	GOOD
73	6"	BIRCH	GOOD	2022	6"	MAPLE	GOOD
74	6"	MAPLE	GOOD	2022	7"	TWIN MAPLE	GOOD
75	12"	BIRCH	GOOD	2024	14"	MAPLE	GOOD
76	14"	OW	GOOD	2025	8"	MAPLE	GOOD
77	12"	BIRCH	GOOD	2028	24"	OW	GOOD
78	8"	BIRCH	GOOD	2022	8"	BIRCH	GOOD
81	8"	ASH	GOOD	2028	14"	TRIPLE MAPLE	GOOD
82	8"	BIRCH	GOOD	2030	7"	BIRCH	GOOD
84	10"	TWIN MAPLE	GOOD	2031	14"	BIRCH	GOOD
87	6"	ASH	GOOD	2032	6"	BIRCH	GOOD
88	8"	TRIPLE BIRCH	GOOD	2032	8"	MAPLE	GOOD
89	12"	BIRCH	GOOD	2034	8"	MAPLE	GOOD
91	14"	OW	GOOD	2036	13"	TWIN MAPLE	GOOD
93	7"	FINE	GOOD	2037	9"	MAPLE	POOR
94	7"	FINE	GOOD	2038	9"	BIRCH	GOOD
95	10"	FINE	GOOD	2040	14"	MAPLE	GOOD
96	8"	FINE	GOOD	2041	11"	MAPLE	GOOD
97	10"	FINE	GOOD	2044	13"	MAPLE	GOOD
98	10"	FINE	GOOD	2043	8"	MAPLE	POOR
99	11"	FINE	GOOD	2044	13"	MAPLE	GOOD
100	10"	FINE	GOOD	2045	7"	MAPLE	POOR
101	8"	FINE	GOOD	2046	13"	MAPLE	POOR
102	8"	POPLAR	POOR	2047	6"	TWIN MAPLE	POOR
103	8"	POPLAR	POOR	2048	13"	MAPLE	GOOD
104	12"	POPLAR	GOOD	2048	13"	MAPLE	GOOD
105	8"	TWIN BIRCH	GOOD	2050	11"	MAPLE	GOOD
106	11"	ASH	GOOD	2051	11"	MAPLE	GOOD
107	10"	ASH	GOOD	2052	8"	MAPLE	GOOD
108	11"	OW	GOOD	2053	10"	MAPLE	GOOD
109	18"	OW	GOOD	2054	6"	TWIN MAPLE	GOOD
110	10"	TWIN BIRCH	GOOD	2055	10"	MAPLE	GOOD
111	6"	BIRCH	GOOD	2056	6"	MAPLE	GOOD
112	10"	OW	GOOD	2057	10"	MAPLE	GOOD
113	6"	BIRCH	GOOD	2058	6"	MAPLE	POOR
114	8"	ASH	GOOD	2058	8"	LOUSET	POOR
115	10"	ASH	GOOD	2060	8"	LOUSET	POOR
116	24"	OW	GOOD	2060	8"	LINDEN	POOR
117	10"	MAPLE	GOOD	2062	12"	MAPLE	GOOD
118	14"	OW	GOOD	2061	24"	MAPLE	GOOD
119	9"	MAPLE	GOOD	2064	14"	MAPLE	GOOD
120	12"	MAPLE	GOOD	2065	10"	MAPLE	GOOD
121	8"	MAPLE	GOOD	2066	13"	MAPLE	GOOD
122	10"	MAPLE	GOOD	2067	10"	LOUSET	GOOD
123	8"	MAPLE	GOOD	2068	10"	MAPLE	GOOD
124	10"	MAPLE	GOOD	2068	10"	MAPLE	GOOD
125	12"	MAPLE	GOOD	2069	10"	LOUSET	GOOD
126	8"	BIRCH	GOOD	2068	7"	TWIN MAPLE	GOOD
127	8"	BIRCH	GOOD	2069	10"	MAPLE	GOOD
128	8"	BIRCH	GOOD	2070	10"	MAPLE	GOOD
129	8"	BIRCH	GOOD	2071	9"	TRIPLE MAPLE	GOOD
130	8"	MAPLE	GOOD	2072	6"	MAPLE	GOOD
131	8"	MAPLE	GOOD	2073	6"	BIRCH	GOOD
132	12"	TWIN MAPLE	GOOD	2074	9"	TWIN MAPLE	GOOD
133	8"	MAPLE	GOOD	2075	6"	BIRCH	POOR
134	14"	ASH	GOOD	2076	10"	MAPLE	POOR
135	10"	OW	GOOD	2076	10"	MAPLE	GOOD
136	10"	OW	GOOD	2077	11"	LOUSET	POOR
137	10"	ASH	GOOD	2077	11"	BIRCH	GOOD
138	10"	BIRCH	GOOD	2078	6"	MAPLE	GOOD
139	10"	BIRCH	GOOD	2079	8"	MAPLE	GOOD
140	10"	BIRCH	GOOD	2079	8"	MAPLE	GOOD
141	10"	MAPLE	GOOD	2080	10"	LOUSET	GOOD
142	10"	MAPLE	GOOD	2080	7"	MAPLE	GOOD
143	10"	MAPLE	GOOD	2081	10"	TRIPLE MAPLE	GOOD
144	10"	MAPLE	GOOD	2081	10"	LOUSET	GOOD
145	10"	MAPLE	GOOD	2082	10"	LOUSET	GOOD
146	10"	MAPLE	GOOD	2083	10"	LOUSET	GOOD
147	10"	MAPLE	GOOD	2084	10"	LOUSET	GOOD
148	10"	MAPLE	GOOD	2085	11"	ASH	GOOD
149	10"	MAPLE	GOOD	2086	11"	ASH	GOOD
150	10"	MAPLE	GOOD	2087	11"	ASH	GOOD
151	10"	MAPLE	GOOD	2088	7"	TWIN MAPLE	GOOD
152	10"	MAPLE	GOOD	2089	7"	MAPLE	GOOD
153	10"	MAPLE	GOOD	2090	7"	MAPLE	GOOD
154	10"	MAPLE	GOOD	2091	7"	MAPLE	GOOD
155	10"	MAPLE	GOOD	2092	7"	MAPLE	GOOD
156	10"	MAPLE	GOOD	2093	7"	MAPLE	GOOD
157	10"	MAPLE	GOOD	2094	7"	MAPLE	GOOD
158	10"	MAPLE	GOOD	2095	7"	MAPLE	GOOD
159	10"	MAPLE	GOOD	2096	7"	MAPLE	GOOD
160	10"	MAPLE	GOOD	2097	7"	MAPLE	GOOD
161	10"	MAPLE	GOOD	2098	7"	MAPLE	GOOD
162	10"	MAPLE	GOOD	2099	7"	MAPLE	GOOD
163	10"	MAPLE	GOOD	2100	6"	TWIN BIRCH	POOR
164	10"	MAPLE	GOOD	2101	11"	MAPLE	GOOD
165	10"	MAPLE	GOOD	2102	11"	TWIN MAPLE	GOOD
166	10"	MAPLE	GOOD	2103	7"	BIRCH	POOR
167	10"	MAPLE	GOOD	2104	7"	ASH	GOOD
168	10"	MAPLE	GOOD	2105	8"	MAPLE	GOOD
169	10"	MAPLE	GOOD	2106	8"	MAPLE	GOOD
170	10"	MAPLE	GOOD	2107	6"	MAPLE	GOOD
171	10"	MAPLE	GOOD	2108	6"	MAPLE	GOOD
172	10"	MAPLE	GOOD	2109	6"	MAPLE	GOOD
173	10"	MAPLE	GOOD	2110	6"	MAPLE	GOOD
174	10"	MAPLE	GOOD	2111	6"	MAPLE	GOOD
175	10"	MAPLE	GOOD	2112	6"	MAPLE	GOOD
176	10"	MAPLE	GOOD	2113	6"	MAPLE	GOOD
177	10"	MAPLE	GOOD	2114	6"	MAPLE	GOOD
178	10"	MAPLE	GOOD	2115	6"	MAPLE	GOOD
179	10"	MAPLE	GOOD	2116	6"	MAPLE	GOOD
180	10"	MAPLE	GOOD	2117	6"	MAPLE	GOOD
181	10"	MAPLE	GOOD	2118	6"	MAPLE	GOOD
182	10"	MAPLE	GOOD	2119	6"	MAPLE	GOOD
183	10"	MAPLE	GOOD	2120	6"	MAPLE	GOOD
184	10"	MAPLE	GOOD	2121	6"	MAPLE	GOOD
185	10"	MAPLE	GOOD	2122	6"	MAPLE	GOOD
186	10"	MAPLE	GOOD	2123	6"	MAPLE	GOOD
187	10"	MAPLE	GOOD	2124	6"	MAPLE	GOOD
188	10"	MAPLE	GOOD	2125	6"	MAPLE	GOOD
189	10"	MAPLE	GOOD	2126	6"	MAPLE	GOOD
190	10"	MAPLE	GOOD	2127	6"	MAPLE	GOOD
191	10"	MAPLE	GOOD	2128	6"	MAPLE	GOOD
192	10"	MAPLE	GOOD	2129	6"	MAPLE	GOOD
193	10"	MAPLE	GOOD	2130	6"	MAPLE	GOOD
194	10"	MAPLE	GOOD	2131	6"	MAPLE	GOOD
195	10"	MAPLE	GOOD	2132	6"	MAPLE	GOOD
196	10"	MAPLE	GOOD	2133	6"	MAPLE	GOOD
197	10"	MAPLE	GOOD	2134	6"	MAPLE	GOOD
198	10"	MAPLE	GOOD	2135	6"	MAPLE	GOOD
199	10"	MAPLE	GOOD	2136	6"	MAPLE	GOOD
200	10"	MAPLE	GOOD	2137	6"	MAPLE	GOOD
201	10"	MAPLE	GOOD	2138	6"	MAPLE	GOOD
202	10"	MAPLE	GOOD	2139	6"	MAPLE	GOOD
203	10"	MAPLE	GOOD	2140	6"	MAPLE	GOOD
204	10"	MAPLE	GOOD	2141	6"	MAPLE	GOOD
205	10"	MAPLE	GOOD	2142	6"	MAPLE	GOOD
206	10"	MAPLE	GOOD	2143	6"	MAPLE	GOOD
207	10"	MAPLE	GOOD	2144	6"	MAPLE	GOOD
208	10"	MAPLE	GOOD	2145	6"	MAPLE	GOOD
209	10"	MAPLE	GOOD	2146	6"	MAPLE	GOOD
210	10"	MAPLE	GOOD	2147	6"	MAPLE	GOOD
211	10"	MAPLE	GOOD	2148	6"	MAPLE	GOOD
212	10"	MAPLE	GOOD	2149	6"	MAPLE	GOOD
213	10"	MAPLE	GOOD	2150	6"	MAPLE	GOOD
214	10"	MAPLE	GOOD	2151	6"	MAPLE	GOOD
215	10"	MAPLE	GOOD	2152	6"	MAPLE	GOOD
216	10"	MAPLE	GOOD	2153	6"	MAPLE	GOOD
217	10"	MAPLE	GOOD	2154	6"	MAPLE	GOOD
218	10"	MAPLE	GOOD	2155	6"	MAPLE	GOOD
219	10"	MAPLE	GOOD	2156	6"	MAPLE	GOOD
220	10"	MAPLE	GOOD	2157	6"	MAPLE	GOOD
221	10"	MAPLE	GOOD	2158	6"	MAPLE	GOOD
222	10"	MAPLE	GOOD	2159	6"	MAPLE	GOOD
223	10"	MAPLE	GOOD	2160	6"	MAPLE	GOOD
224	10"	MAPLE	GOOD	2161	6"	MAPLE	GOOD
225	10"	MAPLE	GOOD	2162	6"	MAPLE	GOOD
226	10"	MAPLE	GOOD	2163	6"	MAPLE	GOOD
227	10"	MAPLE	GOOD	2164	6"	MAPLE	GOOD
228	10"	MAPLE	GOOD	2165	6"	MAPLE	GOOD
229	10"	MAPLE	GOOD	2166	6"	MAPLE	GOOD
230	10"	MAPLE	GOOD	2167	6"	MAPLE	GOOD
231	10"	MAPLE	GOOD	2168	6"	MAPLE	GOOD
232	10"	MAPLE	GOOD	2169	6"	MAPLE	GOOD
233	10"	MAPLE	GOOD	2170	6"	MAPLE	GOOD
234	10"	MAPLE	GOOD	2171	6"	MAPLE	GOOD
235	10"	MAPLE	GOOD	2172	6"	MAPLE	GOOD
236	10"	MAPLE	GOOD	2173	6"	MAPLE	GOOD
237	10"	MAPLE	GOOD	2174	6"	MAPLE	GOOD
238	10"	MAPLE	GOOD	2175	6"	MAPLE	GOOD
239	10"	MAPLE	GOOD	2176	6"	MAPLE	GOOD
240	10"	MAPLE	GOOD	2177	6"	MAPLE	GOOD
241	10"	MAPLE	GOOD	2178	6"	MAPLE	GOOD
242	10"	MAPLE	GOOD	2179	6"	MAPLE	GOOD
243	10"	MAPLE	GOOD	2180	6"	MAPLE	GOOD
244							



RAB CONTACT INFORMATION:
DANIEL SALES (732) 965-8806
RAB LIGHTING (201) 631-6062



12, 18 AND 24 WATT SLIM WALL MOUNTS ARE ULTRA EFFICIENT AND
DESIGN SPECIFIC LIGHT DISTRIBUTION WITH A COMPACT LOW PROFILE
DESIGN THAT'S SUPER EASY TO INSTALL AS A DOWNLIGHT OR UPLIGHT.

COLOR: BRONZE HEIGHT: 4.5 IN

SLIM12X WALL MOUNT DETAIL
N.T.S.

Luminaire Schedule	Symbol	Qty	Label	Arrangement	Total Lamp Lumens	LLF	Description	BUGD Rating
M.C.	2	SLIM12X	SINGLE	N.A.	N.A.	1,000	Wall Mount	EX-LVD-G3

NOTE:
ALL SITE LIGHTING WILL BE MOTION SENSOR

REVISION	DATE	DESCRIPTION
8	04-09-24	DRY POND & LIMIT OF DISTURBANCE
7	02-12-24	LIMIT OF DISTURBANCE PER TOWN ENGINEER
6	01-19-24	DRAINAGE REVISION PER BUILDING LAYOUT
5	06-02-22	DRAINAGE REVISION PER INFILTRATION TEST
4	02-25-22	PER PLANNING BOARD 2-10-22
3	02-07-22	PER 2-3-22 ECB MEETING
2	01-25-22	PER PW MTS. 1-13-22, PER ECB & PW SUBMISSION
1	11-15-21	PER PW MTS. 9-22-21


ATZL, NASHER & ZIGLER P.C.
ENGINEERS-SEVEREYB-PLANNERS
232 North Main Street
New City, New York 10956
Tel: (845) 634-4694
Fax: (845) 634-5543
E-mail: info@anzny.com
Web: www.ANZNY.com

PROJECT: **MAHOPAC WELLS 1, 2 & 3**


TOWN OF CARMEL
PUTNAM COUNTY, NEW YORK

TITLE: **LIGHTING PLAN**

DRAWN BY: IS	CHECKED BY: JRA
DATE: AUGUST 27, 2021	SCALE: 1" = 30' FT.
PROJECT NO: 4870	DRAWING NO: 8



THE EDUCATION LAW OF THE STATE OF NEW YORK
PROHIBITS ANY PERSON ALtering ANYTHING ON
THIS DRAWING AND/OR THE ACCOMPANYING
SPECIFICATIONS UNLESS IT IS UNDER THE SUPERVISION
OF A REGISTERED PROFESSIONAL ENGINEER OR ARCHITECT
WHERE SUCH ALTERATIONS ARE MADE, THE REGISTERED
PROFESSIONAL ENGINEER OR ARCHITECT SHALL BE
RESPONSIBLE THEREFOR. DATE OF ISSUE: 08/27/2021
ALTERATION ON THE DRAWING AND/OR IN THE
SPECIFICATIONS, UNLESS INDICATED BY A
REVISION OR SUBSEQUENT DRAWING.



8	04-09-24	DRY POND & LIMIT OF DISTURBANCE
7	02-12-24	LIMIT OF DISTURBANCE PER TOWN ENGINEER
6	01-19-24	DRAINAGE REVISION PER BUILDING LAYOUT
5	06-02-22	DRAINAGE REVISION PER INFILTRATION TEST
4	02-25-22	PER PLANING BOARD 2-15-22
3	02-07-22	PER 2-3-22 ECB MEETING
2	01-25-22	PER PH MTS. 1-13-22, PER ECB & PH SUBMISSION
1	11-15-21	PER PH MTS. 9-22-21
REVISION	DATE	DESCRIPTION

ATZL, NASHER & ZIGLER P.C.
 ENGINEERS-SEWER/DRY-PLANNERS
 232 North Main Street
 New City, New York 10956
 Tel: (845) 634-6694
 Fax: (845) 634-6543
 E-mail: info@anzny.com
 Web: www.ANZNY.com

PROJECT: **MAHOPAC WELLS 1, 2 & 3**

TOWN OF CARMEL
 PUTNAM COUNTY, NEW YORK

TITLE: **TURNING RADIUS
 MANEUVERABILITY PLAN**

DRAWN BY:	IS	CHECKED BY:	JRA
DATE:	NOVEMBER 15, 2021	SCALE:	1" = 20 FT.
PROJECT NO.:	4870	DRAWING NO.:	9

THE EDUCATION LAW OF THE STATE OF NEW YORK
 PROHIBITS ANY PERSON FROM ANYHOW OR
 IN ANY MANNER, INCLUDING BUT NOT LIMITED TO
 THESE DRAWINGS AND/OR THE ACCOMPANYING
 SPECIFICATIONS, UNLESS IT IS UNDER THE SUPERVISION
 AND CONTROL OF A REGISTERED PROFESSIONAL ENGINEER,
 ARCHITECT, LAND DEVELOPER, PLANNING PROFESSIONAL,
 OR PROFESSIONAL DESIGNER WHOSE NAME AND TITLE
 ARE SHOWN ON THESE DRAWINGS. ANY UNAUTHORIZED
 ALTERATION OF THE DRAWING AND/OR IN THE
 EXECUTION OF THE EDUCATION LAW SECTION 7209(2)

THIS DRAWING HAS BEEN PREPARED IN ACCORDANCE WITH THE EXISTING CODE OF PRACTICE FOR LAND DEVELOPERS GOVERNED BY THE OFFICE OF REGIONAL LAND DEVELOPMENT ASSOCIATION AND DEVELOPMENTAL PLANNING ASSOCIATION. ANY DEVIATION FROM THE ASSOCIATION'S STANDARDS SHALL BE THE RESPONSIBILITY OF THE INDIVIDUALS WHOSE NAMES ARE SHOWN ON THESE DRAWINGS. THE ASSOCIATION'S STANDARDS ARE NOT NECESSARILY APPLICABLE TO ALL PROJECTS AND ARE SUBJECT TO ADDITIONAL REGULATIONS, ORDINANCES AND/OR DECISIONS OF THE EDUCATION LAW SECTION 7209(2)

STATE OF NEW YORK
 SEAL OF THE STATE OF NEW YORK
 REGISTERED PROFESSIONAL ENGINEER
 CIVIL ENGINEERING
 NO. 12345
 EXPIRES 12/31/2028

STATE OF NEW YORK
 SEAL OF THE STATE OF NEW YORK
 REGISTERED PROFESSIONAL ENGINEER
 CIVIL ENGINEERING
 NO. 67890
 EXPIRES 12/31/2028

